MACHINERY

DECEMBER 13 1961

V.99 # 2561

What makes the...

a best seller?

* SEE PAGES 18 and 19!

flying scot
30"-36"-42"

KEARNEY & TRECKER-C.V.A LTD.

BIRMINGHAM GLASGOW MANCHESTER

The quick and simple modern way of grinding form tools, gauges, etc., with high accuracy



The PeTeWe Projection Form Grinding Machine is the answer to many of the problems of production associated with the grinding of complicated shapes and forms to high degrees of accuracy and in materials such as tungsten carbide. The drawing, the workpiece and the grinding wheel are all clearly visible on the same large size screen and control of the grinding operations is extremely simple. The PFS 3d machine illustrated grinds work up to 2in, thick or 4in, diameter.



are all on the same

PeTeWe

Projection Form Grinding Machine

Sales and Service for the British Isles

DRUMMOND-ASQUITH LIMITED


Member of the Asquith Machine Tool Corporation






REE'S HOW MEALD BOREMATICS

achieve **ACCURACY**



by dissipation of heat through cored passages whilst retaining heavily ribbed construction for work and fixture support.



NDLY ...

through positive table travel provided by special, distortion-free cylinder and piston mountings

ALSO BY USING ...

precision boring-head construction fully automatic lubrication constant feed throttling isolated hydraulic power unit.



You'll find IT PAYS to come to-



HEALD MACHINES LIMITED . BIRMINGHAM 24 . ENGLAND

Sales Representatives: ALFRED HERBERT LIMITED . COVENTRY



We reclaimed a whole batch of these rejects by 'Fescol'-ising

It can happen now and again, even in the best regulated machine shops—a faulty machine or small error in setting results in a completely unserviceable run of components on which expensive work has already been done. Fortunately, in many cases, these expensive parts can be reclaimed by 'Fescol'-ising. This process of heavy electro-chemical deposition builds up the components oversize. Accurate machining is then carried out. Fescol Limited undertake the whole job including deposition and the subsequent machining operation.

In the chemical, metallurgical, printing, textile and countless other fields, components can be 'Fescol'-ised with advantage. Outworn parts can be built up, and new ones given an added assurance of longer life. We can advise on any application. For further details and general facts about the process, please write, mentioning the fields in which you are interested, for publication... M26.



FESCOL LIMITED . NORTH ROAD . LONDON . N7

BRANCH WORKS AT PORT GLASGOW, HUDDERSFIELD AND BROWNHILLS, WALSALL





NEWALL LAPPING MACHINES

give precision, flatness & parallelism at high production rates

MODEL 10 U

Simple to operate yet producing components to close accuracy combined with high class finish, this machine has a capacity for flat work up to 3° square x 1½ thick and cylindrical work 3° long x 1½ diameter.

MODEL 2 F


Also a universal machine, model 2 F has a capacity of 8" square x 3" thick for flat work and 8" long x 3" diameter for cylindrical components.

RIGIDLAP

Latest model in the range the Rigidlap, an exceptionally sturdy machine, has contra-rotating lapping wheels and an extremely high output potential.

Maximum capacity for flat work 7 square x $1\frac{1}{2}$ thick and for cylindrical work 7 long x $2\frac{1}{2}$ diameter.

This machine is also offered with automatic work feed mechanism.



Our capping division will be pleased to advise you on production problems and will design workholders to suit your consponents.

Full details on request to:-

NEWALL GROUP SALES LIMITED

Telephone Peterborough 3227 PETERBOROUGH ENGLAND Cables "Precision" Peterborough

GET MORE FROM YOUR CARBIDE TOOLS

with this inexpensive, robustly built

UNION

LAPPING AND CHIPBREAKER
GRINDING MACHINE


Lapping carbide tools after grinding improves performance, prolongs re-grinding intervals and gives a superior finish to the turned part.

BRIEF SPECIFICATION:

4,800 r.p.m. spindle on opposed Timken bearings. Lapping speed 5,000 surface f.p.m. In-built coolant pump and tank. Fully adjustable table on ball bearing slideways. Supplied as bench or cabinet model



SEND FOR FULLY
ILLUSTRATED
LEAFLET — TODAY!



Literature available covers the Harrison range of Lathes from 9" to 17" swing: Milling, Drilling and Grinding Machines and Engineers Accessories.

above left
Table can be inclined
either way up to 20°.
Tool guide moves 90°
with accurately
graduated base.

Quick, accurate setting.

right

Vertical feed with adjustable micrometer dials.

T. S. HARRISON & SONS LIMITED . HECKMONDWIKE . YORKSHIRE

1961

ngs.

E



-but for fractional horse-power in industry...

wherever and whatever the duty, 'ENGLISH ELECTRIC' f.h.p. motors can be put to work with efficiency and economy. These sturdy motors are built to give good service under the most arduous conditions. The right f.h.p. motor for your job, from 1/20 h.p. upwards, is in the 'ENGLISH ELECTRIC' range.



'ENGLISH ELECTRIC'

f.h.p. motors

F.H.P. MOTORS DEPARTMENT, PHOENIX WORKS, BRADFORD The English Electric Company Limited, English Electric House, Strand, London, W.C.2.

When answering advertisements kindly mention MACHINERY.

SHP. 4

new SIP jig boring machine

specially designed for YOUR tool room and production shop

To meet the varied requirements of the engineering industry SIP have developed the new MP-5E jig boring machine.

Modern, robust, containing many advanced features, it makes SIP precision and enduring accuracy available at very low cost.

Incorporating the proven Double Column frame design, automatically corrected leadscrews, powerful Spindle Head containing SIP taper roller bearings, the MP-5E is a dependable and versatile machine, easy to operate, economical to maintain.


The SIP guaranteed accuracy for all displacements of Work Table and Spindle Head is 0.0002".

Specifications and full information available from

SOCIETE GENEVOISE LTD



961



NEWPORT PAGNELL BUCKS Telephone: Newport Pagnell 460/1/2

STRAIGHT - SIDED GRANK PRESSES

two points of application

The rigid and breakproof body of all steel construction connected by hot shrunk-in tierods

Pressure ratings from 160 to 2000 tons
H po-pneumatic die cushion in the

licator

f rotation

In frotation Li afety guard

Pl ermitting high frequency of

ageability of the



VEB PRESSEN-UND SCHERENBAU ERFURT

ERFURT

Representative: Thos. C. Wild Machinery Ltd. Languett Road Sheffield 6/England.



hmen fuer Werkzeugvaren Werkzeuge Berlin W8 German

1961

tons the

f all hot

uency

the

T

uguge nan





"It's really good if it's ACTARC!"

There's a good deal behind that easy approval of the man on the job. For instance ACTARC assures:-


The widest application know-how. Compact handy transformers. Dependable electrode quality. Laboratory advisory service. Quick delivery from large stocks.

A full range, fully approved.





ARC MANUFACTURING CO. LTD., Actarc Works, Nitshill, Glasgow, 8.W.3, Telephone: BARRHEAD 2293, Telegrams: ACTIVARC, GLASGOW



THE HEPWORTH IRON COMPANY (Engineering) LIMITED industrial hydraulic mechanisms

Haziehead Nr. Sheffield telephone Penistone 3342/3 telegrams Carlecotes, Penistone





NEW "5" SUPER CHUCK

555

AHA H

FASTER STRONGER MORE ACCURATE


Clark Son

Stype AUTOLOCK


CLARKSON (ENGINEERS) LIMITED KING EDWARD ROAD, NUNEATON WARWICKSHIRE BRANCHES AT LONDON, CROYDON, BARKING, ENFIELD, BIRMINGHAM, BELFAST, BRISTOL, COVENTRY, LEEDS, GLASGOW, HAYES, MANCHESTER, NEWCASTLE, WOLVZEHAMPTON

THE VICE

with all the virtues



OR THE TOOLROOM & PRODUCTION NO TRAPS FOR SWARF, LOW HEIGHT WITH RIGIT



Y SLIDES ADJUSTABLE FOR WEAR. LONG BEARING SURFACES. IMPOSSIBLE FOR THE JAW TO LIFT AND TILT THE JOB.

TOTALLY ENCLOSED SCREW
WHICH CANNOT BECOME SEIZED OR BRUISED.

SLIDING JAW MACHINED OVER ITS WHOLE SURFACE FOR THE USE OF THE SCRIBING BLOCK.

GROUND TOOL STEEL JAWS AND PHOSPHOR BRONZE NUT

ACCURATELY MACHINE DIVIDED SWIVEL BASES INDEXED FULLY THROUGH 360 .

ABWOOD Machine Vices are available in the following types: PLAIN, SWIYEL TYPE (illustrated), SHAPER, UNIVERSAL and UNIVERSAL COMPOUND ANGLE TABLES.

FOR THE TOOLROOM & PRODUCTION

ABWOOD MACHINE TOOLS LIMITED



I RIGII






COLD ROLLED STRIP STAINLESS STRIP
HIGH CARBON STRIP
HIGH STRAIN & SPECIAL QUALITY WIRES
ROUND & FLAT SECTION
STAINLESS WIRES BRIGHT BARS
DRAWN OR TURNED PRECISION GROUND

ARTHUR
Training State I wastes
A frequency State of the S

When answering advertisements kindly mention MACHINERY.



PNEUMATIC TOOLS

- 1. Diegrinders, 90,000 40,000, 22,000; 15,000 r.p.m.
- 2. Angle Grinders, for Fettling and Notching and rubber disc sanding.
- 3. Silent Drills from 400 to 18,000 r.p.m.
- 4. Nylon Blowguns almost indestructible.
- 5. Rust Brushes, 3,000 r.p.m. for Cup or Wheel Brushes.
- 6. Grinders—4,300 r.p.m. to 15,000.

Also—Hammers and Chisels, Bench Rammers, Surface Descalers, Air Vice with safety feature, Quick Action Plugs, Sockets, Hoses and all types of accessories.

Send for Catalogue ZAI

B. O. MORRIS LTD, Morrisflex Works, COVENTRY

London Birmingham Altrincham Glasgow Leeds Bristol Whitley Bay Sydney, Australia

FINE MACHINE TOOLS

CHAPPUIS Progressive Tool

Presses

BURKHARDT

& WEBER Multi-spindle Drilling

Machines

REINECKER Grindley Machine

OHANSSON

Production

for the United Kingsom

Universal Grinding Machines

加制


(STONEBRIDGE HIGHWAY, WILLENHALL, COVENTRY, ENGLA

608R Cogos

COMPLETE ELECTRO-HYDRAULIC SERVO SYSTEMS FROM ONE SOURCE

THIS SERVICE GIVES YOU THE FOLLOWING ADVANTAGES:

- ★ Standard 'Building-Block' Hydraulic and Electronic Components with a wide range of application.
- * Accurate position of velocity control up to 12 h.p.
- ★ A comprehensive system design service from specialists in this field.



Actuating

Cylinder

Photograph by courtesy of Messrs. Drummond Bros. Ltd.

Here is an example . . .

An Electro-Hydraulic copying attachment, embodying a VICKERS power unit and other components, as fitted to the Drummond 'Maximinor' combined multi-tool and copy turning lathe.

VICKERS SPERRY RAND LIMITED

(formerly Stein Atkinson Vickers Hydraulics Ltd.) Division of Vickers Incorporated, U.S.A.


NEW LANE, HAVANT, HAMPSHIRE • Telephone: Havant 2281

Technical Sales and Service at London, Glasgow, Birmingham, Leeds and Manchester.

Power Unit

961

Production Increase from Your Auto...



LET US ESTIMATE SAVINGS ON YOUR EXISTING RUN

- Only 4 seconds reloading
- No idle time, continuous running.
- Proved in use, one operator handles several machines.
- Range covers to in. to itin. bar, tin, to itin, tube,
- Feeds to last workpiece—without fingers.
- · Ejects remnant automatically.
- Patented Rear Ejection gives posi-tive control of remnant at all times, increases versatility of Bar Feed.

AUTOMATIC BAR FEED



WRITE FOR LEAFLET to dept. M2555

Patents Nos. 728898 and 743461, 827417


Automation Ltd

DEVONSHIRE HOUSE : VICARAGE CRESCENT - LONDON - S W 11

Here's why the GRAY

- pyramid side walls on full abutment tool aprons double-length bed
- knee and rail counterbalance
- new design knee with **GRAY** safety-nut
- square lock construction throughout
- table safety stop and synchromesh table replacer
- I full pendant control

- speed range. 30-300 ft. per min.
- infinitely variable feed ranges
- height under rail 30", 36" or 42"
- table widths -30", 36" or 42"
- stroke lengths, 6—30 ft.



DOUBLE-CUTTING HEADS (OPTIONAL)


Universal type heads permit cutting in both directions-no idle stroke. They in no way restrict conventional planing

operations.



SPACE SAVER DRIVE WITH **EXCLUSIVE HELICONE TRANSMISSION**

Allows ideal location of motor. Extremely smooth drive with three or more teeth always in mesh between rack and bull gear.



Hying scot is a best seller!...

ADS

permit s-no way laning

The construction of the FLYING SCOT is such that it will perform precisely for years. Carbide planing

up to 300 ft. per minute makes it the world's highest production small planer.


Optional equipment includes left hand rail head and side head in either plain or universal styles. Write now for descriptive literature.

Manufactured and Distributed in U.K. by agreement with The G. A. GRAY Co., U.S.A.

KEARNEY & TRECKER-C.V.A

GARANTOOLS HOUSE . PORTLAND ROAD . HOVE . SUSSEX Tel : Hove 47253 Cables: Ceveatools (Telex) Hove

LONDON . BIRMINGHAM . GLASGOW . MANCHESTER . BRISTOL



High Production-Precision Finish at Less Cost ...

No 24 MATTISON **DUPLEX** Rotary Surface Grinder The No. 24 Mattison Duplex Rotary Surface Grinder represents an entirely new approach to the problem of increasing production without decreasing quality or adding manpower. In operation one of the chucks is always under the grinding wheel. Adjustable dogs control length of carriage stroke - each chuck can be instantly brought to its correct position in lateral relation to grinding wheel. Top of each chuck is ground off to precisely the same height — finished pieces from one chuck exactly match those ground on its mate. Every control within instant reach of operator.

Write for data.

GASTON E.MARBAIX LTD.

Phone: Battersea 8888 (8 lines).

3, 1961

Can you take advantage of these



Tapping three 15"-18 holes in steel at 1,800 holes/hr. with No. X-11 Piece Part Fixture.

TIME SAVED 75%



Drilling eight &" holes in brass at 1,920 holes/hr. with No. 16 Vertical Indexing and Clamping Fixture.

TIME SAVED 58% SAVINGS in automatic drilling. tapping and threading?

> The average Snow machine pays for itself completely in 300 to 600 hours. That's only 9 to 17 weeks of 35 hours/week. A Snow machine can be idle 85 per cent. of the time and still pay for itself in one year!

> Such savings are possible because Snow machines give two to four times the hourly production of non-automatic machines. A complete range of air-operated fixtures permit minimum tooling for each job. On your next job, let us explain what the Snow method can do.

TIME SAVED 63%



Threading two ends \(\frac{2}{3}"\)—30 bress at 1,800 ends/hr. with No. 612 Air Vice.

TIME SAVED 67%



Drilling 18" hole through brass at 2,600 holes/hr. with No. 15 Vertical Indexing Fixture.

SNO

MASTER FIXTURES SAVE POUNDS AND DAYS IN TOOLING COSTS!

GASTON E.MARBAIX LTD.

Full Proposals on Application

DEVONSHIRE HOUSE, VICARAGE CRESCENT, BATTERSEA, LONDON, S.W.11

Phone: Battersea 8888 (8 lines).

When answering advertisements kindly mention MACHINERY.


ich to tuor

der ·ol each

actly or.

ines). 36308

De



WIEDEMANN

pierces the Time and Cost Barrier



Wiedemann cuts the cost of short and medium run piercing by as much as 85% and does the job much better and much faster. No more marking out—No more setting up, drilling, flycutting, chiselling out or finishing to size and no more costly tooling. Modifications or complete changes of layout made quickly, easily, cheaply.

Write for Wiedemann Brochure No. M/176 and study the 'hole' time and cost question — and send sketches of some of your jobs and ask for time studies.

BRITISH WIEDEMANN TURRET PUNCH PRESSES

RA. 41P with pantograph table and stylus for rapid hole location. Throat depth 28" with 16, 18 or 20 turret stations. 30,000 lbs. capacity. Other models—hand and power operated—15,000 to 160,000 lbs. punching pressure.

See this machine at our Showrooms



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14
Tel: WESTERN 8877 (8 lines) Telex: 23182 Grams: ACCURATOOL LONDON TELEX

December 13, 1961

Automatic PRODUCTION COPY MILLING

-by installing

RIGID AUTOMATIC **HYDROCOPYING** MACHINES



Speed up production by copy milling the 'RIGID' way. Line-by-line scanning automatically copies vertical angles up to 90° and 360° profiles at constant feed without rotating the work-table. With a reverse image attachment similar profiles of the same or opposite hand can be made from the one master. Tracer pressure is so light that plaster or wooden masters can be used.

Model KA.200/2. Two Spindles. Table size 921" x 231"

KA.200 illustrated

Send for illustrated brochure M/142 to Sole U.K. Distributors



DOWDING &

When answering advertisements kindly mention MACHINERY.

For BORING to close tolerances

ROLLS-ROYCE use

SWISS

DIX

HORIZONTAL OPTICAL
JIG BORERS



Experimental
Compressor Shaft
mounted on pixi
circular table, boring
fine limit blade pin
holes. Maximum
tolerance on finish:
16 micro inches.

BRIEF SPECIFICATION

Table size

Spindle speeds

Spindle dia.

DIXI 60

283/4" × 325/8" 34 to 1400 r.p.m. 23/8"

DIXI 75

393/8" x 32" 32 to 225 and 225 to 1600 r.p.m. 3"

Write for illustrated brochure M/238 to Sole U.K. Distributors



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14
Tel: WESTERN 8077 (8 lines) Telex: 23182 Grams: ACCURATOOL LONDON TELE:

3, 196

AL

ring n

1:

23

ir fa

Making the NEW.





RRITISH-RIIII T

THOMPSON Surface Grinder

One of the many British-built Thompson Surface Grinders installed by leading manufacturers, this 16" x 12" x 40" Machine is grinding to close tolerances valve bodies for Borg-Warner Automatic Transmissions.



Built by Coventry Gauge and Tool Co. Ltd., Thompson Surface Grinders for plain or form grinding are available with table sizes from 8" x 24" to 36" x 240".

For further particulars write or telephone TODAY

WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

BIRMINGHAM - TEL: SPRINGFIELD 1134/5 . STOCKPORT - TEL: STOCKPORT 5241 . GLASGOW - TEL: MERRYLEE 2822

MILLING MACHINES



-increase output on small and medium batch sizes

FRITZ WERNER Punched Tape Controlled Milling Machines are standard machines with special electrical equipment for tape control which does not prevent manual operation.

A standard teleprinter tape determines spindle direction and braking; variable feed rates including rapid traverse; direction and length of table movements. The standard feature of automatic hydraulic clamping of stationary slides ensures rigidity.

Automatic dividing attachments, circular tables and clamping fixtures can be included in the programme which can contain an infinite number of stages.

ROCKWELL

For further particulars write or telephone TODAY

WELSH HARP, EDGWARE RD., LONDON, N.W.2. TEL: GLADSTONE 0033

S





* Stock Pulleys Standard Pulleys **SPECIALS** ONE OFF OR QUANTITIES

V-BELT COM-PACWedge V LINK-V

AND SPECIAL GROOVING





Stocks of Atlas
TAPER BUSHED V PULLEYS



OFF-SET BOSS

FLANGE



SPECIALS





***** Top Engineering Quality

* Competitive Prices and **Deliveries**

The London Shafting & Pulley Co. Ltd.


COLLINGWOOD IRON WORKS

Attach this cut-out to your letter heading

Please send NEW comprehensive V-pulley catalogue

.When answering advertisements kindly mention MACHINERY.

THE "MULTI-CYCLE" UNIT MACHINE



with BUILT-IN SELECTION FOR ALL THESE CYCLES brings AUTOMATION for small or quantity production at unusually low cost

Here is a "multi-cycle" machine within the price range of a single-operation production machine which has been developed especially for batch or quantity production. It is available in three sizes—2 h.p., 5 h.p. and 10 h.p. for horizontal or vertical application.

Full details and specification on request.

A'M'T (B'HAM) LTD. Bournbrook, Birmingham 29.

Telephone: SELly Oak 1128/9/20.

Telegrams: "AMTOLD B'ham".

















1961



TOOLING LAYOUT No. 11





STEEL SPINDLE

13" dia. Steel Bar E.N.8. 40 ton Tensile Steel Tungsten Carbide Cutting Tools.

2DS CAPSTAN LATHE

Code Word: Twods Fitted with 14" Air Bar Chuck and Air Bar Feed. Floor to Floor Time: 1 min. 45 secs.

			Tool Position		Spindle	Max. Cutting Speed		Feed			
	DESCRIPTION OF OPERATION			Hex.	Turret	Cross-slide	Speed R.P.M.	Feet per min.	Metres per min.	Cuts per inch	m/m. per rev.
1.	Feed bar to stop & close chuck	-	-	-	1	_	_	_	_	_	_
L.	Centre drill	,00		-	1	-	1110	-	_	Hand	Hand
	Start turn		-	-	2	_	1110	343	104	Hand	Hand
	Tangential roller turn ·887" dia.	-		-	3		1110	343	104	130	-195
	Multiple roller turn 11"762" & .5	79"	dias.	-	4	-	1110	343	104	130	-195
	Thread roll \$"×14 t.p.i			-	5	_	1110	181	55	_	_
	Roller end and chamfer			-	6	_	1110	181	55	Hand	Hand
1.	Tangential part off			-	_	Rear	1110	327	100	Hand	Hand

'PRELECTOR'
combination Turret
Lathes
with Preselective
speed-changing.

TURRET LATHES with capacities up to 35 in. swing over bed

Stock Tools, polholders, Chuc and Accessories for Capstan and Turret Lathes.

H. W. WARD & CO LTD

SELLY OAK, BIRMINGHAM 29



SLIDING RAM GIVES 274in. FEED

Integral double swivelling universal head provided with $27\frac{1}{2}$ in automatic cross feed by the sliding ram, can be set to the horizontal or vertical position, or to any angle instantaneously-permits the heaviest production cuts. Heads can be retracted completely from table line.

27 spindle speeds from 30 to 2,066 r.p.m., 27 feeds from 1/2 in. to 30in.

Rapid traverses in all directions. All operating controls duplicated.

Table slides directly in the knee without cross movement or swivel.

Double guides of knee permit components in excess of 1½ tons to be machined. The double swivelling universal head requires an opening of only 14in. to enter work pieces and the whole sliding ram with its 2½ in. automatic cross movement needs only 18in. clearance. OPTIONAL EXTRA FEATURES: Mounted

spacing casting assemblies providing additional 8in. capacity under spindle. 26in. wide 8 T-slot tables and 39§in. automatic cross feed of sliding ram with special heavy duty knee and front operating position.

Туре	Ta	ble		Long Cross V		Vert.
KU4 KU5 KU6 KU55	56 in. 64 in. 79 in. 64 in.	××××	15‡in. 15‡in. 16‡in. 26in.	431in. 511in. 59in. 511in.	27 in. 27 in. 27 in. 38 in.	194in. 194in. 194in.


HURON MU.6/FERRANTI 3-D MILLER

Type 'L' Open-side Traversing Head Universal Miller will mill, bore, slot and drill the largest work-pieces at one setting.

The unique design permits greatest variety of operation on large work-pieces; the component remains stationary on the large work-table. Upright sildes full length of base table and the sliding ram moves vertically and horizontally.

DUFOUR UNIVERSAL MILLERS

WITH DOUBLE UNIVERSAL SWIVELLING HEAD, RETRACTABLE SLIDE BRACKET AND SPACING CASTING GIVING 26" DAYLIGHT ON No. 59 AND 21" ON No. 61



FOR ALL MODELS Direct reading dial change for speeds and feeds. All parts subject to wear hardened and ground and completely interchangeable. Built to closest tolerances. Rapid traverses in all directions. Table swivels 30°. No. 40 taper for main horizontal spindle, double swivelling universal head, dividing head and rotary table. Hardened and ground centre guide for slideways. Twin overarms. Double swivelling sliding spindle heads with speeds 53-3000 r.p.m. Double swivelling universal head on retractable slide bracket providing with 5½in. Spacing Casting Drive assembly on 59 Machine 26in. daylight, and 21in. on No. 61.

MODELS 53 & 61. 16 universal head spindle speeds. 21-1600 r.p.m.; 8 horizontal spindle speeds 21-1180

21-1600 r.p.m.; 8 horizontal spindle speeds 21-1180 r.p.m.; 8 automatic feeds 1-183in. MODEL 59. 36 universal head spindle speeds 14-1780 r.p.m.; 12 horizontal spindle

speeds 21-1180 r.p.m.; 16 automatic feeds 1-20in.
MODEL 54. Automatic cross feed of universal head 20in.; 18 universal head spindle speeds 12-1500 r.p.m.; 36 horizontal spindle speeds 6-1500 r.p.m.; 18 automatic feeds 12-23 in.

Туре	Table	Long.	Cross Vert	
53	43½in. × 9¾in.	27 in.	9§in.	158in.
61	47½in. × 10¾in.	30 in.	9§in.	158in.
59	51¾in. × 11¾in.	34 in.	11 §in.	21 ± in
54	67in. × 14¾in.	43 in.	14§in.	204in.

d

Send for full particulars of our very extensive range of these machines; ask for demonstration.


SWAN WORKS, FISHERS LANE, Rudolph Carne & Co. Ltd. SWAN WORKS, FISHERS LAN CHISWICK, LONDON, W.4.

Tel: CHISWICK 0514, 6585, 0337. Inland Telegrams: RUDCAR, CHISK, LONDON. Overseas Telegrams: RUDCAR, LONDON. W. 4.

961

ine.
Oin.
ted.
ivel.
ned.
nter
ovented
and
ecial


∄in. ıdle



EDGAR ALLEN'S DIE STEEL

The illustrations show the die and finished product used as a container for an automatic playback tape recorder which is being issued to blind people. The box fits straight over a capstan on the tape deck which is accurately located by fixing lugs from the deck and close limits have to be maintained. The die is made of Edgar Allen's K9 die steel which has been perfected to meet the need for an inexpensive non-shrinking steel suitable for tools from which the highest accuracy is required. K9 will give long production runs with minimum regrinding. The Die was designed and manufactured by P. & H. Metal Products (Kingston) Limited and has produced many thousands of containers.

EDGAR ALLEN & CO. LIMITED
IMPERIAL STEEL WORKS SHEFFIELD 9



To ED	GAR A	LLEN	& CO.	LTD., SHEF	FIELD 9
Please	send	' K9	STEEL	BOOKLET,	to:-
NAME					
POSITI	ON .	******			
FIRM					
ADDRE	SS				

De

STUHLMAN

INTERNAL KEYSEATING MACHINES





Simplicity of tooling. No limit to diameter of workpieces.

> No marking out of components.

Simultaneous cutting of several components.

Automatic cut-out upon reaching full depth of slot. Automatic tool withdrawal. Small floor space needed.







The New Model NZH 100

Hydraulically operated, for cutting grooves up to 4" wide, in bores up to 20" dia. in 3 sizes of length of stroke.

Model NZH 100/500 — 20" /650 — 26" /800 — 31½"

Infinitely variable speeds and adjustable drawing power.

SOLE SELLING AGENTS FOR U.K.



Model NZ 250 S with 10" max. length of stroke. Model NZ 320 S with 12" max. length of stroke.

Mechanically operated for cutting grooves up to $1\frac{1}{2}$ " wide, in bores up to 12" dia.

Model NZ 320 S ex-stock subject to prior sale.



SUNBEAM ROAD. LONDON, N.W.10 Tel: Elgar 4000

STANNINGLEY Near LEEDS Tel: Pudsey 2241

BELL STREET, WEST BROMWICH Tel: West Bromwich 2634

And at: Kingsbury (Nr. Tamworth), Manchester, Glasgow, Swansea, Newcastle-on-Tyne, Sheffield, Southampton, Belfast, Bath

When answering advertisements kindly mention MACHINERY.

961


00

ke.

14"



DECOILING EQUIPMENT



Motorised and entirely self-contained, these machines will efficiently straighten and feed thick and thin stock at a variable speed to suit any requirements. Quick setting facilities to enable presses to be used to maximum capacity. In standard sizes with capacity from 6" to 33" wide by 1/8" thick.

B.H.P. MACHINE TOOL CO. LTD.,

91 WATTVILLE ROAD, BIRMINGHAM, 21

TELEPHONE: NORthern 6220-6623

When answering advertisements kindly mention MACHINERY.



Value for money? Check these points

A.S

With so many important features designed to get the utmost out of your cutting tools, these heavy duty, precision built milling machines offer more value for money than any other miller of comparable weight and performance. Check the vital points of the 3HG and 4HG and see for yourself.

ADCOCK & SHIPLEY LTD

.O. Box 22, Ash Street, Leicester elephone: Leicester 24154


elegrams and Cables: Adcock, Leicester

~	Horse Power	15	25
V	Weight	4 tons	well over 6 ton
V	Table size	60"x 14"	72" x 17"
~	Knee width	19"	25"
V	Spindle bearings	5	5

- ✓ Positive backlash eliminator
- Suitable for tungsten carbide milling
- ✓ Suitable for high rake milling
- ✓ Duplicated controls and locks front and rear
- Every final drive gear bigger than the cutter it drives
- ✓ Infinitely variable feeds ½"—64" per minute
- ✓ Hardened table screw
- ✓ Automatic slide and screw lubrication.
- ✓ 24 speeds from 23 to 1250 r.p.m.
- ✓ Built-in fly wheel







Unit construction of Herbert Drilling Machines makes it possible to produce a very wide range of machines without resource to specialization except in assembly.

The range is sufficiently extensive to meet the demand for most general-purpose machines and to provide a basis from which to build special-purpose machines with equipment of jigs, tools and fixtures for continuous high production.

We will quote for suitable equipment for dealing with specific work.

Standard Herbert Drilling Machines are made in ten types for drilling and tapping up to 1½-in. Multi-spindle and Turret-type machines also available.

The World's Largest Machine-tool Organisation presents "Production in Pictures"

The ultimate object of the machine-tool maker is to sell, not only machines, but production.

Excellence of design is an indisputable but only partial contribution; it is complementary to the ability of the maker to provide an efficient service which will enable his customers to obtain the best results from the machines installed. He must be able to advise on methods of production, to design and supply tools, jigs and fixtures, to recommend appropriate feeds and speeds for various materials and operations.

This is a service we offer with great success; we have been doing it for over 60 years for all branches of the engineering industry.

We can supply practically any type of machine tool.

We can equip complete plants.

Dec

Mach

on a time and t pre-s to re sette

> dia cen The Vic Car pro An ma tee cor Ca Th

> > N fa

> > > 2



Developed to meet the latest demands of the automobile industry for the mass production of brake discs to precision limits, our new No. 632 Brake Disc Grinder will handle work from 9in, to 14in, diameter, with from 2in, to 34in, face.

Both work faces are peripheral ground simultaneously and on a disc of 11in, diameter by 2in, face, removing 0.006in, stock from each side, the production cycle is only 40 seconds.

Size and finish are maintained by hydraulically-operated diamond dressers, which automatically traverse the grinding wheels at preset intervals.

Twin work spindles mounted in an indexing drum permit loading whilst grinding. Wheel heads are hydraulically controlled, the in-feed of the heads being infinitely variable between 0.004in. and 0.030in. per min. We will gladly quote production times on your own work.

Send blue prints as samples.

LUMSDEN MACHINE


Sole Agents: ALFRED HERBERT LTD., COVENTRY

AD. 689

961

PRE-SET LATHE TOOLING


Machining pulley blanks from EN. 8 steel billets on a Herbert No. 3 Capstan Lathe; machining time 6 minutes. The quick-acting square turret and toolholders on the turret are modified for pre-set tooling which permits the unskilled to replace worn tools without recourse to the setter and which reduces "down time".



HERBERT

A CENTRE AND COPY-TURNING LATHE.


The Herbert Carbijunior, for work up to 34" diameter × 221" long, can be used as an ordinary centre lathe or a high-production copying lathe. The initial one-off can be used as the master. Victory Engineers Ltd. informed us that their Carbijunior dealt, in two days, with two weeks' production relative to previous machining methods. An outstanding time saving effected was in machining broaches, 22" long, with ten cutting teeth and four burnishing teeth; each broach was completely copy-turned in a floor-to-floor time of 12 minutes. Using expensive form tools on a Capstan Lathe, machining time was 52 minutes. The illustration shows the production of a stud from 18" diameter bright drawn steel bar; two operations are done in 24 minutes.




HERBERT

EFFICIENT LATHE PRODUCTION

Tooling and indexing fixture on a Herbert No. 4 Senior Preoptive Capstan Lathe for facing, drilling, boring, reaming and grooving seven radially-spaced bores in an aluminium casting, at one setting. Floor-to-floor time, 28 minutes.





Com large

Turi

Ma Au spi bo

al

SE

Introducing the new LANDIS-MAIDEN double spindle Threading machine


Hardened and ground replaceable bedways.

Carriage front adjustable in both vertical and horizontal directions.

Hammer-blow handwheels give maximum grip and eliminate fatigue.

Spindles may be run at different speeds; 8 speeds by pick-off gears.

For threading bolts and pipes up to $1\frac{1}{2}$ " dia., pipes up to 2" bore. Fitted with genuine Landis Tangenti al Dieheads and Ground-thread



Cutting a 11 t.p.i. B.S.P. taper thread, ream and chamfer I" close nipples in a floor-to-floor time of 12 seconds for both ends.


LANDIS MACHINE-MAIDEN LTD

HYDE - CHESHIRE

Sole Agents
ALFRED HERBERT LTD COVENTRY

HEAVY LATHE WORK

Completely machining piston heads for large diesel engines, from a solid billet, on a Herbert No. 14/36 Combination Turret Lathe 36" swing. The skirt end is rough and finish machined in 17 hours.



HERBER


AUTO-LATHE WORK

Machined on the latest-type Herbert Auto-Junior which has an automatic spindle reversal, in 11 minutes. Microbore cluster tooling is used in this set-up.



RAPID PRODUCTION OF SMALL PRECISION PARTS

This component is completely machined. in two operations, in 22.5 seconds on Bechler Automatics. The picture alongside shows the tooling set-up with automatic loading and ejection, for the second operation.




1961

No. 35/I for leng

ad

simplicity of repetition machining on —





A Brown & Ward 1¼in. four-Operation Bar Automatic produces brass clack valves at the rate of 3.6 components per minute.

After the forming and drilling, the machined stem is loaded into the loading head on the turret and inserted in the valve body.

The wall of the valve head is peened over the edge of the stem, prior to parting-off.

BROWN & WARD single-spindle BAR AUTOMATICS

Uses simple standard cams and tools.

Wide range of attachments increases versatility,

Competitive to six-station machines relative to low capital outlay. Six sizes, three types, for work up to 1½in, diameter by 4½in, long,

ALFRED

HERBERT


Factored Division, Red Lane Works.

AD 638

g,

HEAVY METAL REMOVAL


Ardoloy-tipped Multi-tooling on a Herbert No. 12B Cross-sliding Turret Lathe-32" swing, 35/11 h.p. motor. This is the ideal machine for boring and facing with short turning lengths, on work produced in small batches. Extremely heavy metal removal.



HERBERT

ONE SET-UP MACHINES RANGE OF FLANGES


A set-up on a Herbert No. 9C Combination Turret Lathe for machining pipe flanges from steel forgings. Some fifty different sizes and types of flange are machined with only minor adjustments to the tooling. Ardoloy-tipped tools are used throughout.




HERBERT

AN ADAPTABLE SMALL SURFACE GRINDING MACHINE

A self-contained 10" × 4" × 9" capacity machine primarily designed and now extensively used for light production jobbing work but which, due to the wide range of tool and cutter grinding attachments available, is now included in most efficient tool maintenance plants. It has micrometer dials for precision control of longitudinal and transverse movements to the table. Pomp lubricated covered slide ways.



A lither the sale book fact He for jight white his



HOLEROOK Precision Lathes

The Holbrook range includes:— Model H—20" x 42".

Model B—14¼" x 36" and 22½" x 48".

Model D-20" x 42".


Model R—two sizes for relieving and grinding hobs and cutters up to 4" and 9" diameter respectively.

Model U-17" x 42".

The Holbrook model 'H' No. 17 Precision Lathe, in the standard form, has a 20" swing over bed, 42" between centres, spindle speeds 15-1,000 r.p.m. Features include: 16 spindle speeds (forward and reverse) with single lever control, cam-lock spindle nose $2\frac{5}{8}$ " dia. hole, single helical ground gear final drive, totally-enclosed gearbox and apron, 60 direct changes of threads and feeds, precision leadscrew and compensated thrust bearing. Also available with alternative speed range and bed length, rapid power traverse and two-speed tailstock.


Hydraulic profiling equipment, tapering equipment, etc., can be fitted.

HOLBROOK MACHINE TOOL CO LTD HARLOW, ESSEX



MAXIMUM OPERATIONS PER SET-UP


A Herbert/DeVlieg Jigmil completely machines the cylinder block of the 3.7 litre engine for the David Brown Aston Martin DB. 4 sports saloon. Operations include drilling, tapping, boring, counter-boring, line boring, spot facing, back facing and face milling. The Herbert-designed locating fixture is also used for machining the cylinder head. Accurate jigless positioning is obtained with the "Duplitrol" co-ordinate positioning system, which provides rapid batch production and a high machine utilization.



HERBERT

RAPID FORMING OF SHEET METAL


A Pullmax machine forms flat rings into a radiused section, see below, from 16 s.w.g, mild-steel sheet in approx. 15 minutes.



HERBERT

TRACER-CONTROLLED MILLING

The Keller Automatic Toolroom Machine with automatic electric controls, for two- or three-dimensional work on dies and moulds of all kinds, press tools (motor-car roof punches are machined), metal patterns and similar work. Two sizes—5' \times 2½' and 6' \times 4'—now built in this country by Pratt Whitney & Herbert Ltd. The core box (4' 6" \times 2' 6") shown was automatically machined in a floor-to-floor time of 100 hours. Accuracy was such that the layout ines were split during machining.



Hea

acco

12

Quality for your products starts here ____




...and we can meet your planing capacities with

Double-column Planers with capacities up to $12^{\circ}0^{\circ}\times 5^{\circ}6^{\circ}\times 6^{\circ}0^{\circ}$ (Spiral Drive except "Junior" types). Openside All-electric Spiral Drive Planers with capacities up to $10^{\circ}0^{\circ}\times 4^{\circ}6^{\circ}\times 4^{\circ}6^{\circ}$. Openside Planer Shaper with capacities up to $96^{\circ}\times 25^{\circ}\times 2_{4}^{*}$. Can be fitted with Milling, Grinding or Profiling Attachments.

AD 690





December 13, 19

961

to g,

90

A WELL-ESTABLISHED CENTRE-LATHE

The illustration shows a battery of Edgwick 6½" Gap-Bed Centre Lathes installed at the Heaton Works of C. A. Parsons & Co. Ltd. The Edgwick Lathe, over 3,700 have been sold during the last 20 years, is designed to accommodate 95% of the centre-lathe work required in industry today.

The modern version, designated Mk. II, is available with 6' 8" or 7' 8" bed length. Swing over bed: 14". Swing in gap: $22" \times 7\frac{1}{4}"$ 12 speeds 17-670 r.p.m. or 25-100 r.p.m.


Can be fitted with hydraulic copy-turning attachment.




HERBERT

PRECISION AUTOMATIC GRINDING

Automatic grinding a 1.2785/1.2795" external diameter on a Heald 171 Sizematic Internal Grinding Machine. Up to fifty components ground per hour (80% efficiency).





HERBERT

THREAD ROLLING

In-feed rolling and ajustable worm on a Landis Lan-nu-rol Thread Rolling Machine. A $\frac{9}{16}$ " dia., 14 t.p.i., full depth acme thread is produced in 12 seconds.



Plane

to c

copy with The rever per to avail

> Wal cent Mac dia.


> dev

mer

plat

Sp. Kn

and Th



HERBERT HEXAGON TURRET LATHES

The illustration above shows the standard outfit of tools supplied with these machines and the method of arranging them around the turret,

The Hexagon Turret Lathe is essentially for the production of shafts, spindles, pins, bolts, studs, collars, bushes and other work which can be made direct from the bar and thus eliminate the cost of forgings and stampings.

Since bar work operations mainly comprise the machining of various diameters and lengths and the cutting of threads of a restricted range of sizes, there is no necessity for a saddle and practically all operations within the capacity of the machine can be performed with the standard outfit of tools.

Two sizes available to accommodate work up to 3" diameter by 38" long.

Both sizes now available for

EARLY DELIVERY








961

COPYING OPERATION ON A PLANING MACHINE

We are sole agents for the standard and specialpurpose reciprocating machines made by Planers (Huddersfield) Ltd.

The illustration shows a Planers 8' 0" × 4' 0" x 4' 0" Openside Planer equipped with a copying toolbox on the cross slide, in addition to one standard-type toolbox. copying can be done through an angle of 180° with this equipment.


The machine is driven from a 25 h.p. main reversing motor and table speeds from 30-200 ft. per minute, on cutting and return strokes, are available.



HERBERT

TURNING, FORMING AND **GRINDING LARGE ROLLS**

Waldrich-Siegen Roll Turning Lathes with centre heights from 40" to 90" and Roll Grinding Machines with capacities for rolls up to 72" dia, and of any length restricted to rolls of a maximum weight of 130 tons. Can be specially developed to meet customers' specific requirements for the manufacture of rolls for producing plate, sheet, strips and foil.




HERBERT

HERBERT GROUND-THREAD

Standard taps in all sizes and forms of thread-Special taps, including those for Acme, Buttress. Knuckle; Staybolt, Mud plug and Tandem taps made to customers' requirements. Accuracy conforms to B.S.I. Specifications, Zones 1, 2 and 3.

The 2¼" dia. × 3 t.p.i. buttress thread shown, was cut in one pass, in a phosphor-bronze nut with a Herbert Ground-Thread Tandem Tap on a Herbert Combination Turret Lathe.



Four speci Villie

100% one

and para and

simu

in di In th thes of si

5 to Box avail

> Mic Arc mad

> face dire and The


New!introducing a series of LOCK FORMING TOOLS to produce a false Wired Edge, Dutch fold, Drive Cleat, Grooved Lock or Flanged Channel in 16 s.w.g. M.S. at speeds in excess of 6ft perminute

PULLMAX



SHEET METAL WORKING MACHINES

No modern sheet-metal department is complete without a PULLMAX machine. These versatile machines are designed for cutting circles, louvres, straight edges and internal or external irregular shapes. In addition many forming operations including beading, flanging, doming, joggling, etc., can be performed.



HERBERT

D., COVENTRY Foctored Division. Red Lane Works.




When answering advertisements kindly mention MACHINERY.

HIGH-SPEED INSPECTION

Four Sigma Liquicolumn Multi-dimension Inspection machines have been supplied to Villiers Engineering Co. Ltd. for high-speed 100% inspection of crankcases and coversone of each type shown alongside. Diameters and lengths, relationship and pitch of holes, parallelism and concentricity, squareness, taper and ovality are inspected in various combinations simultaneously.





HERBERT


LARGE REDUCTION IN DIAMETER WITH HIGH DEGREE OF SURFACE FINISH

Chipstream Boxtools permit large reductions in diameter in one cut.

In the Herbert works, on day-to-day production, these boxtools provide a relatively high degree of surface finish. Measured readings between 5 to 10 micro inches are frequently obtained. Boxtools with capacities up to 3" diameter,

S

Two boxtools are used in the set-up on a Herbert No. 2D Capstan Lathe shown alongside




HERBERT

PRECISION PRODUCTION BORING

Microbores micrometer adjustable single-point Ardoloy-tipped tools—in a cluster on a milling machine, machining three bores and the top face of a gearbox casing. Machining is done direct from the cored holes and sizes, parallelism and ovality held to within close tolerances. The largest diameter, for instance, is machined parallel to within 3.7496/3.7493". The finish obtained eliminated a subsequent

grinding operation necessary prior to the use of Microbore Tooling.





We can supply a wide range of Small Tools and Machine-shop Accessories, most of which have been proved in our own Works.

What is more important, they can be supplied promptly, for a comprehensive range of tools is stocked not only at our Coventry Warehouse (a section of this is pictured above) but also at Branch Offices at:—

LONDON, MANCHESTER, LEEDS, BIRMINGHAM, SHEFFIELD, BRISTOL, NEWCASTLE AND GLASGOW.

ALFRED

HERBERT

LTD., COVENTRY



AD 686



HABIT



FULL 180° OF ARC

The 'Habit' Radform is a completely universal radius generator providing for all types of radius dressing on surface and other grinders using wheels up to $7\frac{1}{2}$ in. diameter. It is in fact two instruments in one. A robust conventional dresser which in seconds can be adjusted to give corrected diamond travel to enable small full concave radii to be generated.

EXCLUSIVE HABIT

- Anti-friction, wear resisting, correction mechanism.
- "Full-House" sealing against dust.
- Built-in dial gauge setting.

FEATURES INCLUDE

- Positive graduated arc limitation.
- Instant conversion from

full to corrected diamond swing.

It pays to make it a 'HABIT'

RADIUS GENERATOR

HABIT DIAMOND TOOLING LTD., LURGAN AVENUE, LONDON, W.6. Telephone: FULHAM 7944

HABIT

De

EXPERIMENTAL SPRINGS?



Select your springs here No. 1217 One gross Assorted Springs



No. 1200 Three dozen Assorted Light Expansion Springs, suitable for carburettor control, etc. 15/-.



No. 760
Three dozen Assorted Light
Compression Springs. 1" to 4" long,
22 to 18 S.W.G., 2" to 1" diam. 7/6.



No. 98A Three dozen Assorted 1" to 4" long, \frac{1}{2}" to \frac{1}{2}" diam., 19G to 15G. 6/6.



That spring you want . . . in a hurry . . . where is it? Pick what you want, when you want it, from TERRY's BOXES OF ASSORTED SPRINGS -our fine range of small boxed assortments of experimental springs. We can show you only a few from the range here. Send a postcard for our full listand if ever you're stuck with a spring problem send it along to our Research Department-they'll gladly help you out.



No. 757
Extra Light Compression, I gross Assorted, § 10 Å diam., § 10 L§ 10 long, 27 to 19 S.W.G.





Fine Expansion Springs, 1 gross Assorted † to † diam., † to 2' long, 27 to 20 S.W.G.

Have you a Presswork problem?

If so, the help of our Design Staff is yours for the asking.

for SPRINGS



Really interested in Springs? "Spring Design and Calculations" 10th Edition tells all—post free 12/6.



Cut Production Costs with Terry's Wire CIRCLIPS. We can supply immediately from stock — from \$\dagger* to \$\dagger*.



Send for a Sample of Terry's Security Worm Drive Hose Clip and price list.

HERBERT TERRY & SONS LTD.

Redditch, Worcs.

(Makers of Quality Springs, Wireforms and Presswork for over 100 years.)

1961

5?

hen RY's

RINGS

Ve

end a

send

adly



YOU are invited

TO VISIT THE

MACHINE TOOL EXHIBITION

AT OUR EXTENDED SHOWROOMS

DECEMBER II-15, 1961

A FULL RANGE
OF MACHINE TOOLS
DEMONSTRATED
UNDER POWER

MORTIMER

EXCLUSIVE

DISTRIBUTORS OF THE FINEST MACHINE TOOLS

MORTIMER MACHINE TOOL CO. LTD . MORTIMER HOUSE . ACTON LANE . LONDON NW10 . Tel: ELGar 3834-5-6

Dec

Ma and


equ jig


MM

from Horizontal to Vertical Mill ... in One Minute!



COMBINED HORIZONTAL & VERTICAL MILLERS





Typical horizontal milling application on the Abene.

High speed with power feed and rapid traverse in all directions.

Combines the working capacity of vertical

and horizontal milling machines.

Due to the inclined design the machine retains the maximum of 20" from spindle to table whether set for vertical or horizontal milling. Also manufactured as a model VHF.2B with power longitudinal feed only.

MODEL VHF.3.

48" x 10" Working surface of table Longitudinal and 5" to 30" per min. " to 183" per min. cross feeds Vertical 44 to 2,000 r.p.m. 12 spindle speeds Motor

MODEL VHF.2B

Working surface of table 41" x 10" 5" to 30" per min. Longitudinal feed Spindle at 45° on end milling job.

ORTIMER


EXCLUSIVE DISTRIBUTORS OF THE FINEST MACHINE TOOLS

MORTIMER MACHINE TOOL CO. LTD · MORTIMER HOUSE · ACTON LANE · LONDON NW10 · Tel: ELGar 3834-5-6

961

THE MOST COMPLETE
RANGE OF UNIVERSAL
JIG MILLING
AND DIESINKING
MACHINES

These Four Universal Tool Milling and Diesinking Machines cover the requirements of all toolrooms large and small. Absolute versatility is provided by unique construction and extremely wide range of auxiliary equipment, including optical co-ordinate setting for jig boring. This range enables tools to be machined up to approximately one ton in weight.



OPTIONAL EXTRA ACCESSORIES INCLUDE . . .

High speed vertical milling heads, slotting attachment, rotary table, fixed swivelling, tilting and inclinable tables, punch milling attachment, dividing head and spiral milling attachment, and on the larger models power fed vertical milling attachment will be available. It is also possible on the MAHO model MH.800 to fit this machine with hydraulic copying equipment, and on the model MH.1000 HEID electronic copying equipment is available.

Optical readers and rules can be supplied for the headstock slide, longitudinal traverse slide and vertical traverse slide,

SHOWROOMS & SALES OFFICES:

MORTIMER MACHINE TOOL CO. LTD.

MORTIMER HOUSE, ACTON LANE
LONDON N.W.10.

Tol: FLGAR 3834







CHECK YOUR TOOLROOM REQUIRE-MENTS AGAINST THESE MODELS

MAHO MH.600. Table 24" x 8½", horizontal spindle speed 55 - 1000 r.p.m., vertical spindle speed 99 - 1650 r.p.m.

MAHO MH.700. Table 27½" x 10½", horizontal spindle speed 65 - 1000 r.p.m., vertical spindle speed 99 - 1650 r.p.m.

MAHO MH.800. Table 31½" x 12½", horizontal spindle speed 32 - 1320 r.p.m., vertical spindle speed 45 - 1900 r.p.m.

MAHO MH.1000. Table 474" x 14½", horizontal spindle speed 40 - 2000 r.p.m., vertical spindle speed 40 - 2000 r.p.m.

Models MH.800 and MH.1000 are equipped with independent spindle drive motors mounted on ram.





Tel: ELGAR 3834 EXCUSIVE DISTRIBUTORS OF THE FINEST MACHINE TOOLS

NRP 5083

4-5-6

Dece

DELL

GENTRE LATHES

MODELS

BV. 28 - 29 in

BV. 32 - 32 in Swing over bed

BV. 36 - 37 in

- 24 speed headstock
- 4.9-400 or 7.5-600 r.p.m.
- Helical final drive to spindle
- 48 change feed screwcutting gearbox

Optional extras include:

- 12 belt spindle speeds of 100-800 r.p.m.
- Power feed to 360 deg. swivelling tool-slide
- Quick power traverse of carriage and cross-slide





Manufacturers of:

Centre Lathes from 17" (430 mm) to 42" (1065 mm) Swing Surfacing and Boring Lathes of 17" (430 mm) and 25" (635 mm) Swing

TAS/CC.92

DENHAM'S ENGINEERING CO. LTD., HALIFAX, ENG.

Member of the Charles Churchill Group of Companies

ec. 13, 1961

ving

C.92

DE LAVAL

TURBO MATIC

FOR THE MOST
EFFICIENT
CLARIFICATION
OF GRINDING
AND HONING
COOLANTS

DE LAVAL
TURBO-MATIC CLARIFIER
Type BX 215-34S

FIC

DE LAVAL
TURBO-MATIC
HINOR CLARIFIER

Type WX 209 - 34
Completely automatic in operation and ensures wainterrupted flow of coolant


By the continuous removal of solids, De Laval Turbo-Matic Clarifiers ensure a coolant clarity unattainable by any other method.

The extracted solids, held in the large capacity bowl, are discharged automatically at pre-determined intervals.

De Laval Turbo-Matic Clarifiers can be used for individual requirements, or coupled up as a centralized installation.


Write now for fully descriptive literature
FACTORY EQUIPMENT DIVISION

ALFA-LAVAL COMPANY LIMITED NINE TURBO-MATIC clarifiers, automatically controlled by a timing device, installed by a large British bearing manufacturer for the centralized treatment of mineral oil.



GREAT WEST ROAD - BRENTFORD - MIDDLESEX - TELEPHONE: ISLeworth 1221





new standard in

GOPYMATIC

PRODUCED IN THREE SIZES...1610(13") 2013(16") 2013-17(20")

AND IN TWO TYPES ENGINE & TOOLMAKER

Powerturn Copymatics have the versatility of the standard lathe and the productive capacity of a special purpose lathe—without the high cost and limited use of the latter. Instant changeover from standard lathe operation to Copymatic saves time and money. Exceptional sensitivity ensures accurate duplication.

Quick, accurate duplication of square shoulder faces, grinding necks, tapers in both directions, chamfers, curved contours and straight diameters in both turning and boring operations.

Base mounted, inverted type stylus eliminates tracer and tracer mount interference and permits 360° operation.

Choice of using round or flat* templates.
*Optional Extra



automatic duplication

KEARNEY & TRECKER-C.V.A LTD.

GARANTOOLS HOUSE . PORTLAND ROAD . HOVE . SUSSEX Tel: Hove 47253 Cables: Ceveatools (Telex) Hove

LONDON . BIRMINGHAM . GLASGOW . MANCHESTER . BRISTOL

The


HYDRAULIC FACE DRIVING UNIT

ROHM CONSTANT

SPECIAL ADVANTAGES :

- · Easy handling of large diameters.
- Easy and quick exchange of driving pins without the use of any mechanical means.
- Every driving plate forms a complete hydraulic unit. The driving pins can be exchanged without loss of hydraulic fluid.
- Absolutely true and concentric run of the workpiece.
- Highest possible degree of axial and radial rigidity.





Full length of component completely unobstructed



SPECIAL ADVANTAGES :

- Any expansion caused by heat is automatically compensated.
- It is not necessary to watch the pressure gauge during turning.
- End pressure being constant, there is a certainty of efficient drive by the face driving unit.
- No shape alteration of the workpiece due to bending, side thrust,
- No possibility of overloading the machine — or centre bearings.
- Considerable saving in operation time.

Five standard sizes

Complete details on request

Main U.K. Distributors for ROHM Face Driving Units:

CHARLES CHURCHILL & CO LTD., Coventry Road, South Yardley, Birmingham, and all Branches

Sole Importers for the United Kingdom



MICHAELS, THOMPSON LTD.

.185/7 HAMMERSMITH ROAD

LONDON W.6

Telephone RIVerside 7922/3

Telegrams TOMTOOL, LONDON W.6

COMPENSATION FOR LENGTH

The finest tools of their kind



CONTINUOUS LOADS

MILLERS' OILS

JOHN W. MILLER & SON LTD. Brighouse · Yorkshire · England Tel : Brighouse 1047 (3 lines)



Greatly increased life

of bogie suspension unit with

Black-Moly

REMARKABLE REPORT FROM BRITISH RAILWAYS, WESTERN REGION



* LUBRICANT GRADES USED WERE:

BLACK-MOLY AEROSOL BLACK-MOLY PASTE BLACK-MOLY M.P. 'Q' GREASE

POST THIS COUPON FOR FULL DETAILS OF BLACK-MOLY

BLACK-MOLY



Severe scuffing had been experienced on the insides of coil spring guides on Diesel Locomotives, caused by heavy metal to metal contact. Tests were commenced using BLACK-MOLY Molybdenised Lubricants, and after complete treatment these Bogies were put back into service.

The same Bogies ran 175,000 track miles before general overhaul, whereupon the suspension units were found to be in excellent condition and with considerably less wear than ever before.

This transmant with

BLACK-MOLY

s now standard procedure in the Western Regio

To: JOHN MILLER & SON LTD . BRIGHOUSE . YORKSHIRE

WITHOUT OBLIGATION send me further details of BLACK-MOLY Molybdenised Lubricants. Ask your representative to arrange an appointment*

Name

Company

Address

Telephone

is the registered trade mark of JOHN MILLER & SON LTD . BRIGHOUSE . YORKSHIRE . ENGLAND

Spectra color

Engineers' layout fluid in transparent blue, now in handy aerosols

- * Cannot spill or evaporate
- * Cuts out brushes and pots
- * Gives a thin, durable film of solid, even colour
- * Dries instantly-reduces waiting time
- * Cannot crack, peel, chip or flake
- * Resists petrol, water and most oils
- * Easily removed with Spectra Remover

Now in handy aerosol form and even easier to use, Spectra Spray leaves a blue film which speeds marking off to very fine limits—gives greater accuracy in machining with less eye strain and lower incidence

Each operator needing Spectra Color can now be supplied with an individual can, avoiding time loss in collecting and returning

MAKE A BLUE-PRINT ON METAL FROM A BLUE-PRINT



In Transparent Blue only (6 fl. ozs.) Part No. SS1, 7/6 each. Carton lots of 12, 7/- each. 36 and above carriage free.

Also available in other sizes and colours for brush application-write for details.

Spectra Spray Paints


For the small spray job on prototypes, models, machinery, mock-ups, "one-offs" etc.

- * Available for instant use
- * Saves maintenance of spray guns for small jobs
- * Dries rapidly and evenly without brush marks
- * Fine mist delivery reaches inaccessible parts
- * Special non-clogging spray head-avoids tearing
- * Available in 14 colours and primer

These handy spray cans are so easy to use-each coat is dry in a few minutes-reducing waiting time for additional coats.

APPLICATIONS For spray painting of jigs, models prototypes, radiators, small repair jobs, stencilling crates, part numbers-rapid colour coding-finishing display work, etc.


SPECTRA CHEMICALS LIMITED. 31 High St, Caterham, Surrey. Caterham 4231



COLOURS AND PART NOS.

Red	PR	Dark Green	PT
Yellow	PY	Light Blue	PK
Fawn	PF	Dark Blue	PL
Brown	PB	Gold	PG
Light Grey	PD	Silver	PS
Dark Grey	PE	White	PW
Light Green	PI	Black	PZ
	Prime		

in 6 fl. oz. aerosols at 9/6 each. Cartons of six (colours to choice), 9/- each.



Ultrasonic Cleaning

cleans ultra-efficiently

HOW?

By introducing high frequency pressure waves in liquid cleaning media (alkaline or solvents), causing momentary tiny vacua, called cavitations. The effect is a mechanical scrubbing action on surfaces to be cleaned, removing all oily or solid contaminations like dirt, swarf or grease. The pressure waves are created by immersed nickel transducers, which oscillate at a frequency of 22 kilocycles, the source of which is a valve generator converting the mains current to high frequency current.

WHAT?

Ultrasonic cleaning is the most effective method of cleaning articles which are difficult to clean by ordinary methods. In particular, parts which are contaminated with solid soil, such as pieces of polishing cloth or polishing paste, swarf in fine holes, enclosed angles, ridges, ledges, hollows; parts with dirt deposits of long standing; parts having residues of hardening compound, etc.

WHERE?

Ultrasonic cleaning can be applied in any kind of conventional cleaning installation, such as alkaline cleaning tanks, Tridegreasers, etc., by simply immersing the nickel transducers in the cleaning liquid. Special equipment entirely adapted to particular applications of Ultrasonic cleaning, either hand operated or fully automatic, can be supplied.

FURTHER QUESTIONS . . . concerning Ultrasonic Cleaning, its capabilities and characteristics, are answered in our special leaflet. Please write for a copy.

From Roto-Finish come these other surface treatments:

Barrelling and Vibrafinishing for metal and plastics to deburr, descale, deflash, radius, surface blend, polish or lustre. Atram phosphating processes.

Electropolishing.
Ultrasonic cleaning.
Mechanical cleaning.
Grisiron Alkaline cleaners.
Euron cleaner passivator.
Conversion and protective coatings.

Tell you more about any or all of them? We would be happy to if you write or telephone us.

Rely on

Roto-Finish

to provide the finishing touch

Mark Road, Hemel Hempstead, Herts. Boxmoor 4600 (PBX)

For Holland:

N.V. Roto-Finish Mij., Rotterdamseweg 370A, Delft, Holland

Talk to Sykes about the VIOB

41 gears in 59 minutes



... you would probably be quite satisfied if you produced these 41 gears in the time stated. With the V10B Vertical Gear Generator (Basic model) we promise you more than that ... you can set the machine, size the first gear and cut the remainder of the batch ... in less than an hour.

If you would like to know more about the remarkable savings which the V10B can effect on setting and cutting times on batch production write for a copy of brochure P18/60.






W. E. SYKES LIMITED . STAINES . MIDDLESEX . ENGLAND

and associated companies:

Sykes Tool Corporation Ltd., Windsor, Ontario, Canada. Sykes Machine & Gear Corporation, Detroit, Michigan, U.S.A. W. E. Sykes Ltd., Mascot, Sydney, NSW, Australia.



INCREASE YOUR PRODUCTION CAPACITY

Automatic or semi-automatic machinery increases production and reduces costs, and Martonair pneumatic equipment has been the means of building thousands of machines. Low cost, adaptability and simplicity are special features of Martonair products. If there is no machine available for the operation you wish to mechanise, or existing machines are for some reason unsuitable, it may well be possible to build a simple special purpose machine. The Martonair Technical Service is at your disposal at all times, and has considerable experience of the applications of pneumatics in industry.



MARTONAIR LIMITED, PARKSHOT, RICHMOND, SURREY, ENGLAND.
... AND AT BIRMINGHAM · CARDIFF · GATESHEAD · GLASGOW · SHEFFIELD · AUSTRALIA
BELGIUM · CANADA · DENMARK · FINLAND · GERMANY · HOLLAND · ICELAND · ITALY
NEW ZEALAND · NORWAY · SOUTH AFRICA · SPAIN · SWEDEN · SWITZERLAND AND U.S.A.

1961

duces ilding pecial or the eason thine.


AND.

U.S.A.





PUMPS



If you have a pumping problem involving any commercial fluid, it is worthwhile contacting us. BROOKE PUMPS will supply SUDS and COOLANTS to Machine Tools. They will also handle PAINT, SILICONE FLUIDS, EDIBLE OILS and FATS, TAR, DIESEL OIL, or INK to name a few of their successful applications. BROOKE PUMPS are used on a variety of HYDRAULIC SYSTEMS and in FORCED FEED LUBRICATION of MACHINE TOOLS. Write for brochure GP.4/7/61

FOR FULL TEST DETAIL on all standard types, illustration and description of important specia models send for our BROCHURE ON BROOKE PUMPS

THE BROOKE TOOL MANUFACTURING CO. LTD.

WARWICK ROAD, BIRMINGHAM 11. Tel. Victoria 2323

Telex 33313


KEARNS


of Broadheath
wish you a
Merry Christmas
and all the best for
1962



H. W. KEARNS & CO. LIMITED BROADHEATH Nr. MANCHESTER
Horizontal Surfacing, Boring & Milling Machines







Ryder does it this way...

Ford use the standard RYDER No. 8 VERTICALAUTO with double autohandling to produce two components per cycle. Here is a system that gets right to the heart of higher overheads, providing the production scope of special equipment on a standard machine.

RYDER VERTICALAUTOS suitably adapted for automatic handling can cut your production costs too.

THOMAS RYDER & SON LIMITED, TURNER BRIDGE WORKS, BOLTON, ENGLAND.

See Ryder


about automatics and auto-handling

RHODES.


HYDRAVERSAL SHEARS



The unique patented 'scissors' action



The rake of the top blade is inclined upwards towards the fulcrum of the 'scissors', giving progressively increasing pressure.



The shorter the cut the greater the capacity of the shears; heavy cropping operations can be done.

cuts any of these ...







SLABS

PLATES



SHEETS

WILL DO THE WORK OF SEVERAL DIFFERENT KINDS

OF SHEARS— COSTS LESS THAN ANY ONE OF THEM!

A unique feature of the 'Hydraversal' Shears is the progressive increase of capacity throughout the stroke, so that cuts of increasing thickness can be taken as the width of cut diminishes. The hydraulic drive makes overload impossible—an insurance against the damaging effects of misuse and overload. Cuts of extreme accuracy can be taken—vou can shave with these shears!

with this lowcost investment you can revolutionise your shearing techniques...

The versatility of these shears abolishes the need for several types of special purpose machines—releasing space and capital for other purposes.

Write for descriptive literature.

RHODES
HYDRAVERSAL
SHEARS

JOSEPH RHODES & SONS LIMITED

WAKEFIELD . ENGLAND Telephone: 2756 (3 lines)


LONDON Norfolk House, Laurence Pountney Hill, E.C.4. Telephone Hanslon House 7746-7747



IN THIS NEW WILLSON II' GAP BED LATHE ...

Here is a thoroughbred, embodying the characteristics conferred by sixty years' experience of lathe production and the employment of the very latest development in modern manufacturing techniques. The WILLSON I lin. is the latest addition to a distinguished range, designed and built for the high performance which will maintain and enchance the world-wide reputation of a famous name in lathes.

Write for full details.



44 ILLUV

OVENDEN SHALIFAX . ENGLAND

HALIFAX 5844/5









... just two of the range of Behr-Manning Information Leaflets available on Coated Abrasives ... and too useful to miss. These handy sized leaflets can help you, for example, on your choice of belts for offhand polishing, on your choice of contact wheels, on the application and advantages of developments in contour polishing and grinding, and on some of the problems of disc grinding. The photographs, charts and information they contain will help not only to improve your finishing processes but also to streamline your production. Put your name on our mailing list for future leaflets as they become available and send for these now—it's well worth your while.

1. OFFHAND BELT FINISHING RECOMMENDATIONS. 2. CONTACT WHEELS AND HOW THEY WORK. 3. 4 & 5. CONTOUR POLISHING AND GRINDING. 6. DISC GRINDING-PROBLEMS. 7. LUBRICATION.



Coated Abrasive Division, WELWYN GARDEN CITY, HERTFORDSHIRE · Telephone : Welwyn Garden 23484 (15 Lines)

* Registered Trade Mark of Norton Company, U.S.A.





work to fine limits

with



'Eclipse' hacksaw blades and other tools are made by James Neill & Co. (Sheffield) Ltd. and are obtainable from all tool distributors.





MORE AND MORE ARE TURNING TO



11" SWING LATHES


THOUSANDS in use in Great Britain and throughout the World!

- * SLIDING, SURFACING AND SCREWCUTTING LATHE
- * ALL GEARED HEADSTOCK GIVING SPEEDS RANGING FROM 39-1500 r.p.m.
- * TYPE LOO PRECISION TAPERED SPINDLE NOSE
- * FEED BOX GIVES 62 PITCHES AND 7 FEEDS FROM -0004 in.-- 024 in.
- * CAMLOCK TAILSTOCK
- * BEDWAYS AND SLIDES PRECISION GROUND
- * HARDENED BEDWAYS **OPTIONAL EXTRA**

manufactured within the KERRY GROUP by KERRY'S (Engineering) CO. LTD GRANGE ROAD, LEYTON, LONDON, E.10



Sales Office: WARTON ROAD, STRATFORD, LONDON, E.15. Telephone: MARyland 6611



HEAVY DUTY Vertical BORING & TURNING MILLS

with 5, 6, 8 or 10 ft diameter work tables

These incomparable machines are massively constructed for years of hard service. Accuracy and dependability are of the high order that industry has learned to expect of Broadbent Machine Tools. Notable features of these Boring and Turning Mills include twelve changes of speed and six changes of feed, controllable from either side of the machine; spiral bevel and spur reduction gears driving the work table; pendant control of rams and cross slides; and rapid power traverse with independent control of the two heads.

Please write for fully illustrated brochure.



manufactured within the KERRY GROUP by
HENRY BROADBENT LIMITED
SOWERBY BRIDGE, YORKSHIRE



961






manufactured within the KERRY GROUP by **OLDFIELD & SCHOFIELD CO. LTD** BOOTHTOWN, HALIFAX, YORKSHIRE



latest developments in modern lathe design.

Sales Office: WARTON ROAD, STRATFORD, LONDON, E.15. Telephone: MARyland 6611





SAWMASTER TYPE 10 B AUTOCUT HEAV Y-DUTY BANDSAW

For higher production

Infinitely variable cutting speeds, accurate blade guidance, faster cutting times, power lifting and lowering of sawframe, simplicity of operation and of blade changing mean higher production than with any comparable saw. The completely automatic cutting cycle facilitates repetition work.

the British made Bandsaw that is in the world's top class

-and the famous SAWMASTER Power Hacksaws 6" 8" 10" or 12" capacity



manufactured within the KERRY GROUP by QUALTERS & SMITH BROS. LTD BARNSLEY, YORKSHIRE







For counting units singly or in batches; for counting impulses per second, revolutions per minute, or the hours an engine has run; for counting up to a preset total or a predetermined length—for countless counting operations, SMITHS Industrial Division provides the appropriate, accurate instrument. Inset above is SMITHS Synchronous Hours Counter. By indicating running times of mains-powered equipment or machinery, this very robust instrument makes maintenance schedules easy to apply and helps to cut down stoppages. Let us send a Technical Representative to see you if you have a counting problem. You can count on SMITHS to solve it.

SMITHS range of counting instruments includes: Revolution Counters; Impulse Counters: Unit Counters; Lift Counters; Distance Counters; Pick and Loom Revolution Counters; Engine Service Counters; True Hours Counters: Synchronous Hours Counters A.C.; Engine Hours Meters D.C.; Predetermined Counters; Batch Counters.

SMITHS

INDUSTRIAL DIVISION

The Industrial Division of S. Smith & Sons (England) Ltd

Kelvin House Wembley Park Drive Wembley Middx. Phone Wembley 8888

When answering advertisements kindly mention MACHINERY.

☑ C.I.

ZBROJOVKA

Plano Miller FP16



TABLE 50in. x 140in.

- Wide range of Spindle Speeds enabling use of high-speed steel and comented carbide tipped cutters.
- Table speeds infinitely variable.
- Independent drive to individual headstocks, individual drive to table and headstock feeds.
- Automatic clamping of cross rail to guide-

ELGAR

EXCLUSIVE DISTRIBUTORS IN THE UNITED KINGDOM

MACHINE TOOL: COMPANY LIMITED

172-178 VICTORIA ROAD · ACTON · LONDON W3 · Telephone ACORN 5555
MIDLANDS SHOWROOM: 1075 KINGSBURY ROAD, ERDINGTON, BIRMINGHAM 24. Tel: Castle Bromwich 3781/2
Sole Scottish Agents: ANGUS & CRICHTON (Sales) Ltd., 7, Midland Street, Glasgow, C.I. Tel: City 4560

Finalised your VISITING DATE?

ELGAR
LATEST IN
TURNING
LATHES

FEBRUARY 5th-16th 1962



Display of the Latest EUROPEAN Turning Methods and Techniques

FEATURING:-

SEMI-AUTOMATIC TURRET LATHES
PROGRAMME CONTROL LATHES
SINGLE SPINDLE AUTOMATICS
HIGH SPEED THREADING
FINE TURNING LATHES
CAMLESS AUTOMATICS
COPY TURNING

ELGAR

MACHINE TOOL COMPANY LIMITED

172-178 VICTORIA ROAD - ACTON - LONDON W3 - Telephone ACORN 5555




When answering advertisements kindly mention MACHINERY.





If you design or manufacture plant and machinery



STANDARDISE ON WDS HANDWHEELS

and cut your costs

Save time in the drawing office. Save time and money by standardising on WDS handwheels in a range of sizes and types to meet most normal needs. Stop making your own handwheels. We can supply them in standard sizes quicker and cheaper. Immediate delivery from stock.




TOOL UP THE WOODSIDE


Write for a copy of this catalogue

Look through the list of handwheels and you'll see the advantages of standardlsing on WDS. The comprehensive selection of handwheels is a further addition to the WDS range which includes basic tooling accessories in many individual forms and sizes.

THESE COMPANIES ALREADY SAVE THE WOODSIDE WAY

Associated Motor Cycles Ltd., Bristol Siddeley Engines Ltd., Brook Motors Ltd., Coventry Gauge & Tool Co. Ltd., Daniel Doncaster & Sons Ltd., Dowty Group Ltd.; E.M.I. Electronics Ltd., Fisher & Ludlow Ltd., Folland Aircraft Ltd., Girling Ltd., Glacier Metal Company Ltd., The Hoffmann Manufacturing Co. Ltd., 1BM United Kingdom Ltd., Imperial Typewriter Co. Ltd., Ingersoll-Rand Company Ltd., Johnson & Johnson (Gt. Britain) Ltd., Kendall & Gent Ltd., Kodak Ltd., Lang Pneumatic Ltd., Napier Aero Engines Ltd., Newton, Chambers & Company Ltd. (Engineering Division)









WOODSIDE WORKS, NEWLAY, LEEDS 13 Tel: Horsforth 4251/5 Telegrams: Wooddle, Leeds Telex 55185



W046



OIL FOR BUSY BEARINGS Correct bearing lubrication is the first essential of efficient machine tool operation. Aiding you in this important phase of machine tool lubrication are the GENA range of lubricants. They comprise oils of specially graded viscosity ratings to lubricate all types of spindles, plain bearings and gear boxes.


To select the proper grade for your usage, write for Publication SP.178 "Machine Tool Lubrication", or ask our Technical Representative to call.

FLETCHER MILLER

Machine Tool Lubricants

GENA THE MACHINE TOOL LUBRICANT ALMARINE FOR ALL GREASE POINTS VETA FOR HYDRAULIC SYSTEMS GENERALLY

FLETCHER MILLER LTD · HYDE · CHESHIRE Telephone : HYDF 3471 (5 LINES) Telegrams : EMULSION, HYDE



Ten good reasons or increased production

- Increased horse-power available at the tool for high-speed machining
- Maximum speed and optimum performance held irrespective of load
- . Fligh duty cycle by rapid several of the table
- Controlled toware during reversal gives shockless drive to main transplasion with amount and return and deceleration
- Simplified circuits reduces syntenance
- All controls can be arranged adjacent to poperator, his to the up time and operator's fatigue
- Infini ely variable feeds ensure on finum mad
- Two rates of traverse of the tool box provide and the provide setting of the too
- Combines a new retem of control to the with a modernised arrangement of planer feet antrol for the tool box

AEI Electrical Equipment for Planing Machines

Make sure your PLANING MACHINES include the latest equipment, developed specially by AEI to give increased production. Equipments have been supplied to and proved by the leading British Planer Manufacturers.

A closed loop system, incorporating a magnetic amplifier of the flux resetting type, controls the variable voltage main reversing motor.

The angular rotation of the feed motor is selected by means of a magnetic integrator circuit.


Specialist Engineers are available for consultation.



Associated Electrical Industries Limited
Motor and Control Gear Division

RUGBY & HANCHESTER

Shell achievement



One of Shell's recent achievements in Industrial Lubrication has been to reduce the risk of skin trouble for machine operators. Until the new Shell Dromus range, most modern soluble cutting oils contained phenolic compounds, which can cause skin irritation. They were used as coupling agents between the actual oil and the emulsifier. On high-speed machines,

especially, the water evaporates and the emulsion concentrates. And that's when the trouble can start. Shell scientists found a better coupling agent, and made it work. And now, at

no extra cost, management can reduce working risks for their staff. Write for the book, 'Selecting Your Cutting Oils', to Shell-Mex House, London.



SHELL INDUSTRIAL OILS

Shell demonstration



Two clean, bright pennies are placed in beakers of oil, of equal performance level, one Shell Garia Oil 21, the other a conventional cutting oil containing sulphurised additives. After three hours at room temperature one penny is still bright and stain-free, the other heavily stained with black copper sulphide. The bright penny is from the beaker containing Shell Garia Oil 21, the blackened one from that containing the conventional oil. While these

were just pennies they could have been bronze bushes in your machine tools—stained in less than half a shift. Sulphur is essential in heavy-duty cutting oils. Special additives in Shell Cutting Oils protect your machine tools and yet allow the sulphur to do its job.

Write for the book "Selecting Your Cutting Oils" to Lubricants Department, Shell-Mex House, London, W.C.2.
DROMUS...PELLA...MACRON...GARIA



SHELL CUTTING OILS

ELECTRO HYDRAULIC CONTROL

- A. High Torque Power Units for attaching to the machine feed shafts.
- B. Control Cabinet for interlocked tracer control for one, two or threedimensional machining with combined 360° profiling with depth control.
- C. Electric Tracing Head for universal copying from models or templates.

For one, two or three-dimensional control attach the power units to the machine feed shafts for copy milling, turning or planing, 360° profiling and three - dimensional machining from models or templates.

MECHANICAL POSITION FEEDBACK

THREE HIGH TORQUE POWER UNITS



TABLE LEAD SCREWS.
LONGITUDINAL, TRANSVERSE,
VERTICAL.



CONTROL CABINET



TRACING HEAD

GIVES










RE-ENTRANT TURNING AT ONE PASS



HELICAL CAM-MILLING

ARMYTAGE

This illustration is the subject matter of British and Fereign Patents.

Full particulars sent on application

(TOOLS) LTD. FOUNDRY LANE, KNOTTINGLEY, YORKSHIRE


Telephone: Knottingley 2743/4

Telegrams: Armytage Bros., Kaostingley

POWER FEED VERTICAL HEAD

This plus feature makes the 'Test' miller the finest buy in universal milling machines today.





(No. 40 NS taper spindle, 10" throat), with 3 rates of power down feed in each direction, 4" traverse
Models 1 and 2 only. Price £425

send now for full details to:-



UNIVERSAL MILLING MACHINES

HERBERT WIDDOWSON & SONS LTD


Canal Street Works, Nottingham

Tel: 51891 (4 lines) Grams: TOOLS, NOTTINGHAM

The



SICMATIC



Automatic and Semi-Automatic Hydraulic Profiling Lathes

Specification

Bore of spindle			2∔in.
Spindle nose		5in.	A.S.A.
Max. swing over bed			151in.
Max, swing over sade	dle		9∄in.
Max. length turned			27-in.
Hydraulc traverse o	f cop	ying	4in.
Hydraulic feed of spindle	tails	tock	4½in.
Number of feed	rates	2.0	
copying slide			48
Max. tool pressure			300 lbs
Approx, net weight		5.0	000 lbs.

7

POINT FEATURES INCLUDE

- I Capacity.
- 2 Duplomatic Hydraulic Styems.
- 3 Hardened Bed Slideways.
- 4 Auto cycling up to six depths of cut.
- 5 Hydraulic tailstock for drilling and boring.
- 6 Uses template or existing component.
- 7 Eight models to choose from.

Basic price under £2,500.

QUICK DELIVERY

Daily demonstrations at our works



HERBERT WIDDOWSON & SONS LTD

Canal Street Works, Nottingham

Telephone: 51891 (4 lines) Telegrams: TOOLS NOTTINGHAM

961

g.




When answering advertisements kindly mention MACHINERY.

De

EXTRUDER MACHINE MAKERS

Specify

DERI SINE OIL HYDRAULIC MOTORS



Photograph by courtesy of Messrs. R. H. Windsor Ltd.

The R. H. Windsor AP30/115 Injection Moulding Machine incorporates three Deri Sine Motors to provide reliable and efficient operation.

The real test of an oil Hydraulic Motor is in heavy duty work and Deri Sine Hydraulic equipment is able to ensure reliable performance under the most gruelling continuous service on Injection Moulding and Extruding Machines. For example, where a breakdown may wreck a production schedule and cost money, manufacturers of the most modern machines take no chances—they specify Deri Sine

Backed by a superb range of Americandesigned Valves and Pumping equipment, Axial Piston and Vane type, Denison Deri can satisfy your most exacting requirements.







Denison Deri

DENISON DERI LTD. · VICTORIA GARDENS · BURGESS HILL · SUSSEX.

TELEPHONE: BURGESS HILL 85747/8/9



Facing Copy Lathes

MODELS

KH 45

and 55

With the UNICOP electronic-hydraulic two co-ordinate copying system for machining deep and difficult profiles.

The headstock and carriage are mounted on a common bed with two veeslides on which both can be traversed.


A single button on the pendant control panel sets the machine for use as a normal facing lathe without copying.

Available with infinitely variable spindle speeds and constant cutting speed control: Maximum turning diameter up to 55 inches,

SYKES MACHINE TOOL COMPANY LIMITED
Hythe Works, The Hythe, Staines, Middlesex. Telephone Staines 55474 (5 lines). Telegrams Sytool Staines



machine shop equipment





MILLING & DRILLING VICES-HEAVY DUTY

The range of J & S Machine vices covers all kinds from precision types for light grinding operations to heavy duty models for use on Milling, Drilling and Planing Machines.

The Milling Machine Vice, top right, is manufactured in two types, plain and swivel, in a variety of capacities.

An Angular Sine Vice is available for extreme precision work.



UNIVERSAL VICE FOR PRECISION GRINDING MACHINES

PRECISION BENCH CENTRES These Bench Centres are designed to ensure maximum rigidity and perfect alignment between tailstock centres, and the private of the

MANDREL PRESSES

J & S Mandrel Presses are designed to give maximum rigidity and remain solid under very heavy pressures.

Three sizes are available in the type illustrated. A more powerful type is also manufactured which provides extra powerful leverage. All types can be supplied as Bench or Column Models.

These Bench Centres are designed to ensure maximum rigidity and perfect alignment between tailstock centres. A bracket carrying a clock indicator or any other precision tool can be provided. They are manufactured in 11 sizes from 18½in. to 72in. between centres, and 8in. to 20in. diameter swing.

AVAILABLE FROM ALL J & S DISTRIBUTING AGENTS

A. A. JONES & SHIPMAN LTD., LEICESTER. Telephone: 823222. Grams: "CHUCK" Leicester

1961

e s i l i

ter






Fully Automatic Copying Lathe for quick change over



A Range of Centre Lathes

Tool room and Production Lathes with capacities up to 29in. swing over bed and 160in, between centres are available with or without copying equipment.



H.E.B. Type HN.250 Centre Lathe.

H.E.B. 'S' PILOT AUTOMATIC **MULTI-CYCLING COPYING LATHE**

Developed to make available fast, accurate copying methods and piloted feed features for small and medium quantity production. Special attention has therefore been paid to accessibility of setting mechanisms and speed of set up.

Whether for large or small batches, roughing and finishing, turning or boring, the 'S' Pilot can be applied to advantage. The machine has a swing over bed of 173 in. and swing over slide 113 in. Distance between centres is from 195in. to 393in. and maximum diameter of master 53in.


Write today for full details of this versatile copying lathe.

Sales and Service for the British Isles

DRUMMOND-ASQUITH LIMITED

Member of the Asquith Machine Tool Corporation

KING EDWARD HOUSE, NEW ST., BIRMINGHAM Phone: Midland 3431. Also at LONDON Phone: Trafalgar 7224 & GLASGOW Phone: Central 0922



'HYDRAX' GEAR HOBBING MACHINES

Lockheed semi-rotary slave units operate

- 1. The automatic hob shift and
- 2. The automatic loading—see close-up. These Lockheed units provide a greatly simplified and compact installation.

SEMI-ROTARY SLAVE UNITS BY

LOCKHEED PRECISION PRODUCTS LTD.

INDUSTRIAL HYDRAULICS DIVISION

SHAW ROAD, SPEKE, LIVERPOOL 24, ENGLAND

Telephone: Hunts Cross 2121.

Telex 62394.

Industrial Hydraulics Sales Engineers are at your service also at:

Automotive House Great Portland Street London, W.I

Tachbrook Road Leamington Spa Warwickshire

144 St. Vincent Street Glasgow C.2

Langham 2527 Telex 23446

Leamington Spa 2700

Telex 31549

Central 0291

Lockheed semi-rotary units are available both in single-vane form giving up to 300° movement, and in doublevane form giving up to 120°. Torques range from 1,270 to 1,100,000 lb./ins. at 1,000 p.s.i.

Below: the flange-mounted type, also available with foot mounting.



ONE OF THE **AUTOMOTIVE**

PRODUCTS GROUP

S


lg ees

0



New from


PELS



Square notching up to 3/8" thickness.




Mitre notching up to 5/16" thickness. Alternative to square notcher or supplied extra if both required.




Optional die saddle for punching into flanges of joists and channels.



Cropping up to $3' \times 3' \times 3/8''$ angles and tees.



Shearing up to 3/8" thickness.



MKC 10 STEELWORKER

A new model incorporating all welded steel frame, hand and foot operation, interchangeable notching head and cropper carrier, twin spindle 'down-holder' and even sturdier construction.

Angle and plate punching with solid die-to-floor support. Capacity—13/16" dia. through 3/8" or 11/16" dia. through 1/2".

From the Pels stable at a highly competitive price...

Write for full quotation and capacities.



HENRY PELS & CO.LTD.


32-38 OSNABURGH ST., LONDON, N.W.I

Telephone: EUSTON 4113 Cables: RYPELSNEH, LONDON


Model 14-5
The Finest, Most Versatile,
14" Screen Contour Projector Available.



Model 8
Economical 8" Screen Projector. Can be used in Horizontal or Vertical Position.




Model 14-2B A Precision Measuring, Bench Model Projector for All-Round Use.



EX-CELL-0

CONTOUR PROJECTORS* FIT YOUR OPTICAL GAUGING REQUIREMENTS


Model 30 A True, Heavy Duty Precision Measuring Projector with 30" Diameter Screen, and 12" Diameter Capacity



Model 14-6
with Plain Table for Production-Line Use with Chart-Gauges and Fixtures.



Model 14-6
with Measuring Table for
Production-Line or Limited
Tool Room Use.



Write for new edition of EX-CELL-O Contour Projector Booklet—Available Now!

SOLD AND SERVICED BY

EX-CELL-O GROUP SALES LIMITED

HALFORD HOUSE, CHARLES STREET, LEICESTER, ENGLAND.

TELEPHONE: LEICESTER 26791

TELEGRAMS: GROUPEX LEICESTER





Intomatically for surface broaching

Built for 'one operator' control, simple to operate and exceptionally easy to maintain, Lapointe surface broachers are essentially light on manpower.

Push button controls, automatic lubrication and other typically Lapointe features make these machines the best value in their class.

D



ROUNDNESS LESS THAN A TENTH ACTUAL: 8' 100.000



THANKS TO TIMKEN "DOUBLE ZEROS"

the advantages of "fine boring"

techniques are now universally accepted by progressive firms.

By running the cutting tool at its maximum cutting speed, time is saved, and accuracy and finish greatly improved. Hitherto such machines were limited to light cuts and fixed centre heights: this is no longer so. The Milnes Heavy duty boring machine has overcome these limitations, and has extended the application to a wide range of general engineering components either as one offs or batches of thousands. The machine is capable of roughing castings with cuts up to $\frac{1}{2}$ in. deep, and spacing accurately any number of bores. It is robust, dependable and easy to operate, and can be profitably employed in all modern machine shops.


MATERIAL: ALUMINIUM C.L.A. 10u° CENTRE LINE AVERAGE TEN MICRO INCHES (MILLIONTHS)

ACCURATION OF THE PROPERTY OF

produced by

Henry Milnes Ltd.,

INGLEBY WKS., ROSSE ST., BRADFORD 8, YORKS.
TELEPHONE: BRADFORD 41301
EST. 1858






HOPKINSONS LTD., VALVE STAKERS, HUDOERSPIELD.

961

ms. me uch

ine ion ing ing

LAMBERION 750 TON VERTICAL FORGING PRESS



Photograph by courtesy of The Austin Motor Company Limited

A fast working press suitable for mass production forging

An automatic feeder can be fitted

Write for full details to:

EUMUCO (England) LIMITED

26 FITZROY SQUARE · LONDON W1 · TELEPHONE: EUSTON 4651



Designing and Planning for Quality Castings

TAKE ADVANTAGE OF THIS FREE OFFER

Copies of this new bulletin will be sent free

on request, please write for:

Bill Designing and planning for Quality Castings.

using the Meehanite Recommended Procedures

These have been compiled for the guidance of designers, engineers and buyers in a recent bulletin. This publication contains useful and practical notes on Designing the casting, Selecting the metal, Choosing the pattern, and Planning for low-cost production. Readers of this bulletin will find it of value in obtaining high quality Meehanite castings.



MEEHANITE

THE INTERNATIONAL MEEHANITE METAL CO., LTD., EPSOM, SURREY





Making the NEW.

BW Automatic 35 TRANSMISSION


Churchill

MODEL H.B.A.
AUTOMATIC SIZING
INTERNAL
GRINDER

Churchill High Precision
Grinding Machines in
the 'Borg-Warner'
Plant

Engaged on finishing the bore and internal face of front wheel clutch cylinders this model H.B.A. automatic internal grinder is dependable for the rapid production of close limit

work.
There are CHURCHILL high precision grinders to cover every need.
Details of a machine for your own
work will gladly be sent on requeste



A Member of the B.S.A. Group of Companies

THE CHURCHILL MACHINE TOOL CO. LTD

BROADHEATH

HOME SELLING AGENTS

CHARLES CHURCHILL & CO. LTD

BIRMINGHAM and BRANCHES



MANCHESTER

EXPORT SALES ORGANISATION
ASSOCIATED BRITISH
MACHINE TOOL MAKERS LTD
LONDON, BRANCHES and AGENTS

It's New and Different!

DO NOT CONFUSE WITH WHAT YOU MAY HAVE SEEN BEFORE

VERALOY CLAMP TOOL for use on FISCHER COPY LATHE

POSITIVE TOP RAKE

ADJUSTABLE
CARBIDE TIPPED
CHIPBREAKER
DOES AWAY
WITH CHIP
GROOVE
GRINDING

INTERCHANGEABLE
TIP MOVES
FORWARD AFTER

HARDENED STEEL
REPLACEABLE TIP SEAT

REGRINDING

Constructed on the Veraloy Principle of Mechanical Clamping, this positive top rake tool will:

- 1 Do all that a brazed tool does;
- 2 Do away with chip groove grinding;
- 3 Save you no end of money in purchase and regrinding cost;
- 4 Save space in the Stores and the Workshop;
- 5 Double the life of your machines by reducing the load on it as compared with negative rake clamp or throw-away tools.

Standard Turning Tools on the same principle available.

Also tools for Copy
Lathes of other makes

VERALOY PRODUCTS LTD




BEECH ROAD . THE MARSH · HIGH WYCOMBE · BUCKINGHAMSHIRE Telephone: High Wycombe 2795-8.

Telegrams: Versloy High Wycombe

from 125 to 5 micro-inches surface finish

in one 5-second pass!



with the revolutionary

burnishing tool


- Finishes rough bored or turned surfaces (125 micro-inches and higher)
- to 4 micro-inches and lower. Feed rates of 8 to 12 inches per minute. Finishes any machinable metal . . . all sizes and shapes of surfaces. Adjustable for size control. Sizes in extremely small increments. In actual applications, controlled size changes of .000075in. are accomplished.
- Run thousands of parts without tool wear. No resetting or adjustment. No stones to replace, maintain or adjust. No operating skill required.
- Use tool in any standard shop equipment.
- Tool creates a condensed, compacted surface . . . smoother, harder,
- longer wearing.
 Saves as much as 90% in labour and tool costs.
 Results guaranteed! Tool in use by more than 1,000 leading companies

Sole manufacturers and distributors in the United Kingdon



BIRMINGHAM GAUGE CO. SOHO HILL, HANDSWORTH, BIRMINGHAM 19 Tel.: NORTHERN 3344









OIL SEALS

SUPER OIL SEALS & GASKETS LTD . BIRMINGHAM 30 FACTORY CENTRE KINGS NORTON BIRMINGHAM 30 Tel: KINGS NORTON 2041

When answering advertisements kindly mention MACHINERY.





Hydraulics

HYDRAULIC POWER PACKS



IN THEIR NEATEST FORM

THE 'MIDGET'

THE 'MINOR'

THE 'MAJOR'

THE 'MIGHTY'

Keelavite power packs provide a range of self-contained hydraulic power units suitable for many widely differing industrial applications. A large number of pumping capacities are available. All packs are so designed that the valves most suitable for the customer's requirements can be fitted. Standard units from the enormous Keelavite range are used.

KELLAVITE POWER PACKS ARE ESPECIALLY USEFUL-

... When you require a mobile hydraulic power unit. A caster mounted pack is ideal for operating a pattery of hydraulic liga and tools in intermittent use.

... when installing a remote control system. The pack may be located at a distance from the operated mechanism, particularly useful where explosive streampers are secondared.

... when size and weight restrictions are imposed.

Mount the pack alongside the machine and just couple up to the actuators.

	Name	Dimensions: less height of motor	Tank Capacity	Electric Motor H. P.	Pump Capacities
ı	The MIDGET	18" x 12" x 12"	74 gall.	up to 2	To
۱	The MINOR	30" x 16" x 16\"	20 gall.	up to 5	sult
١	The MAJOR	40" x 24" x 16\f"	50 gall.	up to 124	customer's
	The MIGHTY	40" x 24" x 24"	75 gall.	up to 25	requirements

introducing an entirely new Power Pack of which you will want details

The KEELAPACK

A desk top console which houses the complete hydraulic system. Hydraulic and electrical controls neatly contained in minimum space. Custom built from standard components.



THE RECOGNISED AUTHORITY ON NYDRAULIE POWER TRANSMISSIO

For full details write to

KEELAVITE

KEELAVITE HYDRAULICS LTD

KEELAVITE COMPLETE HYDRAULICS

a complete range of units
 thirty years of hydraulic experience
 and a service that means success



SPEEDICUT

PROGRESSIVE TEETH

With the pitch of teeth progressing from 29 to 18 per inch along its length, this blade takes advantage of the natural sawing action. The fine pitch lead-in reduces the effort required and minimises breakage, so often met when blades of incorrect pitch are being used. Supplied in SPEEDICUT High Speed Steel and DIE-HARD Alloy Steel in 10° and 12° sizes at the same price as normal blades.

FIRTH BROWN TOOLS LIMITED
SPEEDIGUT WORKS CARLISLE ST. EAST SHEFFIELD



HIGH SPEED AUTOMATIC INDEX ON

Product of INDEX-WERKE K.G. HAHN & TESSKY Esslingen-Neckar, Germany



Drilled, countersunk both sides and tapped complete



EXAMPLES (**
OF PRODUCTION TIMES
Scale: Actual Size
B = Bross · S = Steel
A = Aluminium



Sole Agents for Great Britain and Northern Ireland

GEO. KINGSBURY & Cº

(MACHINE TOOLS) LTD
4-6 MILNER STREET, CHELSEA,
LONDON S.W.3.

Middlesex County Council chooses Regent

DUAL FUEL DIESEL ENGINES AT MOGDEN RUN ON URSA P FOR 20 YEARS

At the main sewage purification works at Mogden, Middlesex, eleven 650 b.h.p. and one 250 b.h.p. dual fuel engines have averaged 18½ hrs. daily running time since December 1935. For more than 20 years the engines have been lubricated by URSA P lubricating oil.

The plant, which is one of the largest in Europe, deals with approximately 80 million gallons of sewage every day.

LOW ENGINE WEAR

After 25 years of constant use, the engines were examined recently. Engine wear was found to be extremely low. Crankshafts are now being reground and the bearings are all cleaning up at .020". There was no ring sticking and no measurable wear on the blower bearings or step-up gears. All parts

were remarkably clean and free from carbon and varnish deposits. Coking up on the oil-cooled pistons was virtually nil — Ursa's high oxidation stability means carbonisation is reduced to the minimum. In addition, Ursa's demulsifying properties allow the water to be easily centrifuged out.

CONSISTENTLY HIGH QUALITY

Regent Ursa P is used for these engines because it maintains its consistently high quality and because it keeps its high level of flashpoint, a desirable feature for all dual fuel engines.

URSA P is one of a wide range of diesel engine lubricants supplied by the Regent Oil Company to meet the needs of modern industry.



961

1-

n, ie

el al

el



PYROMANCY IS THE

SECRET BEHIND OUR HIGH

SPEED AND ALLOY TOOL STEELS

Pyromancy... as if you didn't know... is simply the prediction of future events by observing the glare of a fire, and as a technique goes back before the Court of King Arthur.

We at Balfour's, who are up to every trick in the book, short of diabolic possession, can most certainly attribute the exceptional quality of our High Speed and Alloy Tool Steels to the scientific exploitation of the technique. Manufacture based on quality control from the melt to the finished bar, disc or ring ensures a predictably lengthy and profitable future for every Balfour tool steel product. And if that isn't Pyromancy, we don't know what is!

ARTHUR BALFOUR

ESCOMATIC Coil-fed

Model DS 2

5/32" Capacity, without Turret

Model D4


5/32" Capacity, with 3-Spindle Turret

Model D 6


1/4" Capacity, without Turret

Model D 6 R

1/4" Capacity, with 4-Spindle Turret







- No part-off pip
- No wastage of bar ends
- Smaller floor space requirements
- Long production runs between feeding, allowing more machines per operator.

HAHN & KOLB (Great Britain) LTD. 243-245 Horn Lane, ACTON, LONDON W 3, Tel.: ACORN 8938/9

ESCOMATIC



Mod. D 6 R







invest in quality

use





ENERGOL INDUSTRIAL LUBRICANTS

Distributed by

THE POWER PETROLEUM COMPANY LTD

De

When location difficulties occur, an external circlip fitted to the bearing may be the solution.

ball journals are versatile and adaptable

Where some thrust is combined with radial loads, a ball journal, with correct internal clearance, can take it.


Quite often, opportunities to simplify and improve the efficiency of a design are missed — because the versatility of Rom ball journals has not been fully exploited. Their possibilities are not always appreciated. This is understandable since ball bearings themselves are an involved design study.


Further possibilities arise with notched rings for increased journal capacity, special manufacturing controls for high speeds, and special materials for high temperatures.


Next time you have a bearing problem, remember that Ransome and Maries Technical Department would be pleased to effer you expert, impartial and confidential advice.

RANSOME & MARLES BEARING COMPANY LIMITED NEWARK-ON-TRENT





















The SAIMP range of fine milling machines

There's a model to suit your needs in this fine range of proven millers - built to the finest limits and beautifully finished. From Italy's leading machine tool factory. Write now for prices and delivery . . .

SOLE SELLING AGENTS for the U.K.



MIDLAND 9221/2

BRANCHES: LONDON: BRISTOL

When answering advertisements kindly mention MACHINERY.


TAYSON R 513

The Sand Martin (COTILE RIPARIA) is a summer visitor to the British Isles less familiar than the Swallow and House Martin, being a rarer bird and preferring a habitat remote from that of man. The nest it builds is a slight affair of grass builds is a slight affair of grass and feathers deposited at the end of a gallery bored in a sandy bank. Although ill equipped for boring, the Sand Martin makes a speedy job of the business and the tunnel, which he a slight unward ille which has a slight upward tilt for drainage, can be anything up to nine feet long.


The Cotile Riparia is efficient. . . but bardly a

Illustrated right is the Richards "ELECTRABORE" Travelling Column Floor type Horizontal Boring, Facing, Milling, **Drilling and Tapping** machine, supplied with or without traversing spindles from 34" to 8" diameter. A power operated rotary type table can be supplied.

GEORGE




HORIZONTAL and VERTICAL BORERS produced by GEORGE RICHARDS & CO. LTD., however, are unsurpassed for precision, speed and adaptability. Continuous research and development keep RICHARDS borers way ahead of all others.



& CO. LTD. water & **BROADHEATH-ALTRINCHAM-CHESHIRE** Sole Agents: ALFRED HERBERT LTD., FACTORED DIVISION, COVENTRY



The LEYLAND MOTORS GROUP choose



This Walter Automatic Cutter Head Grinder is installed at Leyland Motors Ltd. for the accurate grinding of crank pin milling cutters.

There are also nine Walter machines in use at the Standard Motor Company Ltd.

Face and periphery of blades with connecting radius, ground in one continuous operation.

Capacity 4—40" diameter. Also available Model AMS. 500 for cutters 31—20" diameter.

EXCLUSIVE DISTRIBUTORS IN THE UNITED KINGDOM

AMS. 1000

ELGAR

MACHINE TOOL COMPANY LIMITED

172-178 VICTORIA ROAD ACTON LONDON W3 - Telephone ACORN 5555 MIDLANDS SHOWROOM: 1075 KINGSBURY ROAD, ERDINIGTON, BIRMINGHAM 24, Tel: Castle Bromwich 3781/2 SOLE SCOTTISH AGENTS: ANGUS & CRICHTON (SALES) LTD., 7 MIDLAND STREET, GLASGOW C.1. TELEPHONE: CITY 4560



TRANSFER PRODUCTION ON ANY PRESS OR PRESS BRAKE WITH LOW COST!

Standard UNIPIERCE and UNICROP Units cut the cost of tooling and get you into production faster.

At a fraction of the usual cost our standardised units make possible multi-operation transfer work on all types of Presses and Press Brakes. Full details and technical help without obligation. Catalogue UP/1002/M4 on request.

REDMAN TOOLS & PRODUCTS LTD.

Box. No. M.4. Gregory's Bank, Worcester.

Tel: Worcester 26933 (6 lines) Telex 33594 'Grams. Redtools, Worcester. Northern Agents: Dunmac Ltd., 123 Hope Street, Glasgow C.2. Tel: Central 0421/2.

REDGA **Drilling Machines**

Arboga drilling machines are available as bench, pillar or radials in capacities from in. to 2in.

A comprehensive range of equipment is available for both Tool-room and production-shop use. Illustrated is model E 210, 3in. capacity. Incorporates motor of special design giving practically constant torque at all speeds.

ALL ARBOGA PRODUCTS ARE SOLD THROUGH THE FOLLOWING DISTRIBUTORS:

Buck & Hickman Ltd. Glasgow **CENtral** 7174 A. Douglas Co. Ltd. Monks & Crane Ltd. High Wycombe High Wycombe 4390 London **HAMpstead** 9624 Monks & Crane Ltd. Birmingham **STEchford** 4051 Joseph Pugsley & Sons Ltd. Bristol Bristol 56037 J. & H. Smith Ltd. Victa Engineering Co. Poole, Dorset Lychett Minster 578

KAVANAGH O'MOORE & Co., LTD. 1a, ALDRED ROAD WEST HAMPSTEAD - LONDON - N: W-6

Telephone: HAMpstead 6548 Telegrams: Toledoro Cent London"



1961

the ion nits pes nical on D.



NEAT CUTTING OILS BROACHING OILS GRINDING OILS TAPPING OILS HONING OILS SOLUBLE OILS (Emulsion types Translucent types) DRAWING OILS HYDRAULIC OILS (Including Houghto-Safe Fire-resistant types) QUENCHING OILS TEMPERING OILS LUBRICATING OILS AND GREASES

PORTRAIT ...

of a happy production manager

He relies on the recommendations of Edgar Vaughan. The selection of Cutting Oils and Coolants for the machine shop has long ceased to bother him. He asserts that the economy of leaving this to Vaughans has proved itself in hard cash, as reflected in lower production costs, i.e., better finish, faster machining times, economy in use, reduced labour costs and longer tool life.

You, too, can obtain the same economic production at lower costs by leaving the selection of cutting oils and coolants to Edgar Vaughan. Ask for an experienced representative to call. Advice and recommendation is supplied without obligation.



LEGGE STREET - BIRMINGHAM 4

Works and Depots at : Birmingham, London (Southall), Manchester, Liverpool, Bristol, Glasgow



An interesting Brochure entitled 'Metal Cutting Oils' is available on request; on your business heading, please.



In association with the Houghton group of companies all ever the world.

SCHAERER


SIMPLICITY IN

for maximum production . . .

Model HK401 Automatic Copying Lathe



The SCHAERER Model HK401 is the latest type of Automatic Copying Lathe developed from a long line of successful predecessors. Care has been taken to provide utmost rigidity of bed and copying slide, whilst at the same time allowing for easy chip disposal. The separate feed drive to the copying slide is of the steplessly variable type for maximum efficiency. A completely automatic work cycle including speed and feed changes can be selected, and additional plunge-cutting or longitudinal turning slides incorporated as required. In the set-up shown, one conveyor loading unit is serving two copying lathes. Automatic set-ups such as this offer great savings in production, but not all components lend themselves to similar treatment. Please send us drawings and we will gladly advise you.



THE SCHAERER MANUFACTURING PROGRAMME.

The world-renowned Schaerer Standard and Production Lathes with the familiar underslung bedways are built with centre heights from 8½ in. to 15½ in. and centre distances from 30 in. to 20 ft. Due to the extra heavy construction, full advantage can be taken of the high horse power available. Production Lathes are supplied with or without automatic cycle. An automatic version type HPD is shown opposite.

In addition, Schaerer build Automatic Copying Lathes type HK as illustrated above and special machines for non-concentric copying, used in the manufacture of glass moulds and extrusion dies. A wide range of special equipment ensures unsurpassed economy and output from Schaerer Lathes. The Schaerer profile copying unit is also available as a separate unit for fitting to all types of Lathes with centre height from 8in. to 12in.

961


121

AUTOMATION

SCHAERER

... at lowest cost

Model HPD Automatic Production Lathe



LONGIT TURNING ALENCE CUTTING

ST. 1 1 2 + 2 + 7 E

AND FACING

ST. 1 1 2 + 2 + 7 E

TOTAL TRAVERSE

END OF CYCLE

The HPD Production Lathe is an entirely new machine based on the well-known SCHAERER Standard and Production Lathe. The keynote of the machine is its simplicity of operation and the short changeover times, factors which ensure economical use even on small batches when more complicated and costly production machines cannot be justified. The automatic work cycle is selected on a simple plug-in panel incorporated in a separate switchgear cabinet. No electronic control gear is used. The range of work which can be produced on the HPD machine is very great indeed, Please consult our Specialists who can advise you in detail.

Write or phone for further details:

SOAG MACHINE TOOLS LTD

JUXON STREET LAMBETH LONDON SEIL . RELIANCE 7201

SOAG

HOW DO YOU MEASURE A TENTH?














Gauge scale—actual size

. . . the drawings call for 'tenth' tolerances. Your customer says the parts are wrong. You have a heap of rejects. How do you prove who's right?

Look at the scale above. It is the measuring scale incorporated in all PARNUM gauging equipment. The tenths are easy to read, aren't they? But more than that—they repeat. Not to just a tenth—to a hundredth, .0000 lin. No customer—or anyone else—can tell you you're wrong if PARNUM equipment says you're right.

Whatever your gauging problem, some unit in the PARNUM range will solve it.

STANDARD GAUGE COMPLETE WITH PROBE £80

Please send for further information to

PARNUM GAUGES LTD., BRACKNELL. BERKS
Bracknell 1831

- ACCURATELY YOURS-

PARNUM)

GAUGING EQUIPMENT

When answering advertisements kindly mention MACHINERY.

1961

ays

ove

ed

ad.

t a

ne

ays

ge

80

perfect drill point geometry for accurate holes

THE GRINDING PROCESS—to simplify setting a chart provided gives angles 'A' and 'T' for various diameters. Flexibility of method allows point geometry to be varied as desired. The amount of metal removal can be pre-set by simple fine-screw adjustment to the axial position of the drill. Grinding is effected by a simple reciprocating movement.

for sharpening righthand 2-flute drills, parallel or taper shank, $V_{16}^{-}-V_{2}^{n}$ (1.5 - 13mm) dia.

MAXIMUM ECONOMY IN WHEEL REPLACEMENT Replacement grinding wheels can be cemented on to the non-expendable backplate by wheel suppliers at moderate cost. A 60-grit wheel supplied with the machine covers the whole range of drill sizes dealt with. For continuous grinding of the smaller sizes of drills an 80-grit wheel can be supplied.



Brochure describing the machine and method on request.

Enables perfect drill points to be produced, to suit any requirements, speedily and with unskilled labour, No collets or guide bushings required. Soft wheel — does not burn drill — no coolant necessary. Stepped drills and drill reamers handled equally well.

DRILL POINTING MACHINE

B.S.A. No. O

Motor: § h.p. 2850 r.p.m.

Weight: (with pedestal base & dust extraction unit) 476lb. (216 kg)

Floor space occupied: 33" × 33" × 33" × 52" high (840 × 840 × 1320 mm).

B.S.A. TOOLS LIMITED BIRMINGHAM

GHAM 33 ENGLAND

B.S.A. Drill Pointing Machine No. 8 Motor:

h.p. 2850 r.p.m.

Cables: HADRICUT BIRMINGHAM TELEX 33-207.

SOLE AGENTS U.K.: BURTON GRIFFITHS & CO. LTD. MONTGOMERY STREET BIRMINGHA
Telephone: VICTORIA 2351

AD No SO


When answering advertisements kindly mention MACHINERY.



BURS


- for machining and finishing any material from plastics to hardened steel
- These tough tools are perfectly balanced with sharp, accurate tooth forms
- Very fast cutting rates are possible with 'PROLITE' BURS
- The working life is 50 to 100 times that for steel burs
- Available in fine, medium or coarse flutings, also diamond cut and file cut, in a wide variety of shapes and sizes
- An efficient REGRIND-ING SERVICE is available

Write for our catalogue of 'PROLITE' BURS



Export Sales: MUREX LIMITED (Powder Metallurgy Division), RAINHAM, ESSEX, ENGLAND. Telephone: Rainham, Essex 3322. Telex: 28632. Telegrams: Murex, Rainham-Dagenham Telex.





FROM 62" TO 162" HEIGHT OF CENTRES

These machines are built out of a long tradition of craftsmanship to the highest modern standard of design, productive capacity and precision. There are sizes and types to meet your own needs. Ask us to send you details.

MANUFACTURERS: D. MITCHELL & CO. LTD., KEIGHLEY, YORKS
Telephone: Keighley 4283

London and Export Office:

MORRISON, MARSHALL & HILL LTD., TOWER HILL, LONDON, E.C.3
Tel: Royal 1461 Cables: Morimil, London Grams: Morimil, Fen London

CHRISTMAS GIFTS FOR ENGINEERS

A "MACHINERY"
TECHNICAL BOOK
IS A THOROUGHLY
PRACTICAL GIFT
...IT WILL BE
TREASURED BY
CONSTANT DAY-TODAY USE LONG
AFTER FESTIVITIES
ARE FORGOTTEN

Write for a Book Catalogue with details of MACHINERY'S Plan for Payments by Instalments.



	Cash C.O.D.	Instal Price		Cash C.O.D.	Instal Price
MACHINERY'S HANDBOOK	96/-	106/-	COPY TURNING	20/-	22/-
ELEMENTARY MATHEMATICS	12/6	13/9	INGENIOUS MECHANISMS (3 Vols.)	160/-	176/-
MACHINE TOOLS	52/6	58/-	METALLISING HANDBOOK	42/-	46/-
CENTRE LATHE WORK	20/-	22/-	FUNDAMENTALS OF PRESS TOOL DESIG	N 12/6	13/9
JIG & FIXTURE DESIGN	50/-	55/-	INDUSTRIAL LUBRICATION PRACTICE	75/-	82/6
MACHINE SHOP TRAINING COL	JRSE		DIE DESIGN & DIE MAKING PRACTICE	80/-	88/-
(2 Vois.)	75/-	82/6	BROACHING	20/-	22/-
PIPE & TUBE BENDING	47/6	52/-	DIE CASTING DIE DESIGN	20/-	22/-
EXTRUSION OF METALS	45/-	50/-	CAPSTAN & TURRET LATHE PRACTICE	20/-	22/-
MACHINE TOOL RECONDITIONING	120/-	132/-	TOOL & CUTTER GRINDING	20/-	22/-
PRACTICAL ENGINEERING METROL	OGY 30/-	33/-	GEAR RATIO TABLES	46/-	50/6
MACHINERY'S	YELLOW	BACKS	(Over 70 Titles) 5/6 each		

A. E. or beauty has many a small and an arrange of				
You can buy MACHINERY'S BOOKS by CASH, C.O.D., or INSTALMENTS.	To MACHINERY, National House, 21 West Street, Brighton, I. Please send me			
All titles sent (U.K. only) ON APPROVAL.	pay FULL CASH, or by INSTALMENTS, as stated above.			
NO DEPOSIT.	Name Signature			
Write for complete Catalogue.	Address Position			
	Firm			



MACHINE SHOP EQUIPMENT LTD.

ECTORS: W.R.L. WARHOCK (CHARMAN) E.M. POULRES. (MANAGING) H.F. JO

TELEPHONES VICTORIA SAZES 6086 (5 LINES)

SPENSER STREET LONDON · S·W·I

CABLES EMESETOOL. SQWEST LONDON

Grinding Machine Users-

Dear Sir,

We think you will agree that the necessity for keeping coolant clean in grinding and similar machining operations has been amply Various methods of achieving this are demonstrated in recent years. Tarious methods of conferring one are in current use and all pay dividends, to a lesser or greater degree, in better workpiece quality and in operating and other economies.

Now, the simplest and most effective means of coolant clarification is provided by centrifugal force - and the MSE "3C" Centrifugal Coolant Clarifiers provide the simplest and most effective means of putting that force to work. The plain facts are that "3C" Clarifiers continuously remove both magnetic and non-magnetic matter from either soluble or straight cutting oils, constantly returning over 99.9% clean coolant to the machine tool. All this without filters, papers or mess and with no loss of coolant strength. And that, we submit, is about as near to Utopia as any machine operator is likely to get!

The enclosed leaflet goes into the facts rather more fully. If, after reading it, you have any questions to put or would like us to show just what sort of "3C" Clarifier installation would best suit your own specific requirements, please telephone us or drop us a line. One of our specialists would be glad to call on you to discuss the matter - quite without any obligation on your part of course.



MACHINE SHOP EQUIPMENT LTD.

Spenser Street, London, S.W.1. Telephone: VICtoria 6086

CASTROL INDUSTRIAL OILS



18 Station Transfer machine working on parts for new Anglia gearbox

Hydraulic Oils

The Hyspin range of fully additived hydraulic oils combines all those features which mean optimum performance and long life. There is also a fire-resistant grade of Hyspin which is highly efficient and economical in use.



CASTROL INDUSTRIAL LTD., CASTROL HOUSE, MARYLEBONE ROAD, LONDON, N.W.I.

When answering advertisements kindly mention MACHINERY.

.1.



MACHINERY is registered as a newspaper at the General Post Office and is published every Wednesday by The Machinery Publishing Co., Ltd. The name is a registered trade mark.

All rights of reproduction and translation are reserved by the publishers by virtue of the Universal Copyright and International Copyright (Brussels and Berne) Conventions and throughout the World.

C The Machinery Publishing Company, Limited, 1961.

LONDON OFFICE

REGISTERED OFFICE, EDITORIAL, SHALL AND CLASSIFIED ADVERTISEMENTS DEPARTMENTS AND ENQUIRY SUREAU

CLIFTON HOUSE 83-117 EUSTON ROAD. LONDON, N.W.I

Telephone: Euston 8441/2 Telegrams: Machtool, Norwest, London

HEAD OFFICE

SUBSCRIPTION, ADVERTISEMENT, SERVICE,

NATIONAL HOUSE 21 WEST STREET. BRIGHTON, I

Telephones Brighton 27356 (4 lines)



Telegrams: Machtool. Brighton

NEW YORK: 93, Worth Street

PARIS: 15. Rua Blaue

Managing Director: LESLIE R. MASON Editor: CHARLES H. BURDER Chief Associate Editor: P. A. SIDDERS Associate Editors: A. P. LIPSCOMBE, L. WILSON, G. W. MASON, S. C. POULSEN, R. E. GREEN, A. W. ASTROP, A. J. BARKER Editorial Representatives: F. W. HERRIDGE,

J. J. MARKLEW PRICE PER COPY:-One shilling and three-

SUBSCRIPTIONS:—Inland and overseas, 52 shillings per annum (and pro rata), post free. Cheques and Money Orders should be made payable to the Machinery Pub-lishing Co., Ltd.

Ishing Co., Ltd.

ADVERTISEMENTS:—Copy for displayed advertisements, if proofs are required, should reach the Brighton office 21 days in advance of publication. Rates on request. Small (classified) advertisements can be accepted, space permitting, at the London office up to Wednesday, for publication on the following Wednesday. For rates, see p. 190.

Blocks are held at advertisers' own risk; no responsibility for loss is accepted by the publishers.

ACHINERY

A JOURNAL OF METAL-WORKING PRACTICE & MACHINE TOOLS

Vol. 99, No. 2561

December 13, 1961



COPIES PRINTED			
CERTIFIED DISTRIBUTION	1,293	per	week
CERTIFIED PAID DISTRIBUTION	9,827	per	week
Copies sold at full price	9,594	per	week
Cobies sold at reduced brices	233	per	week

CONTENTS

						PAGE
Matched Machining or Selec	tive Asser	mbly?				135
Principal Articles (For ab	stracts s	see n	ext pa	ge)		
WERRA Camera Production Some Applications of Fractu Machine Tool Building in Br The Butler Machine Tool	red Race ritain: Co., Ltd.	Ball Mile	Thorn	. Halif		135: 136:
T.I. Helicoidal Bearing Continuous Broaching Root	Forms of	n Tur	bine Bl	ades		137
The Rodolite		::				137
Delapena Induction Hardeni					• •	138
7th European Machine Tool (For detailed list of exhibit				**		138
Making the New Borg-Warn	er Auton	natic 7	Fransm	ission		139
Osromatic Vibratory Finishi	ng Mach	nes		* *		139
Huron/Ferranti Tape-contro	ned Milli	DE IVI				
A Tube-bending Die Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw	ocess ic Shears			. 11	••	136 136 137
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli	ocess ic Shears					136 136 137
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District	ocess ic Shears					130 130 137 140
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District	ocess ic Shears vards	::		12		130 130 137 140 140 140
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South	ocess ic Shears vards	::		::		130 130 137 140 140 140 140
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South Boulton & Paul Fabricating	ocess ic Shears vards					136 136 137 140 140 140 140
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South Boulton & Paul Fabricating Scrap Metals Report	ocess ic Shears wards	::				136 136 137 140 140 140 140 141
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South Boulton & Paul Fabricating	ocess ic Shears wards					130 130 140 140 140 140 141 141
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South Boulton & Paul Fabricating Scrap Metals Report Machine Tool Share Market	ocess ic Shears vards	::				130 137 140 140 140 140 141 141
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South Boulton & Paul Fabricating Scrap Metals Report Machine Tool Share Market Prices of Materials	ocess ic Shears vards	::				136 136 137 140 140 140 141 141 141
Sinter Seal Impregnation Pre Rhodes Up-cutting Hydrauli M.T.T.A. Design Course Aw News of the Industry Manchester and District Machine Tool Orders The South Boulton & Paul Fabricating Scrap Metals Report Machine Tool Share Market	ocess ic Shears vards	::				136 137 140 140 140 140 141 141

Abstracts of Principal Articles

WERRA Camera Production ... P. 1352

This fourth article on the activities of the East German firm of VEB Carl Zeiss, Jena, is concerned with the production of the WERRA range of 35-mm. cameras at their Eisfeld works. After briefly describing the range of cameras, some details are given of the factory, which provides employment for about 500 people and has a floor area of some 50,000 sq. ft. Operations carried out on the pressure die cast aluminium camera body, supplied from the South Works in Jena, include turning, boring and facing of the lens-mounting surfaces on a Zeiss RB 34 instrument lathe. The film plane surfaces are then semi-finish milled, and several mounting boss faces on top of the casting are also milled. Drilling, reaming and tapping operations are carried out on a line of bench drills, with the operator seated on a wheeled stool for ease of movement. Diamond-turning operations performed on camera parts are designed to provide decorative bright surfaces, and special lathes are provided. Special machines are also used for engraving symbols on lens and other adjustment rings, five at a time. During final assembly, milling of the film plane surfaces to ensure accurate positioning relative to the lens-mounting face, is performed on two machines, on one of which a diamond tool is employed. (MACHINERY, 99—13/12/61.)

Some Applications of Fractured-race Ball Bearings P. 1361

Fractured-race ball bearings offer two main advantages, namely that they can be arranged to incorporate more balls than can be carried by a conventional bearing—and consequently their load carrying capacity is increased—and, as the result of the increased number of balls, the life of such a bearing is extended. The design of bearings made by Split Ball Bearing, Lebanon, N.H., U.S.A., is discussed, also applications in connection with light power tools and transmissions for motor vehicles. (MACHINERY, 99—13/12/61.)

The Butler Machine Tool Co., Ltd., Mile Thorn, Halifax . . . P. 1365

Founded by James Butler in 1868, the Butler Machine Tool Co., Ltd., have specialized in the building of planers, shapers and slotters since 1917, when the first part of the Mile Thorn works was built. The works have been extended at various times, the latest addition being the new machine shop, completed in 1950. A

new drawing office was built on to the adjacent office block in 1959. The works are on a site of 5½ acres, and are sub-divided into departments, which specialize in the building of different types of machines, on a batch production basis. Extensive use is made of unit construction, and the illustrations accompanying this article show some typical machining and assembly operations in connection with building machines in the company's range. (MACHINERY, 99—13/12/61.)

The Rodolite P. 1377

Known as the Rodolite—a name derived from the expression "rod of light"—the system here described employs circular diffraction gratings and enables inspection of the main elements and movements of machine tools to be made to a high accuracy. The application of the instrument is described in connection with checking the table and hobbing slide of a large gear hobbing machine. (MACHINERY, 99—13/12/61.)

A previous article was concerned with the machining of pressure die cast aluminium alloy castings employed in the hydraulic control valve assembly for the new Borg-Warner automatic transmission, and further operations on these castings are here considered. Side faces on castings of two sizes are finished by grinding at a single set-up with a wide-faced wheel. The joint faces are then finished on a wheel-type flat honing machine on which the castings are held in a carrier plate and simultaneously oscillated and rotated. Some other operations on the smaller casting, including face milling and drilling and tapping, are also described. (MACHINERY, 99—13/12/61.)

Index to Exhibits at the 7th European Machine Tool Exhibition Described on pages 1383—1391 of this Issue

	PAGI
Bammesberger special-purpose machines	1389
Bohle tape-controlled milling machine	138
De Buyser crankshaft grinding machine	139
E.R.O.P. Microbanc surface grinder	139
Lindner type LB 12 optical jig boring machine	138
Morando type VK 25 vertical turning and boring mill	138
Northing type V K so vertical turning and borning min	
Oerlikon type F 60 chucking lathe	138
Schiess type RFw 10 horizontal gear and pinion hobbing machine	138
Calmaide Course Anna Birth 40 St 4	
Schneider Creusot type RUP 48 Y 4 surface grinder	138

Contributions to MACHINERY

If you know of a more efficient way of designing a tool, gauge, fixture, or mechanism, machining or forming a metal component, heat treating, plating or enamelling, handling parts or material, building up an assembly, utilizing supplies, or laying out or organizing a department or a factory, send it to the Editor. Short comments upon published articles and letters on subjects concerning the metal-working industries are particularly welcome. Payment will be made for exclusive contributions.

W EDITORIAL

Matched Machining or Selective Assembly?

Although machine tools are now available which enable very close tolerances to be maintained on both internal and external work diameters in quantity production, where exceptionally fine limits are specified for the fits or clearances between mating components it is sometimes expedient to forego the advantages of interchangeability. In this connection it may be noted that even if limits as fine as ± 0.0001 in. are held on each of two components, the amount of clearance or interference on assembly may vary by as much as 0.0004 in.,

which may be unacceptable.

To overcome the problems associated with the attainment of very exacting fits, two methods can be employed, either of which may yield very satisfactory results in certain circumstances, namely matched machining and selective assembly. In principle the former method is as old as engineering, and dates back to the time when the skilled lathe operator machined a shaft to suit a previously finished bore, aided only by calipers. This technique has since been greatly refined, and on certain machines it is now possible to grind an external surface to match a bore to a remarkable degree of accuracy, on a quantity basis and under automatic control. For this purpose, it may be recalled, the mating component is placed on a gauging mandrel adjacent to the machine, and while grinding is in progress the diameter of the male part is continuously compared with that of the bore, and the operation is automatically terminated when the required relationship has been obtained.

An example described recently in Machinery affords an indication of what can be achieved by this procedure under production conditions. In this particular instance, a 19-mm. diameter part is ground to suit the bore of a sleeve, and it is specified that the clearance between the assembled parts must not vary by more than 0-00004 in. To maintain this relationship combined with interchangeability, it may be noted, it would be necessary to hold limits of ± 0.00001 in. on both

parts.

Selective assembly is, of course, based on the principle that if a large number of parts is produced within a tolerance band that can be maintained without undue difficulty, the choice of size afforded will permit selection to achieve almost any desired refinement of fit with a particular mating component. If it is necessary to rely on

manual gauging the task may be very tedious and may demand a considerable degree of skill, but with modern gauging equipment it is possible to segregate components into a number of size grades, in each of which the diameters vary by only a very small amount. With the mating parts correspondingly classified, assembly can then be carried out almost as easily as it would be if all the parts were interchangeable.

One effective application of selective assembly is concerned with the plungers for fuel injection pumps which, as is well known, must be a very close fit in the bores. To achieve the required results, one manufacturer segregates plungers of any particular nominal size into 20 grades, each covering a diameter range of only 0.00002 in. Obviously, highly developed equipment is necessary to enable parts to be separated automatically with this degree of discrimination. At the same time it will be evident that it is considerably easier to arrange for such segregation than to attempt to produce parts to the grade tolerance.

Attention was drawn to other accomplishments in the field of automatic gauging for selective assembly in a paper presented by Mr. A. W. Wiseman to the American Society of Automotive Engineers. One gauging machine described, enables gudgeon pins to be inspected at the rate of 3,750 per hour. These pins are rotated at the gauging station, and are checked for roundness and taper as well as for size. The tolerance on diameter is 0.0003 in., and gudgeon pins which are accepted are simultaneously classified in steps of 0.0001 in., a memory system being incorporated to ensure that they are subsequently separated into the three classes when discharged.

For the corresponding piston the problem is complicated by the fact that it must be checked and identified for selective assembly both with a gudgeon pin and a cylinder bore. The machine employed handles 1,500 pistons per hour, and at the first station both ends of the gudgeon pin bore are inspected by means of pneumatic gauges for size, roundness, and taper. Again, there are three size steps, each of 0.0001 in., and the size classification of each accepted piston is automatically stamped on the head. Subsequently the pistons are checked for skirt diameter, skirt taper, and ovality, and for this diameter there are 10 size grades, in steps of 0.00025 in. Fach accepted

(Continued on page 1410)



WERRA Camera Production

Methods Employed by VEB Carl Zeiss, Jena, at the Eisfeld Plant, Thuringia, East Germany

By R. E. GREEN, Associate Editor

ONE OF THE ACTIVITIES to which the East German firm of VEB Carl Zeiss, Jena, has turned during recent years, on instructions from the Government, which decided that all manufacturing companies should produce consumer goods of some kind, is the production of cameras. This development was mentioned in the first of this series of articles*, and some details of the type of camera which was designed, and of the methods employed in its production, are given here.

THE WERRA RANGE OF CAMERAS

Named after the river Werra, a tributary of the Weber flowing through Thuringia, the camera takes 35-mm. standard motion picture film, and the original design was such that a total of six variations could be made, all incorporating many common components. In its simplest form, the camera has a non-interchangeable Tessar f/2-8, 50-mm., lens with a front-mounted shutter and simple view-finder, and is known as the WERRA 1. The shutter is wound by partial rotation of a collar surrounding the lens mount, and a lens hood is provided, with a multi-start thread which screws into this collar, to afford protection when the camera is not in use.

There is also a Werra 2, which is similar but incorporates a built-in exposure meter bought out from VEB Feingeratewerk Weimar. The Werra 3 has no exposure meter, but is arranged to take interchangeable lenses and is fitted with a wide-base coupled range-finder, and in the Werra 4 all

the features so far enumerated are included. The latest version of the camera, the Werramat, is similar to that shown in the heading illustration, and has a built-in mechanism whereby the action of adjusting the exposure meter to the prevailing light conditions automatically sets the lens diaphragm and shutter to the values required for those conditions.

The most elaborate design is known as the Werramatic and resembles the Werramat, with the addition of the coupled range-finder from the Werra 3 and 4 cameras. With the Werramat and the Werramatic cameras, two small mirrors, set in the view-finder window, reflect images of the settings of the diaphragm and shutter into the eyepiece at one side. In addition, the indicator pointer of the exposure meter is read while looking through the view-finder, so that all the essential information for setting the controls to suit the lighting and the distance of the object to be photographed is readily available without taking the camera away from the eye.

Since the complete series of Werra cameras was planned before production began in 1953, it was possible to arrange for the use of many standard parts, of which there are 227 in all, out of the 1,086 components required for the full series. As a result of careful design of individual components, and the provision of multi-purpose tooling, jigs and fixtures for only 336 individual parts are required for the production of the entire range of cameras. Of the camera components, some 39 per cent are made by turning or milling operations, and a further 20-5 per cent by press shop methods. Of the remainder, 24 per cent require combina-

[•] MACHINERY, 99/652—20/9/61, 99/842—11/10/61 and 99/1296—6/12/61.

tions of stamping and machining operations, 8 per cent are of plastics or rubber parts, 5 per cent are optical parts, and 3.5 per cent are pressure die

castings.

These castings, which include the body, back, range-finder base-plate, lens carrier, and film stage, are produced in the die casting foundry at the South Works, mentioned in the second article of the series. Plastics and rubber parts are supplied from the main works at Jena, and lenses and other optical parts from the Saalfeld plant, but most of the machining operations, and the assembly of the cameras, are carried out at a small factory in the town of Eisfeld, about 50 miles from Jena, near the border with West Germany.

THE EISFELD CAMERA WORKS

Originally built in 1923 as a toy factory, the building in which Werra cameras are produced was used as a school after 1933 and subsequently as a factory for the manufacture of aircraft instruments. In 1945, the factory was dismantled—as were many others—by the Russians, and the building stood empty until 1952, when Zeiss began to use it as a tool-making and small machine shop. The manufacture of Werra cameras began there in 1953, and production has increased year by year and reached a total of 50,000 in 1960. Mainly

of wood construction, for which material is readily available in the district, the factory has a floor area of about 50,000 sq. ft., and a productive area of 42,400 sq. ft., on two floors, and is at present being extended.

In addition to cameras, the factory produces 35-mm. slide projectors of 100- and 375capacity, assemblies for 35-mm. sound - film projectors, and toy diesel engines for model ships and aircraft. Some 500 people are employed in the works, including a small number who attend a vocational training centre to learn instrument-making, and of the total, about 200 are women. The factory is operated on a single

shift and 45-hour week, except for the machine shop and surface-finishing department, which have limited capacity and are run on a double-shift basis. Wage scales are basically similar to those quoted in the first article of the series. As the employees come from a rural area, they are characteristically diligent, and it is stated that their outputs are slightly higher than those maintained by workers in other Zeiss establishments. The proportion of administrative staff appears to be higher than in this country, and this applies throughout the organization. Some 45 people are employed solely on inspection and testing of components, sub-assemblies and complete cameras. Design of cameras is carried out at Jena, and there are only a few qualified engineers at Eisfeld, who are concerned with the design of tooling and method studies.

MACHINING OF CAMERA BODIES

Bodies for all the cameras in the Werra range are machined from a common pressure die casting of Silumin aluminium alloy containing up to 13 per cent of silicon. The first operation on such a casting, which is received in the fettled condition, is carried out on the Zeiss RB 34 instrument lathe shown in Fig. 1. Details of the design of this lathe were given in the second of the articles previously published, and this particular machine is




Fig. 1. Turning, boring and facing operations on Werra camera bodies are carried out on this Zeiss RB 34 instrument lathe, on which the casting is held in a face-plate type fixture




Fig. 2. Close-up view of the face-plate fixture on the machine in Fig. 1, showing details of the locations and clamping mechanisms

fitted with a face-plate fixture to hold the work, as seen in the close-up view, Fig. 2.

From this close-up view it will be seen that the casting is loaded with the front face outwards, and it is located by the rear side faces and supported in brackets at each end. For endwise location, a spring-loaded plunger enters a cast slot in one face and can be retracted, for loading and unloading, by means of a lever A. Two swinging clamps which are pivoted to the supporting brackets, and connected to the air-operated draw-bar of the machine

spindle, are applied to the ends of the casting. On the side opposite the locating plunger, the

casting is steadied by a screw with a knurled head B, in a swinging lever which is pivoted in a slot in the faceplate. This lever is lowered, and secured in position by a sliding pin at the right, before the

screw is turned to bring the end into contact with the casting. A spindle speed of 1,200 r.p.m. is employed, and the operations are performed manually. Tools in the turret are moved by means of the handle C, Fig. 1, for facing cuts, the travels being limited by stops on the drum which come into contact with the retractable abutment D. Turning and boring operations are carried out by traversing the turret saddle with the required tool in position and the corresponding stop held against the abutment D.

One internal and two external diameters are machined at this operation, also three faces, the largest of these faces being employed for location of the casting at later stages.

Next, the contact faces of the film gate are semifinish milled on the simple vertical machine shown in Fig. 3, built by the small private firm of Bernhard Paatz, in nearby Zella Mehlis. In the fixture provided, the casting is positioned by the central bore in the front wall, which is engaged with a circular projection, angular location being taken from one long side which is held in contact with an abutment. At the centre of the circular projection there is a vertical draw-bar which can be raised and lowered by movement of the cranked lever E, and a




Fig. 3. Machining of the surface of the film gate at the rear of the camera body is performed with a two-tool cutter on this Paatz vertical milling machine


Fig. 4. The surfaces of four bosses on top of the camera casting are machined flat with a combination of conventional and special milling cutters on this Paatz machine, which employs a spindle housing similar to that on the machine in Fig. 3

slotted washer is inserted beneath a nut on the bar before the latter is pulled down to clamp the casting.

The spindle of the machine is driven at 3,000 r.p.m., and is fitted with a head in which two cutters are mounted at a radius of 1 in. Manual feed is applied to the machine table by the lever at the left, through rack and pinion. An allowance is left on the surfaces milled, which are eventually finished in one plane within 0.01 mm, (0.0004 in.). Additional operations are performed on the small horizontal milling machine shown in

Fig. 4, which has a spindle housing of similar design to that on the previous machine, but arranged horizontally, and a similar table. In the fixture, the casting is held in a nest and is located by a register which engages the bore in the front face.

For clamping, there is a horizontal bar carried on two plungers, which are connected by a second bar



on the far side of the fixture wall. Force is applied to this bar by a cam when a lever F is moved to turn a vertical shaft. Subsequently, screw-operated pads, at the ends of the fixture, are applied to the arcuate projections at both extremities of the camera body in order to provide additional clamping. The milling spindle, which, again, is driven at 3,000 r.p.m., carries a plain cutter at the extreme

end to machine a range-finder mounting boss. Another boss for the range-finder is machined by a fly-cutter in a reduced diameter portion of the body G.

The main portion of the body G carries three cutter blades which machine an annular mounting boss for the exposure meter mechan-



Fig. 5. The stool on which the operator sits is arranged to move on grooved rollers along rails set in the floor to enable drilling and other operations to be completed without rising



Fig. 6 Some of the machines in the line in Fig. 5 are equipped with multi-spindle heads. A simple box jig holds the casting and is roughly located beneath the spindles by angle fences

th

an

th

in

W

ap

SU

th

m

lo

of

d

fa

tl

ism, and in a third portion on the far side, there is another single cutter for machining a fourth boss near the end of the casting. Manual feed is applied to the table by means of the lever in the lower foreground.

Drilling, reaming and tapping operations are next carried out on a line of bench drills as seen in Fig. 5, the operator being provided with a stool which is

supported on a steel framework. The framework has a grooved roller at each corner, and the rollers run on rails of semi-circular section, set in the floor. With this arrangement, the operator can move freely from one machine to the next to perform the

required sequence of operations, without rising. According to the design of the particular camera for which the batch of castings is intended, the number of holes on which operations are performed varies from 21 to 30, and they are in five sides of the casting.

Box-type drilling jigs are employed, and simple angle-fences are provided at each drilling machine—several of which have only a single spindle—to locate the jig approximately in the required position. One of the jigs employed is seen in Fig. 6, opened to show the method of loading. After placing the casting in the box and engaging the central bore in the front face with



Fig. 7. Diamond-turning, to produce a bright polished surface on certain camera components, such as the lens hood, is carried out on a lathe fitted with special bearings, to permit a speed of 2,800 r.p.m.

Fig. 8. Special Zeissbuilt machine for engraving lens mounts and setting rings


the register, the lid, which has an elongated hole for the hinge pin at one end, is swung over and a reduced portion at the other end is engaged in a slot in the opposite wall. Pressure is then applied to the previously milled film gate surfaces, by a captive plate of suitable shape, which is thrust down by a cam.

Each of the machines is fitted with electric micro-switches whereby the spindle-driving

motor is automatically started as the quill is lowered, and switched off when it is raised. Some of the drilling machines, as seen in Fig. 6, are fitted with multi-spindle adapters, and in addition to drills, taps and reamers, the tools may include spot-facing cutters. With all the initial machining operations completed, the bodies are passed to the surface treatment department where they are covered externally with a black plastics, wear-resistant coating, which is cured in an autoclave at a temperature of 140 deg. C.

Other surface treatment applied to the bodies includes anodizing of the internal surfaces, which are subsequently dyed black. The castings are then returned to the machine shop, and the range-finder mounting faces are finish-machined, also two edges on the ends are milled for decorative purposes. Other light alloy components which are handled on conventional machine tools with simple set-ups, are subjected to similar treatment. Certain surfaces on the cover surrounding the lens mount, known as the cocking ring, and on the lens-setting rings, the lens hood, the exposure counting ring, the re-winding mechanism and the tripod nut are precision turned with diamond tools to produce bright surfaces.

After diamond-turning, the surfaces are coated with transparent hard varnish to prevent deterioration of the finish. Diamond turning is carried out on lathes provided with special spindle bearings, an example being shown in Fig. 7, set up for operations on lens hoods. On this machine, the



spindle runs at 2,800 r.p.m., and the turret carries three tools, one of which is diamond-tipped and is employed to turn the diameter adjacent to the multi-start thread at the larger end. The component is held on an expanding mandrel and the feed movements are applied by hand levers.

feed movements are applied by hand levers. In addition to the Zeiss RB 34 instrument lathe, which is widely used in the factory, there is an automatics shop equipped with single-spindle machines by Skoda (Selson Machine Tool Co., Ltd.), MAS (Elgar Machine Tool Co., Ltd.), and Index [Geo. Kingsbury & Co. (Machine Tools), Swiss-type automatics built by Ruhla (William Watts, Ltd.), and Strohm (Adam Machine Equipment, Ltd.) are also installed. An interesting method is employed in the production of facetype gears for the drive between the film speed setting lever and the exposure meter mechanism on certain cameras. The gear teeth are produced on the face of the bar by a cold-forming operation before the remainder of the machining is completed. There is a small press shop for such parts as the top cover, which is produced from brass sheet, and other operations carried out in this shop include the shaving of the film gate aperture in the body casting, on a hydraulic press.

ENGRAVING OF SETTING RINGS

Cameras such as that shown in the heading illustration, also the less complicated types, require a variety of engraved rings showing the




Fig. 9. Close-up view of the work-table and spindle head of the machine in Fig. 8, showing details of the individually-motorized spindles and the indexing mechanism for the workpieces

values of the shutter speed and diaphragm opening, and depth of focus, for example. For the production of such rings in the required numbers, special machines have been designed and built, one of which is seen in Fig. 8. Designed for the engraving of symbols on five rings at a time, the machine has a vertically-moving slide, carrying

five separate, self-contained engraving spindles. These spindles are driven at a speed of 9,000 r.p.m. by integral fractional horse-power motors, which are supplied from a frequency-changing unit at the rear of the machine.

A close-up view of the spindles is given in Fig. 9, and each is fitted with

a collet chuck to hold the engraving tool. Provision is made for both coarse and fine vertical adjustment of the individual spindles, and any spindle can be raised and held in the retracted position, by a lever on the outside of the housing, when it is not in use. A lever at the left, actuated through a linkage from the operator's position, enables the slide carrying the spindles to be lowered and raised at the start and finish of an engraving sequence.

The table beneath the spindles can move longitudinally and transversely

on ball slide-ways, and it is connected through a pantograph linkage to a stylus-holder, seen at the right in Fig. 8. A bracket on the bed holds a grooved table on which the patterns for the symbols to be engraved are supported, and the pantograph is arranged to provide a reduction between the stylus and the table movements of 8 to 1. The



Fig. 10. Finish-machining of the lens plane surfaces at the back of the camera is carried out with a diamond-tipped fly-cutting tool, running at 12,000 r.p.m., on this special machine

Fig. 11. A similar operation to that seen in progress in Fig. 10 is performed on those cameras to which interchangeable lenses are to be fitted. The cutter of this machine runs at 3,000 r.p.m.

table carries the indexing workholder, seen in Fig. 9, which has five parallel shafts to carry the workpieces. For angular location in the final assembly, each of these ring-type components has a slot, and this slot is engaged with a pin on the shaft of the engraving machine.

gh f ye etd set g


A C-washer and nut are employed to hold each piece in place on the shaft, and the table can be adjusted by means of compound slides to bring the work to the required position relative to the points of the engraving cutters. Each of the shafts of the work-holder is connected by a worm-

drive to a longitudinal shaft extending for the length of the unit. The right-hand end of this shaft carries a hand-wheel for adjustment of the angular positions of the workpieces, and at the left-hand end is keyed an axially-sliding bush with a worm thread, which is protected by a cover of transparent plastics material.

At the left in Fig. 9 can be seen a horizontal ballend lever, which is supported from a bracket and is urged downwards by a spring. On the underside of the lever there is a V-shaped projection, which enters notches of similar form in the crest of the worm thread, to hold the shaft in angular positions corresponding to those at which characters are to be engraved in the workpieces. This arrangement enables larger locating grooves to be employed, for characters which are closely spaced, than would otherwise be possible, the threaded bush being displaced axially, as required, to bring different portions of the thread crest beneath the lever.

SLOW-MOVING CONVEYOR LINE FOR ASSEMBLY OPERATIONS

Assembly of the Werra camera is carried out almost entirely by women who are specially trained for the work. As far as possible, components are made up into sub-assemblies which can then be stored until they are required for a particular type of camera. Examples of such sub-assemblies include the range-finder and view-finder units, the



film drive, including the transport roller, and the exposure meter mechanism. Inspection of each unit and any necessary adjustments are carried out at the appropriate stages.

Line methods have been adopted for the final assembly, with slow-moving conveyor belts passing the bench positions at which the individual operations are performed. Camera backs and bodies are fed on to this belt in containers which hold five of each, and the sub-assemblies are built into them in stages. At one stage, a facing operation is performed, at which the distance from the lens flange to the surfaces over which the film runs (the focal plane), is held to limits of ±0·0004 in., and the Zeiss-built machine for carrying out this operation on the Werra 1 and 2 cameras is seen in Fig. 10.

This small machine incorporates an engraving-spindle motor similar to those employed on the machine in Fig. 8 and 9, which is run at 12,000 r.p.m. The casting is positioned from the lensmounting flange, which was machined earlier, and is held in place in the simple block-fixture by means of a lever-operated draw-bar passing through the lens aperture. It is traversed past the diamond-tipped single-point tool in the spindle by means of the lever held in the operator's right hand, the rear end of which is pivoted on the machine base.

Another machine, employed for the corresponding operation on the more complicated variations of the basic camera, is shown in Fig. 11, and is similar to that in Fig. 3. Cameras faced on this machine are of the interchangeable lens type, and each body is fitted with an adapter having an internal face against which a locating face on the lens mounting is pressed when the lens is installed. The fixture provides for supporting the partly-assembled camera by this internal face, and it is clamped in position by a lever-operated draw-bar, as before. The spindle is driven at 3,000 r.p.m., and has a single carbide-tipped fly-cutter.

In addition to visual checks, and operation of the shutter and film winding mechanisms at the end of the assembly track, each shutter speed is checked individually. Prestor shutters of the rotary blade type, made by VEB Kamera & Kinowerke, Dresden, are employed, and have speeds to 1/750 sec. Inspection and adjustment of the coupled range-finders, on those cameras to which they are fitted are also carried out, before the finished cameras are passed to the packing and

despatch departments.

METALPHOTO NAME AND INSTRUCTION PLATES. Aluminium nameplates and instruction plates can be rapidly produced by the use of the Vari-Typer Headliner type composing machine in conjunction with the Metalphoto nameplate process which has been introduced by R. H. Lighting, Ltd., Cobham, Surrey. The Vari-Typer Headliner

machine provides for photographic composition, with automatic development, in a wide range of type styles on either film or paper, the latter being used where lithographic equipment is available. Alternatively, the film positive itself can be used to make a reverse plate, or contact positives. Enlargement or reduction of type can readily be obtained with accuracy and sharpness.

The Metalphoto plates, of aluminium, are available in a wide range of sizes and thicknesses, and the material has a hard anodized layer with photo-sensitive properties. A lithographic negative bearing the necessary information is placed in contact with the Metalphoto plate, which is exposed, developed, fixed, and washed in the same manner as a photographic print. The processing can be carried out under usual darkroom safe-light conditions, and to seal the image permanently in the anodized layer, the plate is boiled in water for 30 min.


Huron/Ferranti Tape-controlled Milling Machine

At the 7th European Machine Tool Exhibition, held recently in Brussels, the Huron tape-controlled milling machine shown in the accompanying close-up view was included among the exhibits of Ferranti, Ltd., Ferry Road, Edinburgh 5. This heavy-duty machine, built by Leon Huré, Paris, (Rudolph Carne & Co., Ltd.) has been specially adapted to suit the Ferranti system, which gives 3-dimensional control. Re-circulating ball screws are provided for moving the table longitudinally on the knee, also the knee vertically, and the spindle head transversely.

The machine has a working capacity of 59 by 27 by 19 in., and feed rates to the longitudinal and transverse motions are steplessly variable up to 15 in. per min. For the knee motion, the maximum feed rate is 7½ in. per min. The universal spindle head can be swivelled through 360 deg. in each of two planes which are mutually inclined

at 45 deg.

Two workpieces are shown clamped on the table, the lower being a large plate in which a peripheral groove was machined under 2-dimensional tape control, also various irregularly-shaped areas. At the centre may be seen a die block, in which a cavity was machined with a ball ended cutter, under 3-dimensional tape control.



A close-up view of a Huron/Ferranti tape-controlled milling machine at the 7th European Machine Tool Exhibition

Some Applications of Fractured Race Ball Bearings

A BALL BEARING with its outer race intentionally split may offer advantages to the designer where it is required to support maximum radial loads, in addition to thrust loads from either direction, with single-row construction. In external appearance, the split type closely resembles a conventional but there are internal differences. Fractured-race ball bearings in all precision grades are made by Split Ballbearing, Lebanon, N.H., U.S.A., a division of Miniature Precision

Bearings, Inc.

e-r-y-

to

al

d

to

al

in ed

The advantages of these bearings result from the fractured-race manufacturing process. By the simple (patented) expedient of splitting the outer race, the raceway can be completely filled with balls without the need for a loading slot or counter-When a retainer is required a one-piece precision-machined component of any desired material may be used. Such a retainer is pierced with as many radial holes as the web section between the pockets will allow, to enable a maximum complement of balls to be inserted, which usually fills about 90 per cent of the raceway. By comparison, only about 60 per cent of the raceway can be filled when bearings are assembled by the conventional method whereby the inner race is moved eccentrically against the outer race to permit the insertion of balls.

Because ball bearings made by the split-race technique contain approximately 40 per cent more balls than conventional bearings of the same envelope dimensions, they are capable of carrying proportionately greater loads. Static load-carrying capacity of a particular size of bearing, as cal-culated by most formulæ, is proportional to the number of balls it contains. Dynamic load-carrying capacity is proportional to the number of balls

to the two-thirds power.

Since the gain in service life of a bearing is proportional to the cube of the increase in dynamic load-carrying capacity, the increased ball complement will extend this life considerably. ample is afforded by an aircraft installation where bearing failure in an auxiliary generator resulted when a 100 per cent overload was imposed on the equipment. Although the bearings were designed for a 1,000-hour life, failure often occurred after only 30 hours of service. Corrective action—the installation of bearings of similar type of the next

closer tolerance grade, and with 2-piece machinedbronze retainers—did not appreciably extend

operating life.

Split ball bearings were then installed. At first, they were used on only a few generators. they had proved to be satisfactory, the bearings were employed on all units in aircraft of that type. Theoretical calculations, using conventional ballbearing formulæ, showed that with the new bearing (with the same approximate external dimensions) there should be an increase in life of 700 Under test they operated for 1,000 hours (with a 100 per cent overload as required by the specification) with no sign of failure. Bearing speeds on the idler gear-shaft were 2,000 r.p.m. and on the generator drive-shaft, 6,000 r.p.m.

LOW-TORQUE CHARACTERISTICS

A large ball complement ensures significantly lower starting and running torques under conditions of heavy loading. The additional number of balls reduces the unit load per ball with the result that the ball-to-race contact is reduced, and a closer

approximation a true rolling surface is obtained for any given load.

to

The maximum complement may be used with precision one-piece retainers of bronze, phenolic - impreg nated linen (Fig. 1), or stainless steel, at high speeds. Where a retainer cannot be used in some of integrally shielded designs, alternative undersize balls can be inserted in raceway to permit speeds up to 4,000 r.p.m. in most cases, and as high



Fig. 1. A fractured race bearing with a one-piece retainer is recommended for lowtorque applications




Fig. 2. Examples of Dyna-Flyte replacement distributor plates for motor vehicles. Each incorporates a split-race thinsection ball bearing

as 6,000 to 8,000 r.p.m. for many applications.

SMALLER LIGHTER MACHINES POSSIBLE

Often, when a smaller bearing can be used, the overall dimensions and weight of a machine or an assembly can be reduced. Compactness may be a very important advantage since unnecessary

size represents an expense to the machine manufacturer during production, handling, and storage.

It was found possible, for example, to reduce the diameter of handoperated air-powered ratchet wrenches by 50 per cent, because of the smaller size of the fractured-race ball bearing used. These wrenches are made by the Gardner-Denver Co., Quincy, Ill., U.S.A., and the smaller size enable the field of application to be extended as compared with that possible with a larger tool.

The use of the thin-section bearing permitted the designer to maintain the dimensions of an internal cam dimension—a critical component of the tool upon which the bearing is mounted—while reducing the diameter of the housing. The bearing employed is a standard precision-ground, thin-section, double-row shielded type. This pre-lubricated bearing has the same envelope dimensions as a standard needle

bearing which could not be used for this application because of the thrust load involved. The bearing is subjected to a 1,000-lb. load (radial and thrust) when the pneumatically powered wrench tightens a nut to the full rated torque. When running free, the speed of the tool is 2,000 r.p.m.

In replacement parts, bearings must often be







Fig. 3. Stages in the assembly of a double-race split ball bearing

designed to fit within a small space. One group of such parts consists of precision ball - bearing distributor plates tended to replace those used in standard motor vehicle ignition distributors. These Dyna-Flyte units (Renberles Products, Detroit, Mich.), examples of which are shown in Fig. 2, incorporate thin-section ball bearings of split design. For this application bearings must sometimes be made to an internal tolerance of only 0.0001 inch. Temperature variations also severe-from -50 to +200 deg. F.and continuous vibration and shock loads are part of the normal operating environment.

d-

et

of

ce

re

).,

er

n

at

ng

 $_{
m in}$

m

of

is

a-

ng

n-

w

ed

oe

le

is

d.

ad

ly

ed

ol




Fig. 4. Double-fracture ball bearings of this type can be assembled in positions where solid-race bearings could not be employed

The method of assembling a double-race split ball bearing is of interest. Referring to Fig. 3, after an inner race has been inserted in the assembly fixture, a full complement of balls for the lower race-way is brought up as seen in the view on the left. Next, the ball carrier is retracted, and the fractured outer race is added, as seen in the central view. Another full complement of balls is now brought up and allowed to fall against the inner race. Pressure is then applied to the outer race which causes the fracture to open. As a result, the upper row of balls is permitted to fall into place in the raceway. At the same time, the outer race is caused to slide over the lower row.

BEARINGS FOR USE IN CORROSION CONDITIONS AND AT HIGH TEMPERATURE

When they are to be subjected to corrosive conditions, 440C stainless steel is recommended as a material for fractured-race bearings. The one-piece retainer can be made from a material which is inert to the particular conditions involved. Retainers of K-Monel silicon-iron-bronze, phenolic resins, and various stainless steels have proved satisfactory for certain applications.

Auxiliary equipment required by the chemical, process, and aircraft industries must often operate at high temperatures. With temperatures not exceeding 450 deg. F., no serious difficulties are

encountered with conventional 52100 bearing steel. For higher temperatures up to 900 deg. F. splitrace bearings can be made from materials such as 440C stainless steel and the M series of tool steels.

Lubrication is, of course, a considerable problem at these higher temperatures. When necessary, for certain applications, split-race ball bearings can be run dry, but the anticipated life is then drastically reduced. In some instances dry lubricants have given satisfactory results.

Contrary to what might be expected, the split race is not a weak feature of the bearing. In practice, this type of bearing performs as if the race had not been fractured at all. No special precautions are required as regards mounting or load application (with the possible exception of pressfitting the outer race under conditions of heavy

When these bearings fail as a result of fatigue, or are intentionally tested to destruction, they fail in the same ways as do conventional bearings. Of the many theories advanced, one is most commonly accepted. When the outer race is fractured, the resulting surfaces have series of jagged points. On closing the outer race, the jagged points fit into corresponding depressions in the opposite faces of the fracture, and the former smoothness of the race is fully restored.

In the double-fracture split bearing, as shown in Fig. 4, both the inner and outer races are split to

permit rapid replacement, for example, at the centre of a shaft or crank. The parts are held together by means of tapered sleeves and screws, and the entire bearing—comprising the inner race, outer race, retainer and the complement of balls—is easily assembled around the mounting surface. The major drawback is cost, as the manufacture of such bearings involves considerably more work.

Double fracture bearings can be loaded with fullcomplements of balls and enable designs to be adopted which would be difficult, or impossible to employ if it was necessary to incorporate conven-

tional bearings.

A Tube-bending Die

By M. W. LOFTUS

The tool shown in the accompanying figure was designed for use on a punch press, for bending seamless steel tubing without causing wrinkling, scratching or galling. As indicated at A, the body of the tool is of inverted-T section, and there are two side plates, as at B and C. These plates serve to house bearings for two pivoted disc-shaped blocks D, which are free to rotate about horizontal axes. Each block has a flat machined at one portion of the periphery, and extending longitudinally along this flat there is a groove of the same radius as the tube to be bent.

At the start of an operation, the pivoting blocks

are disposed with the flats uppermost, and horizontal, and a piece of tube is laid in position so that it registers in the grooves and is located endwise by stops E. The ends of a portion of straight tube are shown chain-dotted in the figure. A punch F is secured to the press ram and as the latter is brought down, the nose of the punch strikes the workpiece and starts to bend it.

As the tube bends, and the ends sweep upwards and together, the blocks D pivot about their horizontal axes and wrap the tube around the form on the punch. After the ram has been raised, the tube is removed, and the blocks D are automatically returned to the starting position by means of spring-loaded plungers as at G. Each plunger is housed in a bore in the plate G and its nose contacts a small peg G projecting from one side of the block G.


Depth stops, not shown, can be provided to limit the downward travel of the ram, and thus control the angle to which the tube is bent.

SINTER SEAL IMPREGNATION PROCESS. Industrial Impregnations, Ltd., Willow Road, Poyle Estate, Colnbrook, Bucks., have developed the Sinter Seal process for impregnating sintered metal parts as a means of preventing internal corrosion.

The material used for impregnation is a speciallycompounded resinous mixture which is stated to be completely stable in the fully-cured state. An impregnated component will withstand temperatures

up to about 200 deg. C. without its efficiency and chemical resistance being impaired.

Increase in weight of the component as a result of impregnation depends upon the density of the original No dimensional changes occur as a result of the treatment, and the original colour retained. Sintered parts, after impregna-tion, have been found capable of withstanding gas pressures up to 100, and hydraulic pressures up to 1,000 lb. per sq. in. Impregnation of parts that are to be electroplated prevents absorp-tion of the solution, and permits a better finish,



A die for bending seamless steel tube on a punch press

MACHINE TOOL BUILDING IN BRITAIN-3



The Butler Machine Tool Co., Ltd., Mile Thorn, Halifax By P. A. SIDDERS, Chief Associate Editor

A MACHINE TOOL BUILDING BUSINESS was established at Halifax in 1868, under the title of J. Butler & Co. The founder, James Butler, had been trained as a mechanic with a firm engaged in carpet manufacture, and was eventually foreman of the Jacquard department. From his training and experience in connection with carpet making machines, he became familiar with intricate mechanisms, and in particular, with cam-actuated systems for developing straight-line movements, and this knowledge proved useful when he started to build machine tools on his own account.

Aeh

n

IS

lt

As was customary for machine tool firms in the latter half of the 19th century, the Butler company built a wide range of different types of machines. Conditions during the 1914-1918 war led to a certain amount of rationalization within the machine tool industry, however, and in 1917, the company was one of the founder members of the Associated British Machine Tool Makers, Ltd. As

a result of this association with other well-known machine tool builders, the company was able to concentrate on the design and production of machine tools with reciprocating action, with the result that the name of Butler has become universally associated with planing, shaping and slotting machines

The opportunity was taken to improve designs, initiate batch production, and establish interchangeability of components through the extensive use of special-purpose equipment, jigs, fixtures, and gauges. Among improvements made in connection with Butler machines may be mentioned the increase of cutting speeds, particularly to meet the recuirements of tungsten carbide tools, and improvements in accuracy, to permit precision planing and shaping operations.

The Butler Machine Tool Co., Ltd., has always been very much a family business, and the founder (Continued on page 1371)




Fig. 1. Boring a location hole for a feed bearing bracket in the upright for a Butler No. 8 Spiral-Electric planer on a 6-in. spindle, Asquith floor-type machine. The cored hole is first rough machined, then finished to 5 in. diameter, \pm 0·0005 in. using a Microbore tool, with a high-speed steel cutting bit, which is run at 100 r.p.m., and fed at a rate of 0·008 in. per rev. This Asquith borer is also used for facing the ends of the upright, with a 16-in. diameter cutter mounted directly on the facing head of the spindle. A speed of 50 r.p.m. is employed, and from $\frac{1}{2}$ to $\frac{3}{4}$ in. of metal is removed from each surface

Fig. 2. Snout boring the body for a 21-in. slotting machine on a Richards No. 5 horizontal borer in 'A' department of the Mile Thorn works. The holes being machined are of 3.750 and 2.875 in. diameter, ±0.001 in., and receive phosphor bronze bushes on assembly. The large hole in the body is snout bored to 17.500 in. diameter, -0, +0.005 in. at a cutting speed of 75 ft. per min. and a feed rate of 0.009 in. per rev. When the boring operations have been completed, the machine table and work are indexed through 90 deg. and the base surface (remote from the camera, at the right) is machined






Fig. 3. During erection in the heavy bay of 'A' department, the alignment of the bed, cross rail and uprights of this Butler No. 8A Spiral-Electric planer is checked by Taylor-Hobson equipment. An alignment telescope and target (seen at the left on the bed), are used first to check the straightness of the bed-ways at a series of positions along their length. A right-angle prism attachment is then fitted to the telescope and a line target (seen directly above the inspector) is secured to the cross rail with the aid of permanent magnets. The alignment of the cross rail is then determined, with reference to the previously established optical axis, at the right, centre and left of both slideways

Fig. 4. This Churchill slideway grinder in 'F' department has two heads on the cross rail and one on the upright. It is seen set up for grinding the guideways on the upright for a Butler No. 7A planer. All faces are ground at one setting in a total time of approximately 16 hours. The outer vertical flat faces (extreme left in the illustration) are ground first, then the upper horizontal face and the lower dovetail face (as shown). A vertical face adjacent to the dovetail face and a narrow face parallel to the upper outer vertical face are ground next, after which the inside horizontal face is ground parallel to the upper horizontal face






Fig. 5. This set-up on a Churchill slide-way grinder with a 6- by 2-ft. table provices for finishing the bearing surfaces on the outside and inside of an annular rib on the swivel slide for a Butler No. 7A planer. A motor-driven rotary table is mounted on the main table of the machine, and the castiron workpiece is rough ground by a combination of the rotary and longitudinal feed motions. For finishing, the feed motion of the rotary table only is used, and the surfaces are covered in a number of stages. If required, surfaces can be ground slightly convex or concave

Fig. 6. Angle faces on swivel slides and down-feed slides which receive the retaining strips are ground simultaneously at this set-up on a Churchill machine to ensure correct seating of the strips, and in consequence, subsequent fitting at the erection stage has been practically eliminated. The V-guides on the down-feed slide are ground first, and the mating slideways on the swivel slide are then ground to suit. The swivel slide is mounted in a fixture and the bearing of the two parts is checked by blueing. When the two slides have been correctly bedded, the down-feed slide is mounted on the swivel slide and the angle faces are then ground






Fig. 7. Two of the Asquith radial drilling machines in 'D' department of the Mile Thorn works. A type OD 1 machine is seen in the background, and the type OD 3 machine in the foreground is set up for operations on a saddle for a Butler 18-in., shaper. With the aid of a universal indexing jig, a total of 18 holes, from in to 2 in. diameter, is drilled in the ends, an intermediate wall and one side. Three holes are tapped ½-in. B.S.F., and the hole in the side is spotfaced

Fig. 8. A recently-installed Milnes fine-boring machine, with Hilger & Watts optical positioning equipment, is here seen set up for operations on two table worm brackets for Butler 21-in. slotting machines. In-line bearing seats are first drilled, then bored to 1·250 in. diameter -0, +0·0005 in., using a Microbore tool, the speed and feed rate for finishing being 300 r.p.m. and 0·005 in. per rev. Aluminium feed brackets for 36-in. openside planers are bored complete on this machine. There are holes and counterbores of 16 different diameters, from $1\frac{1}{4}$ to $3\frac{1}{2}$ in., in these components





Fig. 9. Cutting a slot, $2\frac{1}{2}$ in. wide by 1 indeep, in the ram for a Butler 48-in. drawcut shaper, on one of the company's 4-by 4- by 10-ft. openside, Spiral-Electric planers. The workpiece is a forging in 0-4 per cent carbon steel, and the slot is blind-cut into a transverse groove, $1\frac{1}{16}$ in. wide. High-speed steel tools are used, at a cutting speed of 70 ft. per min. A $\frac{3}{4}$ -in. wide tool is employed for roughing, at a feed rate of 0-024 in. per stroke, and the sides of the slot are then machined to width at the same set-up

Fig. 10. Two of the test stands that are let into the floor of 'D' department. Butler 18-in. hydraulic shaping machines are seen undergoing tests, and the machine in the background is taking a ½-in. deep test cut in a mild steel block, at a cutting speed of 45 ft. per min. and a feed rate of 0·021 in. per stroke. The machines are fitted with vices and combination tables, which permit tilting and swivelling in three planes. Shaping machines of this type are built in batches of 16






Fig. 11. Set up for cutting the thread in the cross-slide traversing screw for a Butler No. 7A planer, on a Binns & Berry thread-whirling lathe equipped with a Burgsmuller head. This thread is of Acme form, 12-mm. pitch, and 2-start, and is 10 ft. long. The starts are machined separately, each in two cuts, at a traverse speed of 2½ in. per min., 0.025 in. of material per flank being removed during the second cut. The cutter head is run at 1,800 r.p.m., and is fitted with four cutters, two of 20 deg. included angle, one of 29 deg., and one for chamfering. Atomized gear cutting oil is applied as a coolant

Fig. 12. This Pfauter spline hobbing machine has been fitted, by Butler, with a special end-support for the work, in place of the tailstock. The support incorporates an internally splined bush, which runs in plain bearings, and it enables splines to be machined on shafts of any length. The Pfauter machine is seen set up for cutting six splines of B.S. straight-sided type, in the 2-in. diameter side shaft for a 21-in. slotter. A 3-in. diameter, single-start hob is used, which is run at 180 r.p.m.. and the feed rate is 0.010 in. per rev. of the work. In the same area there is a Dowding & Doll spline hobbing machine







Fig. 13. A Webster & Bennett 36-in. vertical turning and boring mill in the main machine shop of the Mile Thorn works is here seen set up for machining the pillar for an 18-in. universal table. The operations include turning two bearing portions of 9 and 10 in. diameter, facing the upper surface of the base, facing the upper end of the pillar, and boring the pillar 4.250 in. diameter, ± 0.001 in. Tungsten carbide tipped tools are used, and the work is first rough machined all over at a speed of 39 r.p.m. and a feed rate of 0.037 in. per rev. It is then finish machined at 55 r.p.m. and 0.010-in. per rev. feed, and boring is performed at 72 r.p.m. and 0.010-in. feed

Fig. 14. This Lang 30-in. swing surfacing and boring lathe is equipped with a special fixture for boring gearboxes. The front portion of the fixture is arranged to slide, and a location plunger passes through this front portion into the back plate, to ensure that the holes are machined on the correct centres. In each gearbox there are two pairs of in-line holes which are finished with floating-type cutters to receive Hoffmann bearings. The 2½-in. diameter hole which is here being machined, is finished at a speed of 32 r.p.m., and a feed rate of 132 cuts per in.







Fig. 15. This large Churchill plain grinding machine has recently been installed in the main machine shop of the Mile Thorn works, and has a 12-in. swing capacity. It has a 16-ft. long table and is intended for grinding main drive shafts and screw blanks more than 10 ft. long. The grinding wheel is 28 in. diameter by 3 in. wide, and the table speeds range from 4 to 123 in. per min., and the work speeds from 18 to 110 r.p.m. Here, the machine is seen grinding the blank for a bed screw in 0.5 per cent carbon steel. The work is 6 ft. $4\frac{1}{2}$ in. long, and has six steps, including a portion $2\frac{1}{2}$ in. diameter by 4 ft. $7\frac{1}{2}$ in. long, which is subsequently threaded








Fig. 17. This rig for checking squares has been built and installed in the toolroom of the Mile Thorn works. A bed with an accurately flat upper surface has a column at the rear to support a strip, the edges of which are parallel within very close limits. At either side of the column there are troughs wherein are fitted electric lamps. The stock of a square to be checked is mounted on the bed, and the blade is brought into contact with one side of the parallel strip, which is adjusted to obtain light tightness. Then, the square is repositioned with its blade in contact with the other side of the strip, and if the square is correct, no light should be visible between the blade and the strip. The strip can be raised for checking the inside edge of the blade in a similar manner

was succeeded by his son Mr. Harold Butler, M.B.E., who was at one time joint managing director with his brother, Mr. Herbert Butler. Mr. James W. Butler and Mr. Geoffrey M. Butler, sons of Mr. Harold Butler, are now joint managing directors, the former being chairman, also chairman of Associated British Machine Tool Makers, Ltd. The firm has two works in Halifax, one at Adelaide Street and the other at Mile Thorn, and it is with the latter that this article is concerned. It may be mentioned here that the Adelaide Street works, in which the company operated originally, now house the pattern shop, general pattern stores, foundry and welding department, and have an area of approximately 40,000 sq. ft. The foundry has an output of some 1,000 tons per year, exclusively

in cast iron, and supplies about half the castings required by the company. The remainder, particularly castings for the largest machine components, are obtained from other foundries in the Halifax area.

Mile Thorn works are built on a site of about 5½ acres, and the first group of buildings was completed in 1917. The buildings have since been considerably extended, and the latest addition to the production area was the machine shop which was finished in 1950. All machine tools previously installed at the Adelaide Street works were then moved to the new building, and machining and erection have since been carried out at the one site. Adjacent to the main workshops at Mile Thorn there is a modern office block, mainly of

single storey construction, and a new drawing office was added to this block two years ago. This office is in accordance with the latest standards, and has an area of 6,000 sq. ft. Good natural lighting is provided by fibreglass panels in the roof, and the windows are double-glazed. Hydraulically-operated adjustable stands are provided for the drawing boards, all of which are equipped with draughting machines.

The total number of workpeople employed by the company, which rose to a peak figure of 600 in 1943, has remained at about 400 for some years, and, in addition, there is an office staff of 45, including 12 draughtsmen and a number of drawing office

apprentices.

Mile Thorn works are divided into a number of departments, and "A" department is concerned with the building of planers. A general view of the heavy erection bay of this department is given in the heading illustration, and at the right may be seen a No. 8A spiral drive planer under construction, with a heavy-duty rail planer to the rear. The latter machine has a 25- by 5-ft. tilting table -seen on the floor to the left-which can be set to a maximum inclination of 1 in 30. A second rail planer, with a 36- by 5-ft. table is under construction at the extreme left. There is also a second bay in "A" department for the building of medium-size planers, and the total area of the department is 28,600 sq. ft., the height to the roof trusses being 28 ft. Two overhead travelling cranes, of the company's own design and construction, are installed in each bay, those in the heavy bay having hoists of 15 and 3 tons capacity, and in the medium bay, of 12 and 5 tons capacity. number of heavy-duty planing and boring machines is installed in the department, and setups on some of these machines are shown in certain of the accompanying illustrations.

Butler high-production slotters are built in "B" department which has an area of 10,000 sq. ft., and an adjacent shop houses "C" department, which is devoted to 26 in. shapers and openside hydraulic planers, also "D" department for building 18-in. shapers. All these departments are well equipped with overhead travelling cranes, and, again, the height from floor to roof trusses is 28 ft. The combined area of "C" and "D" departments is 12,400 so. ft., and since the latter department is concerned with smaller, lighter components, there are two 3ton capacity travelling cranes which run on rails that are supported on floor-mounted pillars, below the

main overhead cranes.

Adjoining these departments is a bav which houses "E" and "F" departments, which have a combined area of 14,000 sq. ft. Precision slotters are built in "E" department, where the height from the floor to the roof trusses is 19 ft., whereas "F" department, where the height is 28 ft., forms an extension of the machine shop and houses six Churchill slideway grinding machines. The capacities of these machines range from 8 by 2 by 2 ft. to 16 by 4 by 4 ft., and some typical grinding set-ups are illustrated. Other equipment in this department includes two large Kendall & Gent milling machines, a Richards vertical turning and boring mill, and three Butler openside planing machines-one of 10 by 4 by 4 ft. capacity and

two of the 36-in. type.

The well-equipped main machine shop has an area of 25,000 sq. ft., and the equipment includes a large battery of Ward machines, ranging from No. 10 combination turret to No. 2A capstan lathes. Among other lathes may be mentioned a large group by Lang, a Swift type 11B with a 24ft. long bed, a type 15V5 by the same maker, of 10-ft. by 15-in. swing capacity, with a gap bed and a pentagon tool holder on the compound slide, and two profiling lathes, one by Lang and the other by Churchill-Redman. A large number of Churchill plain grinding machines is installed, and a recent addition is a machine of 12-in. swing with a 16-ft. long bed for grinding main drive shafts and screw blanks over 10 ft. long.

Gear cutting equipment includes a No. 19, a No. 16, and two No. 5B Sunderland machines, a No. 3A Maxicut shaper, a 12-in. Gleason bevel generator, and a Butler automatic indexing slotter. There are Ffauter and Dowding & Doll hobbing machines for generating splines, and a Lapointe type H.P.30 horizontal hydraulic broaching machine with a stroke of 66 in. and a maximum pull of 30,000 lb., for cutting internal splines and similar work.

A toolroom adjoins the machine shop, and is equipped with a Newall type 2436 jig borer, and a wide range of precision lathes, milling machines and other units. Auxiliary equipment includes a Delapena honing machine and a Wild Barfield tool hardening furnace. An Abwood universal circular dividing machine is used for marking circular scales on indexing rings, dials, graduated collars,

and similar parts.

As has already been indicated, Butler machines are built in batches, and unit construction is employed wherever possible. Typical examples of batch sizes are 16 for 18-in. Super shapers, 12 for 26-in. Super shapers, 8 for 8-in. precision slotters, and 4 for 3-ft, 0-in. hydraulic openside planers. The number of Spiral-Electric planers is governed by the erection area, which will accommodate a total bed length of approximately 300 ft. Some representative machining and building operations at the Mile Thorn works are shown in the accompanying illustrations.

T.I. Helicoidal Bearing

Made by La Technique Integrale, 18 bis, rue d'Anjous, Paris 8me., France, the T.I. Helicoidal Bearing is primarily intended for converting from rotary to linear motion, and a sectioned elevation

of a typical unit is seen in Fig. 1.

Mounted concentrically with the screw A, the nut B houses a series of rollers as at C, which are arranged with their axes parallel with that of the unit and can rotate in corresponding holes in cage rings at the ends of the nut. The rollers are prevented from moving axially in the nut, and threads on their peripheries are engaged with the threads on the screw and in the nut, for transmitting motion between the latter members. To obviate the risk of slip between the rollers and the threads in the nut, which might otherwise occur due to the working clearances and would give rise to effective axial play, teeth on the periphery close to the ends of each roller are meshed with corresponding teeth in the bore of the nut.

A thread form with crowned flanks is employed, to reduce the area of contact, and it is claimed that relative motion between the nut and the screw is obtained with virtually no sliding friction. Motion is thus transmitted with high efficiency, as will be evident from the graph in Fig. 2, where a comparison is shown between the efficiencies of Helicoidal Bearings and conventional screw and




Fig. 1. Sectioned elevation of the T.I. Helicoidal Bearing, for converting from rotary to linear motion, or vice versa

nut assemblies with threads having various helix angles. The efficiency is such that motion can also be transmitted in the reverse direction, namely, by traversing one member to cause rotation of the other. Further advantages claimed for the system include high resistance to wear, and the ability to transmit high loads without the risk of seizure.

Units can be made for a maximum travel from 1 in. to approximately 16 ft., for static loads up to 100 tons, and the rotating member can be driven at speeds from 2 to 3,000 r.p.m. In the

standard series, which includes units with screws from 8 to 72 mm. (% to 2% in.) diameter, the dimensions of the nut range from 1 in. diameter by 1% in. long up to 5% in. diameter by 4% in. long. An example is shown in Fig. 3, the nut having been cut away to expose some of the rollers, and as an indication of the capacity, it is stated that at working speeds up to 300 r.p.m., for the smallest and




Fig. 2. Comparison of the efficiency of Helicoidal Bearings and conventional screw and nut assemblies




Fig. 3. A typical Helicoidal Bearing is here shown with the nut cut away, to expose some of the rollers

largest units, the maximum tensile loads may be about 4 cwt. and 29½ tons.

Units can also be supplied for special purposes, and the nut may be incorporated in a member with an external form to suit requirements. To prevent movement in the reverse direction under

load, as is necessary when the screw is employed for jacking, for example, a uni-directional roller clutch can be built into the nut. Thread pitches normally range from 4 to 15 mm. (0.158 to 0.530 in.), and it is stated that, if required, provision can be made for a differential action to enable a small linear movement per rev. to be obtained with threads suitable for transmitting high loads. It is claimed that the speed reduction which is thus provided permits considerable economies in connection with the system whereby drive is transmitted to the rotating member. It should be noted, however, that the accuracy of linear motion obtained with such a unit is not higher than 2 per cent.

The units have been applied by French companies in a wide variety of industries, and reference may R

d

n

o

be made particularly to their incorporation in machine tools built by several well-known firms. A unit for applying motion to the work-table of a milling machine, for example, has a nut which is constructed in two parts, to permit play to be taken up during climb milling operations.


Rhodes Up-cutting Hydraulic Shears

In the figure is shown an up-cutting shears incorporating the company's patented Fluid-Drive

principle, which has been supplied by Joseph Rhodes & Sons, Ltd., Grove Ironworks, Wakefield, to Samuel Fox & Co., Ltd., Stocksbridge, Sheffield. The shears was designed specially for inclusion at the end of a "cut-to-length" automatic line, and are capable of shearing up to 1-in. thick mild steel, or %-in. thick stainless steel, in widths up to 6 ft. 6 in. The cutting rate of the shears on plate up to %-in. thick is 20 strokes per min., and the maximum rate on thicker plates is 6 strokes per min.

With the Fluid-Drive method of operation, there are no clutches, rotating shafts, gears, or flywheels, and a relief valve in the hydraulic circuit ensures that no damage can occur from overloading.

Because the shears are of the upcutting type, the line conveyor can be maintained at a constant height. Use of the orthodox down-cutting shears would have necessitated the provision of an automatic dipping conveyor at the outgoing end of the line.



Rhodes up-cutting hydraulic shears for stainless steel plate

Continuous Broaching Root Forms on Turbine Blades

AT THE TAPCO AIRFOILS WORKS of Thompson Ramo Wooldridge Inc., Cleveland, Ohio, U.S.A., root forms are being machined economically on comparatively small batches of blades and vanes for gas turbines by continuous broaching. These components, some examples of which are shown in Fig. 1, are made in a great variety of forms and sizes, with lengths from 2 to 16 in., and in many different materials. including, aluminium alloy, 403 stainless steel of 30 Rockwell C hardness, A-286 alloy, titanium, and Hastelloy.

It has been found that broaching is essential to produce the intricate forms required with the necessary accuracy, and that the continuous process offers important advantages. A battery of Foote-Burt machines has been installed for this work, some of which are seen in Fig. 2, and their ratings range-from 10 to 30 h.p. with maximum cutting lengths from 40 to 110 in.




Fig. 1. Some typical blades on which the root forms are machined by continuous broaching

Certain blades although of different lengths have identical root forms, and three or four such blades may be handled at the same set up. For this purpose, the fixtures on the broach chain are

pose, the fixtures on the broach chain are arranged in groups, each fixture in a group being designed to receive a blade of a different length. The operator inserts the appropriate blade in each fixture as it passes the loading position, and as the fixture moves forward the blade is automatically clamped by the action of a cam. To protect the



Fig. 2. Part of a battery of Foote-Burt continuous broaching machines employed for operations on turbine blade roots




Fig. 3. The under-side of an interchangeable head for one of the continuous broaching machines with a set of broaches in position

broaches from damage, a safety gate is provided at the entrance to the tunnel, and if a blade has been inserted in the wrong fixture, or is incorrectly located and clamped, it will come in contact with the safety gate. As a result, a limit switch is tripped to stop the machine. The work clamping members of the fixtures can be rapidly interchanged to suit different blade forms.

To enable a different root form to be machined it is necessary, of course, to change the broaches, and to allow this operation to be economically performed, two broaching heads are normally provided for each machine. A view of the underside of one of these heads removed from the machine is given in Fig. 3, with a typical set of root-form broaches in position.

While broaching is being carried out with one head, the broach inserts in the other may be changed to suit the next batch of blades that is to be handled. Accurate pre-setting of the inserts is facilitated by the provision of taper gibs which enable very fine adjustments to be made. With the second broaching head thus prepared, it is stated, the time required for changing over is normally less than two hours.

Although it is desirable, where possible, to utilize the full complement of fixtures on the chain, and to broach two or more different blades with a common root form at one set-up, the continuous process is also employed in some instances for only

one type of blade at a time. In these circumstances, groups of difterent fixtures are still provided on the chain. but only one fixture in each group is loaded. In this connection it is pointed out that the power required for broaching some of the special allovs is such that consecutive fixtures could not be loaded, even if suitable blades were available, because the capacity of the machine would be over-

Outputs obtained from the continuous broaching machines range up to 3,000 blades per day, and it is stated that tolerances on root form as close as 0.0005 in. are maintained in some in-

b

stances. The roots of steel blades are finished by a grinding operation, but titanium blades can be broached to the required limits of accuracy and surface finish.

BLUE BIRD TYPEWRITER WITH TAPE PUNCHING UNIT.—At the recent Business Efficiency Exhibition at Olympia, a new German-built typewriter with a plug-in 5-channel punching unit was shown on the stand of Blue Bird Typewriters, Re-Man House, 44 Gray's Inn Road, London, W.C.1. This equipment enables punched tape to be produced simultaneously with the preparation of typewritten information, on stock record cards, for instance. The typewriter can be used for normal correspondence purposes when required.

Various typing programmes can be pre-set by means of a horizontal splined bar at the back of the carriage. Each spline represents a different programme, and certain portions are cut away. During typing, a solenoid plunger is depressed by the crest of the selected spline and an electrical circuit is thus completed so that information is transmitted to the tape. When a gap in the spline moves past the plunger, the latter is released and signals to the punching unit are temporarily interrupted. During this period, data not required on the tape is typed on the record card. Murray tape-code is used, and the equipment is suitable for use with the Telex system.

The Rodolite*

a nifill

n, in In

he

or he

eh es d,

es se

he

er-

m

ng

to

IV,

at

m

in-

a

be

nd

NG

biter

vn

an his

ed

en

ce.

d-

by

of

ent

ay.

cal

is

is

m-

ata

ord

ip-

A new Optical Device for Checking Machine Tool Alignments

By J. DYSON, Sc.D., F.Inst.P., and R. J. TILLEN,† Grad.Inst.P.

Although the accuracy required in large machine tools is generally not very great, there are certain notable exceptions, and on a large gear-hobbing machine, for example, an error of 0·0001 in. may be important. Since conventional mechanical checks tend to be inconvenient and tedious, they are often omitted, and the results that are obtained by such methods are treated with some reserve.




Fig. 2. The "optical plumb-line" mercury Rodolite, which is self-levelling

* Abstract from a paper entitled "The Rodolite: A new Method for Machine Tool Testing, and Some Applications", presented at the Second International Machine Tool Design and Research Conference, Manchester College of Science and Technology. † A.E.I. Research Laboratory, Aldermaston Court, Aldermaston.

Berks.

\$ Rodolite equipment is being made under licence from A.E.I. by Cooke, Troughton & Simms Ltd., Yorks.

With the development of the "Rodolite";—a registered name derived from "rod of light"—an attempt has been made to provide a method of

alignment-checking that is both more accurate, and more convenient.

OPTICAL PRINCIPLE

The instrument is based on the use of a circular diffraction grating comprising a large number of equallyspaced concentric rings. If a wavefront falls normally on such a grating, as at A, in the diagram at X in Fig. 1, a conical diffracted wave-front B is formed. In this diagram, it should be noted, other conical wave-fronts, corresponding to different orders of diffraction, have been omitted for the The conical wave sake of clarity. intersects itself at all points on the axis, as at C, and at each such point, there is a concentration of light.

Provided that the light-source is sufficiently small, the light-distribution at the intersection takes the form of a small light-spot surrounded by alternate dark and light interference rings, of successively diminishing intensity. With a perfectly made grating, and axially symmetrical illumination, the




Fig. 1. X—Optical principle of the Rodolite. Y—The reflection Rodolite

locus of these spots is straight. Although a phase" grating, consisting of raised rings of rectangular cross-section, is used to ensure maximum light economy, the contrast between the central spot and the interference rings tends to become poor at extreme ranges. Nevertheless, a 1%-in. diameter grating, with 150 rings per in., enables settings to be made to this line within 0.0001 in., over a range of approximately 20 ft., with an eyepiece fitted with cross-hairs. height of the raised portions of the phase grating, it may be noted, is such that the rays passing through the raised rings experience a path difference of half a wave length in relation to rays traversing the intermediate spaces.

Circular gratings can also be used reflectively, as shown in the diagram at Y in Fig. 1. Light from a small source D, near the axis, is diffracted to produce a concentration of light along the line E-F, where E is the centre of the grating, and F is at the same distance from the grating and the axis as D, but on the other side of the axis. The point G, which bisects D-F, is therefore always on the

grating axis.

A convenient arrangement comprises a lamp and condenser H, and a compound prism J, which incorporates a reflecting surface K. A pin-hole or other pattern L, on a side face of the prism, then




Fig. 3. Mercury Rodolite set-up on a hobbing machine for checking column and table-axis alignment




Fig. 4. Hyperboloid of revolution swept by the Rodolite line N—P, Fig. 3, on rotation about the work axis R—S

serves as the light-source. Setting is carried out by reference to cross-hairs on the rear face of the prism, which are observed through the magnifier M. When the prism is displaced sideways slightly, the cross-hairs, and the image F, move in opposite directions, so that the sensitivity of setting is doubled. With a 2-in. diameter, 400-line per in. grating, settings to 0.00005 in. can be made over a

distance of approximately 20 ft.

A third method, for which a transmission grating with rings of half the normal depth is required, is shown in Fig. 2. The grating is mounted close to a layer of mercury, approximately 0·010 in. thick, on the surface of an amalgamated silver plate, and provided that it is not tilted excessively, this combination behaves as a reflection grating which is always horizontal. Since the line defined thereby is always vertical, the device can, in practice, be regarded as an optical plumb-line. Accurate levelling is unnecessary, and the accuracy of setting, to the line, is the same as for an ordinary reflection grating of the same radial pitch.

APPLICATIONS

The object of one typical check, on the column alignment of a gear hobbing machine, performed as shown in Fig. 3, is to determine whether the motion of the saddle is parallel with the axis of rotation of the table. A reflection Rodolite N is used to define the line N-P, which is observed through a sighting head Q. This head, which is mounted on a bracket attached to the hob saddle, is provided with micrometer movements. When the table is rotated, the optical line N-P describes a hyperboloid of revolution about the axis R-S, of the table, as shown in Fig. 4. Since it is a cross-section of the hyperboloid, the path swept by the intersection of the optical line N-P with the sighting head is a circle.

Readings x and y are taken at 90-deg. intervals of table rotation, and the mean values, x and y then indicate the position of the axis of the table in relation to the saddle. These readings are taken with the table in motion, after the machine has been running for about 48 hours, and are

out

the

M.

he

ite

is

in.

r a

ing

is

o a

on

nd

his

ich

re-

ce.

ate

et-

mn

ed

the

of

repeated with the saddle in a series of different positions, z, on the column. Profiles of saddle motion, such as those shown in Fig. 5, are obtained by plotting x and y against z. Irregular variations of x and y indicate lack of straightness in the saddle motion, and linear variations, lack of parallelism between column and table-axis.

When the rotational axis of the table "wanders" during a revolution, the path swept by the image




Fig. 5. Results obtained from reflection Rodolite checks on the column alignment of a 150-in. gear hobbing machine




Fig. 6. "Wander" of axis of rotation on a gear hobbing machine, plotted from Rodolite readings

in the sighting head is not circular. Translational wander can be distinguished from tilting of the axis by examination of paths swept near to, and far away from the grating. If the axis is only moving translationally, the paths will be equally non-circular, whereas if the axis is tilting, they will not be of the same shape. Results obtained on a hobbing machine with a tilted table-axis are shown in Fig. 6, and those from a 150-in. hobbing machine, with departures from circularity of ± 0.0001 in., in Fig. 7.

To check whether the axis of the table wanders during a column-alignment check, a perpendicular section of the figure of revolution swept by the line is examined for deviations from the hyperbolic form. For this purpose, the radii of the circles swept by the Rodolite image, during the check for column alignment, are determined, and plotted against saddle position, z. Hobbing machines can also readily be checked with the Rodolite for cross wind of the vertical guideways, and pitch and yaw of the saddle.

HORIZONTAL GUIDEWAYS

The reflection Rodolite may be used to check the alignments of a wide variety of machine tools, and since gravity has no effect on the line defined, the first two checks described are equally suitable for machines with horizontal guideways, such as lathes and pinion hobbers. Cross wind and pitch of a saddle moving on horizontal guideways may be measured by using the mercury Rodolite as an optical plumb-line. Typically, for performing these checks on a lathe, the mercury pool and

grating are placed on the saddle, and the sighting head is held rigidly above the grating, on a bracket holted to the saddle.

Yaw of saddles on horizontal ways cannot be easily measured with the mercury or reflection Rodolites. However, the reflection Rodolite can easily be converted to operate as an auto-collimator, by attaching a collimating lens to the sighting head and utilizing the zero-order beam diffracted by the grating, the latter then serving as a plane mirror. With the "mirror" attached to the saddle, and the sighting head telescope mounted on a fixed part of the machine, or vice versa, pitch and yaw may be measured directly, from the displacements of the

image in the sighting head.

The following examples of total times for Rodolite checks are typical. Hobber, alignment, reflection Rodolite, 2 hours 45 min.; hobber, cross wind, mercury Rodolite, 1 hour 40 min.; lathe, cross wind and pitch, mercury Rodolite, 35 min.; pinion hobber, yaw and pitch, auto-collimating reflection Rodolite, 40 min. These figures, it may be noted, include both setting-up and measurement times, it being assumed that brackets for mounting the equipment already exist. It will be observed that the times are, in general, shorter than those for the methods of test in common use.




Fig. 7. Path swept by Rodolite image on 150-in. hobbing machine, showing departures from circularity of + 0.0001 in.

The authors express their thanks to Dr. T. E. Allibone, C.B.E., F.R.S., Director of the Laboratory, for permission to present this paper.

ACKNOWLEDGEMENT

This abstract is published by courtesy of Pergamon Press, Ltd., publishers of the International Journal of Machine Tool Design and Research, the joint Editors-in-Chief of which are Prof. S. A. Tobias (Birmingham University) and Prof. F. Koenigsberger (Manchester College of Science and Technology). The papers presented at the Conference will subsequently be reproduced in full, in the above-mentioned Journal.

COBALT STRIP MATERIAL. Pure cobalt strip with good ductility can now be supplied by Sherritt Gordon Mines, Ltd., 25 King Street West, Toronto, 1, Canada, in thicknesses from 0·005-in. to 0·025-in. and widths from ½-in. to 6 in. The strip is rolled from the company's cobalt powder by a new process, and is stated to be 99-9 per cent pure. Cobalt strip, cold rolled with a 4:1 reduction, has a tensile strength of 73 tons per sq. in., an elongation of 0·5 per cent and a Rockwell hardness (45T) of

85. In the annealed condition this strip has a tensile strength of 50 tons per sq. in., an elongation of 15 per cent, and a Rockwell hardness (45T)

of 68.

There are two crystal forms for cobalt metal, namely, close-packed hexagonal at temperatures up to 417 deg. C., and face-centred cubic from this temperature up to the melting point. On cooling after heat-treatment at a temperature above 417 deg. C., a mixture of retained face-centred cubic and newly-formed hexagonal metal is obtained, which has improved ductility.

In the annealed condition, cobalt has important possibilities for applications where corrosion resistance and strength at appreciable elevated temperatures are required. It is twice as strong as nickel, retains this strength at higher temperatures, and has comparable corrosion resistance. In addition, cobalt has excellent magnetic properties which are retained to a higher Curie point than are those of nickel. One promising application of cobalt strip is for magnetic tape for computers.

Delapena Induction Hardening Installation for Shafts

Delapena & Son, Ltd., Tewkesbury Road, Cheltennam, Glos., have recently supplied to Vauxhall Motors, Ltd., the induction hardening installation shown in Fig. 1, for handling several components for the gearbox of the new series of Victor cars. It comprises a type E 15/25 radiofrequency generator, an automatic type HS-DW horizontal shaft hardening machine made by Fritz Dusseldorf, Freiburg, West Germany, and incorporating a Delapena type R 51 radio-frequency transformer, and a re-circulating unit for cooling water. Delapena & Son, Ltd., are the sole agents in Great Britain, the Commonwealth, the U.S.A., and Canada, and the whole of Europe excluding Germany, Austria, and Switzerland, for Fritz Dusseldorf, and the shaft hardening machine in question is stated to be the first of its type to be installed in a British factory.

d

d

of

d

d

h

tt

0,

n.

d

e.

a

m

of

is

ns

er

 Γ)

or

ed

17

m

ıt-

ed

al

ed

alt a-

nd

ed

is

nd

e.

g-

to

of

of

for

The type E 15/25 induction heater is a standard valve-oscillator type radio-frequency generator which delivers power at a frequency of 350 kc./s., with a maximum continuous output of 15 kW. This equipment can be used as a 25-kW. installation for any duty cycle for which the heating period does not exceed three-fifths of the total cycle time, and each heating period, at 25 kW., is not longer than 3 min.

A steplessly variable output power control is provided which can be used for matching the power output to the work over a wide range during the heating period, and is said to offer particular advantages in connection with the heating of ferrous metals. The air-cooled oscillator valves are operated at powers considerably below their rated outputs so that they have a high factor of safety. The equipment is safeguarded by a number of devices, and additional safety switches are pro-

vided for operator protection.

The hardening machine will handle workpieces from 4 to 11.8 in. long, and from % to 2 in. diameter. It incorporates feed and traversing mechanisms, cooling and quench water systems, the radio-frequency transformer and work coil mounting, and the control system. A steel-framed cabinet with aluminium panels provides a support

for the feed and traversing mechanisms, with a drainage tank below.

By means of the feed and traversing mechanisms, the shaft components are transferred from the

magazine to the work station, passed through the inductor work coil and quench ring, and ejected from the machine. As may be seen in the close-up view, Fig. 2, the magazine takes the form of a sloping tray whereon workpieces are stacked automatically or by hand. The component at the lower edge of the tray rests against a stop at the side of a pair of rollers, as may be seen in Fig. 2. These rollers, which are of stainless steel, are carried in ball bearings at each end, and their axes are arranged parallel but are slightly inclined to the horizontal.

There is a small clearance between the rollers and the latter can be rotated in the same direction by means of an electric motor. Each roller is reduced in diameter over a short portion of its length and the gap so formed accommodates the work coil and spray quench ring. At the left-hand lower-end, the rollers are aligned with a V-section guide which receives the finished work-



Fig. 1. General view of the Delapena-Dusseldorf induction heating installation for gearbox components of the Vauxhall Victor motor car




Fig. 2. Close-up view of the magazine and work station of the Delapena-Dusseldorf induction heating installation

A push rod is coupled to the piston of a hydraulic cylinder and extends parallel to and between the two rollers, at the right-hand-upper

Separate cooling and quenching water systems are provided with independent inlet and drain connections, stop valves, and pressure gauges. The cooling water circuit is further divided into two parallel branches for cooling the work coil and the secondary coil of the radio-frequency transformer. A separate stop valve in each circuit permits independent control of the two cooling flows, and allows the supply to the work coil to be shut off when the latter is to be changed. A pressure switch in each circuit shuts off the radio-frequency power if the cooling water supply fails, and a pilot lamp on the control panel affords an indication that the flow of cooling water through both circuits is adequate.

The Delapena type R 51 radio-frequency transformer is mounted on a platform in the upper part of the cabinet, with a work coil adapter bolted to the output terminals and projecting through an insulating panel. Provision is made for adjusting the platform in three planes so that the work coil can be positioned accurately in the gap between the rollers, with its axis aligned with that of the The quenching spray ring is also workpiece. fully adjustable.

Three work coils are provided to cover the range of five components at present being hardened on this equipment. All work coils are fitted with standardized mounting blocks to permit rapid removal from, and assembly with, the adapter.

Various controls provide for setting up and regulation of hardening cycles, as regards timing of the automatic feed, application of a variable rate of traverse for the workpiece, switching on and off the radio-frequency power, and control of the flow of cooling and quenching water. Safety arrangements include a switch which stops the machine when only one component is left in the magazine. The water re-circulating unit is of a standard Delapena type comprising a 60-gal. supply tank, water pump, radiator assembly, and cooling fan. Water is re-circulated through the induction heater and primary coil of the radio-frequency transformer at rates up to 2 gal. per min.

The component shown in the illustrations is a striking fork rod of En.

43B steel which requires to be hardened to a minimum of 51 Rockwell C. The diameter is 0.59 in., and the length 6.8 in., and the cycle time per piece is 21 sec. It is stipulated that the hardened area must not extend to the cross hole or the roots of the grooves.

NEW LEVELTRON INDUSTRIAL LEVEL CON-TROLLER.-A new version of the well-known Leveltron industrial level controller has been introduced by Thomas Industrial Automation, Ltd., Station Buildings, Altrincham, Cheshire. Designated type CS101, the controller is for use with two electrode units, one mounted at the high level and the other at the low level position in a vessel, tank or other container. Only one controller is required for both high and low level control of pumps, conveyor motors, valves and similar equipment.

There is only one relay in the control unit, and it is de-energized when the stored material reaches the high level and is re-energized when the material falls below the low level, thus providing automatic interlocking between the two levels. controller, which is housed in a sheet steel or cast iron case, can be used with any of the standard range of T.I.A. electrodes, and the maximum distance between the controller and electrodes is

7th European Machine Tool Exhibition, Brussels Ninth Article

SCHIESS TYPE RFW 10 HORIZONTAL GEAR AND PINION HOBBING MACHINE

to at

th r-ly

ic

of

ng

r,

ng

e-

ps

n-

ne

a

a

p,

n.

of

at

S-

n.

a

is

10

e

le

m

n

n, e.

se

gh

a

n-

el

nd

ıd

es

al

0-

OF

n-

m

A general view of the German-built Schiess (Sykes Machine Tool Co., Ltd., The Hythe, Stzines, Middx.) type RFw 10 precision horizontal gear and pinion hobbing machine is given in Fig. 1, where it is seen set up for operations on a single-helical gear. It will cut gears of plain spur, single-helical, or double-helical (by end milling) form, and will accept blanks up to 59 in. diameter. The maximum distance obtainable between the faceplate and the tailstock centre is 158 in., and the maximum face-width that can be cut is 112 in.

The faceplate is mounted directly on the headstock spindle, and the latter is driven through the master indexing worm and wormwheel, which has special provision for the elimination of backlash. A feature of the headstock is that the master worm and wheel can be disengaged and drive can be taken through a pinion and bull-ring

faceplate. behind the This drive is employed for roughing operations on large-pitch gears, and relieves the worm and wheel of excessive duty which might affect its accuracy. The tailstock is a massive casting which is supported on flat ways on the front bed, and is adjusted for position longitudinally by means of a pinion which meshes with a rack in the throat of the bed. Twin steadies are provided on the front bed, to support the work at either side of the gear portion.

The hobbing head is swivel mounted on a heavy casting which is arranged for transverse movement on a saddle, and the latter has a longitudinal movement of 112 in. on the rear bed. A close-up view from the rear of the machine is given in Fig. 2, where the hobbing head, saddle, and rear bed can be clearly seen. The saddle slides on wide flat ways, and is traversed by a screw which is housed in a channel and is totally-immersed in oil. The associated nut is of the split type, and provision is made for adjustment to eliminate backlash. A swivelling movement of 45 deg. about a horizontal pivot is provided for the hobbing head, on either side of the central position, to enable right- and left-hand helical gears to be cut.

If required, spur and single-helical gears up to 85 module can be cut by the single-indexing process, an end-milling head being employed in place of a conventional hob. This operation can be carried out with a fully-automatic cycle, and the machine is switched off after a predetermined number of teeth has been cut. Another special attachment enables double-helical gears to be end-milled by the single-pass method. For this




Fig. 1. General view of the Schless type RFw 10 precision horizontal gear and pinion hobbing machine




Fig. 2. Close-up view from the rear of the Schiess hobbing machine, showing the hobbing head and saddle

operation, the machine is provided with special

of the work is automatically reversed when the apex of the doublehelical tooth is reached. Longitudinal travel of the saddle is applied continuously, and it is stated that reversal of rotation is effected at the same point for each tooth within very close limits, so that the apices are in close alignment.

Conventionalor climb-hobbing can be employed, and the drive to the hob spindle is transmitted through duplex worms, to eliminate backlash and to provide a balanced drive. It may be noted that gear teeth up to 30 module size can be cut in steel blanks when the faceplate is driven by the worm and wheel.

OERLIKON TYPE F 60 CHUCKING LATHE

The type F 60 chucking lathe shown in Fig. 3 has been introduced by Oerlikon Machine Tool Works, Buehrle & Co., Zurich, Switzerland (Dowding & Doll, Ltd., 346 Kensington High Street, London, W.14) and is provided with plug-type programme control. It is particularly intended for operations on such parts as gear blanks, hubs, and brake drums, in either small or large batches, and is provided with two tool-slides, each equipped for copying under the control of a hydraulic system. The slides are inclined at 30 deg. to the horizontal, to facilitate the discharge of swarf into a wheeled bin housed in an aperture provided in the welded steel bed.

A maximum diameter of 23% in. can be swung over the bed-ways, and 20% in. diameter over the tool-slides. Lengths up to 15% in. can be turned externally, and up to 7% in. internally, and the stroke of each copying slide is Each copying slide base has a 9 in.

transverse traverse of 10 in. on its saddle, and can reversing gear, whereby the direction of rotation be swivelled up to 30 deg. on either side of a



Fig. 3. Oerlikon type F 60 open-ended chucking lathe, with plug-in programme control

central position. The spindle has a 6¼-in. diameter main bearing, an American standard A11 nose, and a through hole of $4\frac{\pi}{6}$ in. diameter. Spindle speeds range from 22 to 500 r.p.m., in four groups, each divided into four steps, and changes of speed can be made while turning is in progress, and under the control of the programme control equipment. Alternative speed ranges, from 31 to 720, 45 to 1,000 or 63 to 1,400, can be provided, on request.

the

ed

CS.

nd

ng-

nd

me

ed

ear

in

is

ch

he

he

he

ge

in

ed

an

0%

es.

ed

ly,

is

a

an

Longitudinal and transverse feed to the toolslides is applied hydraulically, and the rates range from 0·002 to 0·040 in. per rev., and are steplessly-variable. There is also a rapid traverse rate of 20 ft. per min. for quick advance and withdrawal of the tools in the longitudinal and transverse directions. The movements of each saddle longitudinally are limited by slotted plates, which serve to carry adjustable dogs for actuating limit switches. Other dogs are employed to initiate changes in spindle speed, feed rate, and the engagement of rapid traverse, all in conjunction with the programme control system. The plates, complete with dogs, are readily removable, and can be stored until they are required for a repeat run.

Each copying slide has a 4-position tool turret, which is indexed by programme control, and slotted plates similar to those employed for longitudinal movements are provided for limiting the transverse Flat sheet templates are used for the copying system, and provision is made for raising the templates, under programme control, so that the edges can be engaged successively by a stepped-nose copying stylus. With this arrangement, successive copying passes can be made from the same template, the stylus advancing slightly at the start of each pass so that roughing, semifinishing, and finishing cuts can be taken. programme provides for raising each template as many as six times, so that with a 6-step stylus, heavy metal removal can be spread over that number of passes.

Alternatively, several templates can be used, stacked one above the other, and the elevating motion is then employed to bring each plate successively into line with the copying stylus. Separate push-button and rotary switch control panels are provided adjacent to each saddle, and the programme control equipment, which is of the free-standing type, can be seen at the right in the figure.

BOHLE TAPE-CONTROLLED MILLING MACHINE

Reinhard Bohle, K.G., Bielefeld, Germany (Drummond-Asquith, Ltd., King Edward House, New Street, Birmingham, 2), build a wide range of milling machines, with table sizes from 40 by 12 to




Fig. 4. Bohle type FS 120/1850 vertical milling machine adapted for 3-axis control by the AEG punched-tape system

98 by 25 in., and knee movements from 13% to 17% in. Machines in the standard range have 18 spindle speeds, in various groups from 11 to 560 to 35 to 1,800 r.p.m. according to size of machine and customers' requirements, also 27 feed rates for the longitudinal and transverse motions, from % to 124 in. per min., and vertical feeds of one-third of these rates.

Exhibits included a type FS 120/1850 vertical milling machine, from the standard range, which had been specially adapted for punched-tape control. Shown in Fig. 4, the machine has a 71-by 20-in. work-table with longitudinal and transverse movements of 49 and 17 in., and the vertical movement of the knee is 17 in. The spindle head is of the quill-type, with an axial adjustment of 4% in., and drive is taken from a 25-h.p. motor. On the machine illustrated, the spindle has a standard 50 series nose, but it can be provided with a No. 5 Morse taper as an alternative.

The normal drive arrangements for the three main machine movements have been replaced by servo-motors, which are controlled by punched-tape equipment developed by A.E.G., Hohenzollern-damm 150, Berkin-Grunewald, Germany. A close-up view of the combined control cabinet and tape-reader is shown in Fig. 5, and this unit is installed



Fig. 5. Close-up view of the AEG combined control cabinet and punched-tape reader for the Bohle milling machine shown in Fig. 4

separately from the machine. Standard 8-channel paper tape is employed, and the reader is housed in a recess at the centre of the cabinet, and is covered by a plastics window.

To the right of the tape reader may be seen three horizontal rows of control knobs, which provide for setting dimensions in any of the three axes by hand, if the use of a punched-tape is not justified. The top row of knobs controls longitudinal movement, the centre row transverse movement, and the lower row vertical movement. Above each knob there is a small circular window, and the control is turned until the required digit appears. In this manner dimensions in any axis can be built up. The rotary switch below the dial-in knobs is of the 2-position type, and provides for selecting either automatic (punched-tape) or manual control.

It is hoped to describe the AEG tape control system in more detail in a future issue of MACHINERY

LINDNER TYPE LB 12 OPTICAL JIG BORING MACHINE

The type LB 12 optical jig boring machine shown in Fig. 6 has been introduced by Herbert Lindner G.m.b.H., Berlin-Wittenau, Germany (Stedall Machine Tool Co., 192 Pentonville Road, London, N.1), for operations on small jig and fix-

ture parts, but is also suitable for small-batch production work, and can be employed for facing and milling operations. The working surface of the table measures 20 by 10 in., and it has longitudinal and transverse movements of 16 and 10 in. respectively. A vertical movement of 7% in. is provided for the spindle head, for initial setting purposes, and the boring spindle, which is of the quill-type, has an axial movement of 5 in. The distance from the centre of the spindle to the face of the column is 16 in., and the minimum and maximum distances obtainable from the nose of the spindle to the working surface of the table are 4 and 16% in.

Spindle speeds are steplessly-variable within the range from 60 to 3,000 r.p.m., and speeds from 420 to 3,000 r.p.m. are transmitted directly by way of a belt. For the lower end of the speed range, drive is taken through a gear train. Three rates of vertical feed are provided for the spindle, namely 0.001, 0.002 and 0.005 in. per rev., and depth settings are made with the aid of a dial indicator to an accuracy of 0.0005 in. The feed motion is automatically disengaged when the required depth has been reached.

The work-table moves on hardened and ground rollers in the longitudinal and transverse directions, and initial rapid setting for position is made by means of the two handwheels seen projecting



Fig. 6. The Lindner type LB 12 optical jig boring machine

from the front of the machine, at either side. For final setting there are two additional handwheels, mounted vertically at either side of the control panel. The latter is conveniently placed immediately in front of the operator, and is of the desk-type. It incorporates a number of push-buttons, for starting and stopping the spindle, increasing and decreasing the speed, engaging and disengaging the feed, and controlling the coolant pump. It also houses two projection screens, which are associated with the optical setting equipment for longitudinal and transverse movements of the table.

tch

ing

of

in.

is

ng

he

he

ice

nd

of

ole

in

ds

tly

ed

ee le,

ial

ed

he

 \mathbf{d}

C-

de

ng

The optical system incorporated in the machine is similar to that employed on other Lindner jigborers, and allows the table to be positioned to within 0.0001 in. There are two highly-polished stainless-steel cylinders, one attached to the table and the other to the cross-slide, and each cylinder has a finely-defined helical line engraved on the periphery. Provision is made for turning the cylinder about its longitudinal axis, but it is restrained from moving axially. By means of a lamp, and a system of mirrors, lenses, and prisms, an image of part of the helical line is projected on to a screen which is provided with two closely-pitched parallel lines. Separate screens are provided for the longitudinal and transverse movements.

After turning each cylinder so that the projected images are zeroed between the lines on the projection screens, initial setting of the table is made with the aid of conventional precision scales built into the machine, and graduated in increments of 0.10 in. The remainder of the required dimension is then set with the aid of a micrometer head, which is arranged to turn the appropriate engraved cylinder by the required amount about its longitudinal axis. As a result, the projected image of the helical line is displaced from between the two lines on the associated viewing screen, and it is then necessary only to move the table-by the fine-setting handwheel-until the image is again centralized between the two lines. A feature of the type LB 12 machine is that two additional sceens, one for the longitudinal and one for the transverse movement, are provided, whereon the distances which have been moved during the final setting stage are indicated directly, in whole numbers of 0.0001 in.

SCHNEIDER CREUSOT TYPE RUP 48 Y 4 SURFACE GRINDER

In Fig. 7 is shown the French-built Schneider Creusot type RUP 48 Y 4 surface grinder [Machine Tool Sales (London), Ltd., 79 Portland Place,



Fig. 7. French-built Schneider Creusot type RUP 48 Y 4 hydraulic surface grinder

London, W.1]. The 18- by 11%-in. work-table has a maximum travel of 19% in. on vee and flat guideways, and steplessly-variable traversing speeds from 3·3 to 80 ft. per min. are provided hydraulically. There is no handwheel for longitudinal movement, but the table can be traversed slowly under the control of a separate lever, for example, for positioning when wheel dressing is to be carried out. A cross travel of 12% in. is provided for the saddle, which is guided by central and outer bed-ways, and feed can be applied continuously at rates ranging from 8 to 96 in. per min., or intermittently at the ends of the table movement. Lubricant is delivered to the central bed-way by a built-in pump, and to the other ways by means of rollers.

Drive to the wheel spindle, which runs at 2,950 r.p.m., is taken from a 3-h.p. motor through a flexible coupling, and the bearings are lubricated by a built-in pump. The wheel-head can be swivelled on the saddle by a pinion and segment gear, and may be set in the horizontal or vertical position, or at any intermediate angle. It can be secured to the saddle in the required position, by means of a clamp, and is provided with a sine bar attachment to facilitate accurate setting for angle. Disc-shaped grinding wheels up to 8 in. diameter can be mounted on the spindle. Alternatively, a 6-in. diameter segment-type wheel may be

employed. Work up to 11½ in. diameter high may be ground with a new disc-shaped wheel, and up to 9½ in. high with a segment wheel. The hand-wheel for traversing the wheel-head saddle on the column ways can be set in two positions on its shaft to give coarse and fine adjustment, and provision can be made for down feed to be applied automatically, in increments ranging from 0.0002 to 0.0008 in. per table stroke. Alternatively, hydraulic equipment can be provided, which enables the wheel-head saddle to be continuously traversed on the column ways for a pre-set distance under the control of upper and lower stops.

MORANDO TYPE VK 25 VERTICAL TURNING AND BORING MILL

The type VK 25 turning and boring mill shown in Fig. 8 is representative of a range built by Fratellii Morando & Co., S.p.A., Turin, Italy (Industrial Sales, Ltd., 25 Barton Arcade, Manchester). With a 98-in. diameter work-table, it is the second largest machine in a range of seven, with work-tables from 36 to 118 in. diameter. Of the double-column type, it has two rail-mounted tool slides, the left-hand slide being arranged for copy-turning under the control of electrically- or hydraulically-operated equipment. Both rail heads

MORANDO WX 25

Fig. 8. The Italian-built Morando type VK 25 turning and boring mill, which is representative of a range of machines

are arranged for swivelling, through an angle of 35 deg. to either side of the central position, and each slide has a vertical travel of 39 in. The right-hand column only is provided with a side head, which has a vertical travel of 75 in. and a working stroke of 35 in.

A range of 16 feed rates is provided for all tool slides, in the vertical and transverse directions, from 0.0026 to 0.5 in. per rev. of the table, and the latter, which is driven by a 65-h.p. motor, normally has a speed range of 2 to 60 r.p.m. Alternative speed ranges for the table, of 2.5 to 75 or 1.5 to 45 r.p.m., can be provided if required. Speed changes are effected by sliding gears and clutches, which are actuated hydraulically, and the machine shown at the Exhibition was also equipped with an automatic speed variator, of an electrical type, to enable constant cutting speed

The table is carried on a high-tensile iron spindle which is mounted in opposed taper-roller bearings, and drive is transmitted by a pinion which meshes with a large-diameter single-helical gear secured to a flange at the upper end. Oil for lubrication is delivered under pressure to the top bearing, whence is falls by gravity through the bottom bearing and returns to a sump in which

to be maintained during facing operations.

the latter is immersed.

Power traverse at a rate of 14 in. per min. is provided for the cross-rail on the columns, and it can be raised to allow a 75-in. high workpiece to be machined by the rail heads. The rail is raised and lowered by twin screws, one at the side of each column, which are synchronized by a special coupling, and drive is taken from a motor mounted centrally on the tie bar which joins the tops of the columns. The rail is clamped hydraulically by a double-ended, twin-piston cylinder, which is also mounted on the tie bar. A piston rod extends from each end of this cylinder, and is provided with rack teeth which engage with a pinion carried on the top of a vertical shaft. The shaft serves to turn two pairs of

The copying head and stylus are carried at the end of a shaft which, in turn, is supported from a bracket on the left-hand tool-slide. Flat sheet templates are employed, of the type seen at the extreme left in the figure, and the copying head controls the feed

eccentric type clamps, at the ends of the rail, to lock the latter to the

columns.

motion of the tool-slide vertically and of the saddle transversely, by way of hydraulic motors. As mentioned earlier, electrically - operated copying equipment can be supplied if required.

of

nd he

de

nd

all

18.

nd

or, m.

to

d. id

 \mathbf{d}

so

ed

le

r-h

ar

or

h

weil s, a, al

a r,

Attachments available for use with this machine include a vertical grinding spindle, which is driven through belts by a separate motor, and has a stroke of approximately 16 in. Another, smaller grinding unit, in which the motor is integral with the spindle, is also available, and is particularly intended for operations on workpieces small - diameter with bores. Mention also be made of a slotting attachment, which incorporates a striker mechanism whereby an

increment of feed is applied to the tool at the end of each return stroke.



Examples of special-purpose high-production machines built by Bammesberger & Co., Stuttgart, Germany (Stanley Howard, Ltd., 73 Devon Street, Birmingham, 7), included the rotary type, of which a close-up view is shown in Fig. 9. This machine provides for drilling, chamfering, reaming, and tapping six equally-spaced holes in a blank for a bevel gear, and the output is 137 workpieces per hour at 80 per cent efficiency. A completed workpiece, as taken from the machine, is seen resting on the base in the foreground.

The indexing work-table carries a large rectangular block at its centre, from each side face of which projects a 3-jaw, self-centring, hydraulically-operated chuck. The jaws engage the bore of the blank, and there is a steel block at the inner end of each which serves to locate the blank axially. Loading and unloading take place at the chuck position in the foreground, and the first indexing movement of the table carries the work to the multi-spindle head seen at the left. Here, six 8-5-mm. diameter holes are drilled and chamfered with combination tools, which are steadied in a bush plate in the conventional manner. This




Fig. 9. Close-up view of a Bammesberger 3-head special-purpose machine for drilling, reaming, and tapping operations on blanks for bevel gears

plate incorporates diagonally-arranged locating plungers which engage with bushes that are carried in supports projecting from the workholding block.

At the next indexing movement the work is carried to the second multi-spindle head, which is identical in design to the first, and provides for reaming the holes to 9 mm. diameter. Finally, the holes are tapped to 10 mm. diameter by 1-mm. pitch by spiral-flute taps in the third head, at the right. The machine is of the electro-hydraulic type and the cycle is fully-automatic, the operator being required only to load and unload the work.

A more complex rotary-type machine, which has five working stations and a 7-position indexing table, is shown close-up in Fig. 10, and provides for multiple milling, drilling, and spherical boring operations on end pieces for swivel joints. At A in the figure can be seen a blank, and, at the left, a workpiece in the finished condition as it leaves The blank takes the form of a the machine. solid sphere with a reduced-diameter parallel projecting portion, and batches are fed at random into a vibratory-type hopper, a portion of which can be seen at the extreme left in the figure. From this hopper, the blanks pass down the inclined tube B, having been automatically sorted so that they proceed ball-end first, and a hydraulically-operated shuttle mechanism removes the leading workpiece and loads it, ball-end uppermost, into a fixture.

There are seven identical work-holding fixtures on the table, one of which can be seen clearly at the centre in the figure. There are two opposed V-jaws, arranged for horizontal movement towards and away from each other, which grip the work by the spherical portion, and the lower part of each jaw has a part cylindrical groove to engage the

At the first working station there is a columnmounted head C, arranged for vertical movement, and this head carries two slitting saws, as at D. These saws machine two parallel flats on the spherical portion of the workpiece, the partspherical waste material falling away into a tray below the table. The distance between these flats is slightly greater than the diameter of the parallel boss on the blank, also slightly greater than the thickness of the jaws in the fixture.

At the next station, a parallel hole is drilled through the spherical portion, at right angles to the flats, and at the following station this hole is spherically bored by a special swivel-mounted tool. The head at the fourth station incorporates a long over-arm, which extends over the fixture and carries a milling cutter that approaches the workpiece from the side nearer the centre of the table. This arm is indicated at E and it carries a short horizontal milling spindle and an axially adjustable steady bracket which provides support immediately behind the cutter. The latter finish mills the inner flat on the spherical portion of the workpiece, and opens out the short length of parallel hole which remains after the spherical boring operation.

The fifth head performs similar milling and opening-out operations on the other side of the work, and the final indexing movement brings the piece to the unloading position. Here, the fixture jaws are opened and the work falls into a delivery chute. To obviate the possibility of the work failing to fall clear under its own weight, a doubleacting hydraulic ram F is provided, which is automatically energized to advance and knock the work from the jaws. This machine has an output of 120 parts per hour, at 80 per cent efficiency.

DE BUYSER CRANKSHAFT GRINDING MACHINE


The type C/225-75 crankshaft grinding machine shown in Fig. 11 is typical of the range built by J. De Buyser, 118-122 Rue des Coteaux, Brussels, Belgium (Scot Urquhart, 373a Earlsfield Road, London, S.W.18). With these machines, main journals and crankpins can be ground, also the blending radii between the bearing surfaces and

the webs, with the shaft in the vertical position. The lower end is supported in a special chuck on a power driven table, and the upper end is steadied by a centre in a bracket which extends from the cast-iron column. With this arrangement, it is claimed, the crankshaft is free from the deflecting and torsional forces which would be imposed by its weight if it were mounted horizontally.

There are guides on the column for a saddle, which can be traversed vertically and serves to support the grinding head. The latter is mounted with its spindle horizontal, and grinding is carried out with a cup Drive to the spindle is taken through belts from a motor mounted on the saddle, and there is provision for longitudinal movement of the spindle head, for setting the face of the wheel to the required distance from the centre of the bearing to be ground. The chuck which holds the lower end of the shaft is arranged for radial adjustment, relative to the centre of the table, and on the machine illustrated it can be set to



Fig. 10. This Bammesberger machine performs multiple milling, drilling, and spherical boring operations on end pieces for swivel joints



ıd

h

d

le

10

ry I-

0-

ne

ut

ls,

in ne nd

ioer

is

et

n

is

m

nt

d

d

n

d

neef

r

Fig. 11. De Buyser crankshaft grinding machine

suit crankshafts with throws up to 6½ in. Shafts up to 118 in. long can be handled, and can be driven at speeds between 5 and 28 r.p.m.

For dressing the wheel, a special bracket which carries a diamond is clamped to a convenient journal on the shaft. The latter is held stationary and the spindle head is raised and lowered, to pass the wheel across the diamond.

E.R.O.P. MICROBANC SURFACE GRINDER

The Microbanc type HP 37 surface grinder shown in Fig. 12 has been introduced by E.R.O.P., 71-73 Rue de Colombie (Seine), France, and has a 27½ by 111½ in. work-table. It is of the hydraulic type, and the rate of longitudinal traverse of the table can be varied steplessly between 0 and 82 ft. per min. Movement can also be imparted manually, and in addition to a graduated collar and vernier for setting purposes there is an optical system which enables readings to be made to 0.002 in.

In the transverse direction, a powered movement of 13 in. is provided, and the optical equipment enables settings to be made manually to 0.00008 in. There is provision for setting to a similar accuracy in the vertical direction, and the grinding wheel head has a rise and fall of 16% in. For vertical

traverse, the speed is 9 in. per min., and the maximum distance obtainable between a new 10-in. diameter grinding wheel and the surface of the table is 14% in.

A wide range of automatic grinding cycles can be set with the controls provided. For example, the wheel can be lowered into contact with the work and a setting for a predetermined amount of metal removal can be made by means of the controls for the vertical movement. On pressing the start button, the table will continue to reciprocate, and the head to feed down, until the pre-set amount of metal has been removed. The grinding head is then returned automatically and rapidly to the raised position.

Settings can also be made to enable grooves or slots to be ground to pre-set depths, and to pre-set positions transversely. The head automatically feeds transversely to a dead stop, whereupon the cycle is started and incremental down feed is applied automatically at the end of each stroke. The wheel is thus progressively fed into the work, and the cycle continuues until the required depth is reached. A number of different types of grinding heads is available for use with the machine, including universal and vertical designs.

Another machine, with a 19%- by 1118-in. worktable, designated the type HP 35, is also produced, but does not have the same range of automatic cycles as the type HP 37.



Fig. 12. E.R.O.P. Microbanc type HP 37 surface grinder, which is provided with optical setting equipment. A range of automatic cycles can be obtained

Making the New Borg-Warner Automatic Transmission



The New Borg-Warner automatic transmission was briefly described, and reference was made to methods employed in the production of certain of its components in articles published in Machinery, 99/764—4/10/61, 99/888—18/10/61 and 99/1236—29/11/61. In the latter article, the preliminary operations on the largest of several pressure die cast aluminium alloy valve body components were described, up to the point at which the six valve bores are finish-reamed. Here, the remaining operations on this largest casting are considered, also some of the methods employed for machining another casting which forms part of the valve block assembly.

Some indication of the intricacy of the cored channels in the large valve body casting, which serve as oil-transfer passages in the completed assembly, is afforded by the heading illustration. Here, the operator is engaged in chamfering drilled holes and removing burrs from the channel edges and surfaces with the aid of a Desoutter air-operated drill gun and other hand tools. The complete removal of loose material, which might become detached in service and cause sticking of valve plungers or other troubles in the hydraulic system, is extremely important. Special brushes, of soft nickel-silver wire, to avoid scratching finished sur-

Transmission

Operations on Pressure Die Cast Aluminium Valve Block Castings

By R. E. GREEN, Associate Editor

faces, are employed for thorough cleaning. These brushes are of stepped form, and about $\frac{1}{16}$ in. larger in diameter than the bores to be cleaned.

FINISHING THE JOINT FACES

After the manual cleaning operations, the castings are washed in a water-soluble emulsion and transferred to the British-built Thompson (Rockwell Machine Tool Co., Ltd.) bed-type surface grinding machine shown in Fig. 1. This machine is employed for finishing flat side faces on both the larger castings for the assembly, simultaneously, and is equipped with a simple fixture on which two large and four smaller castings are held in vertical positions. Location of the castings is taken from drill-reamed holes which are engaged with dowels projecting from the vertical faces of the fixture, and they are secured by floating pads, clamping force being applied by lever-operated cams.

The positions in which the castings are thus held ensure that all the side faces are in line, and can be ground with a single wheel, 3 in. wide and of 20 in. diameter when new. The wheel, which is of WA 46 KV specification, is dressed by means of the diamond in a bracket at the front of the ram guideways. On the two larger castings it is the side face, in which there are two valve bores, that is ground. Two of the smaller castings are loaded one way up, and the other two with the opposite faces upwards. Some 0.007/0.008 in. of material is removed from the faces, and they are required to be flat within 0.001 in. total indicator reading after this operation. It may be noted that this grinding operation on the faces of the smaller castings is performed towards the end of the machining sequence.

FLAT-HONING OPERATIONS

The large joint face on the main valve body casting is next honed flat within 0.0003 in. all over on the type 844-1 Microflat (A. A. Jones & Shipman,

Fig. 1. With this set-up, on a British-built Thompson bed-type surface grinding machine, side faces on valve body castings of two sizes are finished simultaneously



Ltd.) machine shown in Fig. 2. This machine is also employed for similar flat - honing operations on several other castings incorporated in the valve block assembly. The horizontal honing wheel has an outside diameter of 40 in. and a face width of 7 in., and is mounted at the top of a

ese

ger

st-

nd

ell

ng

is

he

ly,

ch

in

en

ith

he

ds,

ed

ld

be

in.

of

he

e-

de

is

es is to er ng

e.

n

spindle which is driven at a speed of 40 r.p.m. A transmission system is provided for driving a shaft above the wheel, which carries a steel spider.

In the spaces between the arms of this spider there are steel plates with apertures having outlines similar to those of the castings to be finished. These castings are placed in the apertures in the loading position at the front, so that the joint face of each rests on the wheel. The spider is rotated at about 1 r.p.m., in the same direction as the wheel, and it is also oscillated through an arc about the axis of the supporting pillar. The extent of this oscillation is controlled by the setting of an eccentric pin relative to the centre of a vertical driven shaft in a projection at the rear of the arm. This pin engages with a slot in a bracket secured to the pillar. The oscillating motion, at 10 strokes per min., causes the parts to move across the

wheel as they turn.

The spider carries a

number of brackets in which cranked levers are pivoted. The ends of these levers project above the plate apertures and carry projecting pins, which are arranged so that they bear on flat surfaces on



Fig. 2. The final operations on the joint faces of the aluminium alloy castings employed in the hydraulic valve block are carried out on this Microflat flat honing machine



Fig. 3. Joint faces on valve body castings are inspected for flatness, which must be within 0.0003 in., on this granite surface plate. Movement of an air-gauging head at the table centre are indicated on the manometer tube, which is graduated in 0.0001-in. divisions

the castings. Weights on the arms serve to hold the castings in close contact with the wheel surface. At the inner end, each lever has a roller, and above these rollers there is a cam secured to the quill whereby the spider can be raised and lowered.

As each lever approaches the front of the machine, the roller comes into contact with a rise

on the cam, with the result that the inner end is pushed down, and the weight is lifted from the casting, which can then be removed and replaced by another. Normally, one circuit of the plate, occupying about 1 min., is sufficient to remove some 0.002/0.0025 in. from the joint face and to bring the surface within the required limits for flatness. Limits on surface finish are also imposed, the maximum depth of scratch permissible being 32 micro-inches. During honing,

a mixture of mineral oils, specially compounded for the purpose to a Micromatic specification, is flooded over the wheel and passed through a filter unit seen in the background in Fig. 2.

Fig. 2.

When flatness errors on the finished work exceed the limit of 0.0003 in. mentioned above, the wheel is dressed by means of the air-operated attachment seen in the right foreground in Fig. 2. This unit incorporates two

housings connected by parallel cylindrical guidebars, one housing being pivoted on a bracket at the side of the machine. The other has a hole for a vertical pin which can be engaged with a bore in a hinged post at the centre of the wheel spindle. This post is raised for the wheel dressing operation and serves to support the housing at such a height that



Fig. 4. Equipment supplied by the Vernon Instrument Co., Ltd., is employed for checking the diameters and concentricity of the stepped valve bores in the two larger castings for the valve block assembly




Fig. 5. The upper valve body, which is here shown in plan, end elevation and section, has two stepped bores to house the valve plungers

the guide bars are in a horizontal plane. A carriage on the bars, in which the dressing diamond is mounted, can be moved at any desired rate by means of an air cylinder at the outer end of the attachment, the speed of traverse being controlled by a hydraulic check cylinder alongside.

a in ed

h-

in vo

e-ne a a is d

Considerable thought was given to the method to be employed for inspecting the flatness of the finished surfaces and the simple equipment developed is seen in Fig. 3. This equipment includes a granite surface plate supplied by Windley Bros., Ltd., in which a central hole is drilled. In the hole is fitted an air gauging head of the axial plunger type, with the plunger end projecting slightly above the surface. The head is connected to the single tube of a Vernon

manometer unit at the right, the scale of which is graduated in divisions of 0.0001 in. When the casting is laid flat on the plate and moved over the mushroom-headed plunger, variations in flatness are indicated by movements of the liquid in the tube.

At the final operation on the large casting, the finished surfaces are power brushed to remove any burrs thrown up at the edges of the valve bores during grinding or honing. This work is performed on an old Kent-Owens horizontal milling machine, the spindle of which is fitted with Tampico or bristle brushes, and the castings are then washed, and dried with air jets, in a Dawson type B, automatic unit.

Inspection of the bore diameters in both the

large and the smaller castings is carried out with the Vernon equipment shown in Fig. 4. A separate gauging head is provided for each bore in both castings, and these heads are of the mechanical contact type to avoid difficulties that may arise if air jets are used in long bores of small diameter and blind bores. Movement of the contacts serves to vary the size of an air jet within the body of the gauge, and this variation affects the height of the liquid in one of the manometer tubes shown. Ring gauges, of the nominal diameters of the bores, are provided for setting purposes and are housed in recesses in a cabinet provided for the gauging heads. The scales of the manometer tubes are graduated in 0.0001 in. divisions. Separate equipment is employed for checking the concentricity of the stepped bores on a sample basis.

OPERATIONS ON UPPER VALVE BODIES

The series of operations on the upper valve body, which is shown in plan, end elevation, and section in Fig. 5, is somewhat similar to that performed on the larger casting, and starts with machining of the flat joint face. Two location

Fig. 6. The large joint face and the two end faces are milled on this Heald type 221 single-ended machine at one set-up. After the large joint face has been milled, dowel holes are drillreamed before the castings are loaded in the vertical positions for milling the end faces

holes C, Fig. 5, are then drill-reamed, after which the castings are returned to the first machine, and the side faces are milled. The set-up on this Heald type 221, single-ended, fine-facing machine is shown in Fig. 6, and the castings are loaded at the rear position of the fixture, as seen at D, for the first operation. Location is taken from the ends of the cored valve bores at A-A and B-B, Fig. 5, which are engaged with two spring-loaded tapered dowels projecting from housings beneath the casting.

ro

ie

dr

th

th

to

an

th

pa

fix

is

ta

in

jo

W

re

is

ZC

di

w

cl

ac

fi

OI

of

pi

m

lo

b

th

lo

si

b

tl

Support against the cutting pressure is provided by a pivoted beam E, with a pad at each end. This beam is pivoted on a horizontal, spring-loaded plunger, which can be locked in position by a knurled screw, after the casting has been loaded. The plunger is normally adjusted only for a fresh batch of castings. Behind the casting there is a vertically-moving slide on the fixture, which is actuated by a horizontal air cylinder at the top, through a cam, and this slide carries two tapered dowels which are engaged with the upper ends of the valve bores when it is moved down.

After the facing and drill-reaming operations have been carried out, two castings are loaded, with opposite side faces towards the cutters, in

the fixture at the front in Fig. 6. Here, the castings are dowel-located on opposite faces of a parallel-sided support member, to which they are secured by lever-type clamps as seen in the foreground. Each clamp carries a pivoted beam with pads whereby pressure is applied to the rear face of a casting, and when they are released the clamps are drawn together at their right-hand ends by a tension spring. The ram of an air cylinder at the right (not shown) carries a double wedge which is moved into position between the right-hand ends of the levers, to bring the beam pads into contact with the castings, when the air cylinder is energized by means of a push-button.

For machining the casting faces, pairs of single-point tools, made from solid Ardoloy carbide, are set in the cutter bodies on a pitch circle of 6·5 in. diameter. The spindles are run at 1,300 r.p.m., and the table is fed up to a stop, to bring the work into engagement with the tools, and is then traversed at 11 in. per min. for the facing operation. A finished casting is seen on top of the clamping air cylinder in Fig. 6.

A 6-station Mulhead rotary indexing machine is next employed for drilling and tapping all three faces machined at the previous operation. A close-up view of the tooling is given in Fig. 7, and it will be seen that the table carries two pairs of fixtures. In the fixture at the left, which is duplicated at the opposite side of the table, the casting is held in a horizontal position, joint face upwards, on a work-plate. This plate rests on a carriage which is arranged to slide horizontally, on two cylindrical bars, to move the work to and from the clamping position.

e,

nis ne

ed

D,

m

B.

ed

th

ed

d.

d

d.

h

is

p,

ls

ł,

in

e,

n

e

n

25

y

d

at

n

ıt

e

n

e

0

n

p

When the plate is advanced, the casting is positioned beneath the fixed bush-plate and is raised by a cam mounted

on the end of a shaft which is turned by means of the ball-ended lever F. Pegs and supporting projections on the work-plate provide for approximate location, and the drill-reamed holes engage locating dowels provided on the under-side of the bush-plate as the casting is raised into the clamping position.

On the other two fixtures, one of which is seen at the right in Fig. 7, the castings are again dowellocated, with opposite faces upwards, on a parallel-sided support member, to which they are secured by substantial toggle-type clamps. It will be noted that these latter fixtures are positioned near the table edge, and that the other two are located near the centre.

At the first machining station there is a single spindle which operates on the left-hand of the two vertically mounted castings, to drill a %-in. diameter hole. There are three spindles at the second station, and one hole is drilled in each of the vertical castings and one in the horizontal casting. At the third position there are two spindles which drill one hole in the horizontal and one in the left-hand vertical casting. Six holes, some of which are cored, are tapped in the two end faces at station four, and six more holes are tapped in the horizontal face, at station five.

Holes of % in. diameter by 1.719 and 2.25 in.




Fig. 7. Various holes are drilled and tapped in all three machined faces of the upper valve body casting on this 6-station Mulhead machine. Two pairs of fixtures are mounted on the table

deep are then drilled in the two end faces of the casting, to form oil transfer ports, on a Hüller duplex pillar machine. Two simple fixtures with swinging clamps hold the castings side by side on this machine. A Pollard No. 21A drill is then employed to rough and semi-finish ream the bores at A-A and B-B in Fig. 5. Subsequently, the castings are washed before these bores are finish-reamed on a Heald type 222, double-ended, fine-boring machine. The set-up and the tooling are similar to those employed for the bores of the larger casting, as described in the previous article, and the bores are then brush-deburred before the castings are loaded on the fixture of the Thompson machine in Fig. 1, for grinding the end faces.

Flat-honing of the large joint face follows, on the Microflat machine, after which the finished faces are brushed on the Kent-Owens machine. The castings are finally washed, dried in an air blast, and inspected.

GRINDING, HONING AND LAPPING MACHINES to the value of £2,621,512 were exported during the period up to September 30 this year, which was an increase of £667,180 as compared with the value of similar machines exported in the same period of the previous year.

Osromatic Vibratory Finishing Machines

The latest addition to the mechanical finishing equipment built by Roto-Finish, Ltd., 39 Park Street, London, W.I, is a range of Osromatic vibratory finishing machines for metal and plastics parts. Each of these machines is equipped with an English Electric vibratory motor, of foot-mounted design, which is bolted directly to the under-side of the work-container. With this motor, it may be noted, vibratory action is obtained by means of matched pairs of out-of-balance weights, which are mounted close to the ends of the rotor shaft. One weight in each pair can be adjusted angularly, for altering the amplitude of the motion from 32 to 14 in., and the shaft, which is of suitably large diameter, runs at a speed of 1,500 r.p.m. in roller bearings. The workcontainer, which is lined with abrasion-resistant rubber, is of U-section fabricated steel construction,




Fig. 2. A batch of about 7,000, 0.015-in. thick laminations, as seen in the upper part of this illustration, was de-scaled and de-burred in a cycle time of 20 min. The needles for textile machines, seen below, were de-burred and polished without rounding of the points. The parts are shown before and after vibratory finishing



Fig. 1. Of these die-cast components seen before and after processing by vibratory finishing, the toy motor cars were de-flashed and the surfaces improved, for painting, in a 45-min. cycle. The remaining items were "cut down" and polished, for plating, in separate stages which occupied 4 and 2 hours

and is mounted on four compression springs.

Media are similar to those employed with barrelling equipment, and due to the vibratory motion, relative movement occurs between the medium and the work. combined with rotation of the entire mass within the container. Various advantages claimed for the process have been discussed in recent articles in MACHINERY, and some typical die-cast components are shown in the "before" and "after" conditions in Fig. 1. Attention is also drawn to the delicate components shown in Fig. 2, which afford an indication of the type of work which can be finished without damage by this process.

In operation, liquid compound is continuously sprayed on to the work-load from a distributor pipe, which is mounted above the container and extends for the full length. After passing through the load, the fluid drains from two outlets in the bottom of the container, and is collected in a storage tank, whence it is re-circulated by a motor-driven pump. With this system, which is the subject of a patent, metal particles are continuously removed from the load, and allowed to settle in the tank, and it is claimed, in consequence, that there is no need to wash the components after unloading. Moreover, the fluid can be used for successive operations over a period of some days, with substantial economies.

The range includes the types OV. 1, OV. 3, OV. 7, and OV. 10 machines, which occupy floor spaces measuring from 2 ft. 4½ in. by 2 ft. 4 in. up to 7 ft. 5 in. by 5 ft. 7 in. and the work-container on each machine has a capacity corresponding to the numeral in the designation, in cu. ft. Average loads for the smallest and the largest sizes in the range include 25 and 225 lb. of components. If required, provision can be made on the two largest units for the use of fixtures, for holding large work-pieces, and on each machine, the container is carried by a sub-frame, which is horizontally pivoted and is swung through an arc of 120 deg.



IS

d

Fig. 3. To facilitate unloading, the work-container assembly of the Osromatic type OV. machine is tipped forward by an air-operated system, and the load is here being discharged from a 7 cu. ft. capacity unit




Fig. 4. A recently-built batch-type automatic vibratory finishing machine is here shown without the enclosing covers

towards the front, by means of a push-button controlled air-operated system, for unloading. Such an operation is seen in progress on the type OV. 7 machine in Fig. 3. Doors at the front and the top of the cabinet, whereby access is gained for loading and unloading, complete enclosure of the working area, and all the interior surfaces are faced with a sound-deadening material.

There is also a 10-cu. ft. capacity machine of simpler design, in which the container is carried by the main frame, and cannot be tipped. A door at one end is opened for unloading, to allow the charge to fall on to a chute, and to assist the flow, the container can be vibrated for short periods under the control of an "inching" push-button. On the type OV. 10 and the end-unloading machines, the compound tanks have capacities of 110 and 50 gal., respectively, and as an indication of the power requirements, it may be noted that the vibrator motor on each of these machines is rated at 4 h.p. The control equipment incorporates a process timer, for stopping the motor at the end of a pre-set period.

Since the work-container does not rotate, the process may readily be adapted for automatic operation, and in Fig. 4 is seen an automatic machine which the company has recently built, for



Fig. 5. Work in connection with the development of vibratory finishing equipment for continuous operation is being carried out by Roto-Finish, Ltd., with the aid of this twin-container machine

installation in a factory in Southern England. For purposes of illustration, the covers whereby this machine is almost totally enclosed have been removed. At the beginning of each working cycle, the loading skip A, which is carried by pivoted arms, is swung upwards, to discharge a batch of components into the work-container B, which has been previously charged with the medium. After the skip has returned to the original position, the vibrator motor is started, for processing for a predetermined period, up to 4 hours, under the control of a timer, and simultaneously, the pump which provides for circulating the compound is automatically brought into operation.

Following the processing stage, the motors are stopped and the container is tipped, to discharge the work-load into a hopper. The container is subsequently returned to the original position, and from the hopper, the medium and the components are fed on to the inclined bucket conveyor seen in the foreground. Water is sprayed from distribution pipes above this conveyor, for rinsing, and from the upper end of the run, the medium and the components are discharged on to a lateral vibratory conveyor. At the end of the latter, the components are removed by a magnetic separator, and transferred to a discharge chute, and the medium is passed to a steeply-inclined bucket conveyor at the rear, whence it is returned to the container in readiness for the next cycle. The separator, also the drive motors for the conveyors and the pump in the rinsing system, are started when the container is emptied, and the period for which they run is controlled by a separate timer.

Work in connection with the development of equipment for continuous operation is being carried out with the machine shown in Fig. 5, on which there are two work-containers, arranged side - by - side and inclined in opposite directions. Advantage is taken of the rotary movement of the work-load and by means of vanes, it is caused to travel slowly towards the lower ends of the containers. The load is transferred from each container to

the upper end of the other by means of lateral vibratory conveyors, associated with one of which there may be a separating unit, for removing the components. Individual compound systems are provided for the containers, and with this arrangement, the workpieces may be passed successively through two processing stages, for de-burring and polishing, for example.

PHILIPS VARIABLE TRANSFORMERS WITH DUST PROTECTING ENCLOSURES are now available, so that these units need no longer be mounted outside dust-laden areas, even when the atmosphere contains abrasive or corrosive dust. It is claimed that no de-rating of the transformers is necessary when the new enclosures are provided, unless the ambient temperature exceeds approximately 25 deg. C. Enclosures, which are of welded construction, from steel sheet, and finished in grey "hammered" stove enamel, are available for all sizes of transformers, except the 20-amp. type. If it is required to isolate the transformer from the supply when the cover is removed, a single-pole plunger switch, which is operated by the cover, is fitted.

The sole distributors for Philips variable transformers in the U.K. are Research & Control Instruments, Ltd., 207 King's Cross Road, London, W.C.1.

M.T.T.A. Design Course Awards

Certificates to mark the successful completion of the 2-year course in machine tool design and technology instituted by the Machine Tool Trades Association, were presented to the first group of nine students at the Grand Hotel, Manchester, on December 1. It may be recalled that the introduction of this course was announced by the M.T.T.A. in 1959, and that studies are pursued at Manchester College of Science and Technology (which now forms part of the University of Manchester), under the direction of Dr. F. Koenigsberger, Professor of Machine Tool Engineering. The course is of post-graduate standard, and is intended for young men in the machine tool industry who have already shown aptitude for design. A scholarship scheme on a generous scale, with an admission rate of ten students annually, has been established by the M.T.T.A., and this scheme has now entered its third year.

Nine certificates were awarded on this occasion to recipients who have already returned to industry. In addition a special prize of 25 guineas was given to Mr. Brian Hodgson (William Asquith, Ltd.), who was the outstanding student of the group. The other recipients were Mr. J. R. Earnshaw (Snow & Co., Ltd.), Mr. H. C. Fletcher (James Archdale & Co., Ltd.), Mr. R. G. Francis (Alfred Herbert, Ltd.), Mr. R. H. H. Hartley (James Archdale & Co., Ltd.), Mr. D. Horobin (B.S.A. Tools, Ltd.), Mr. D. S. T. Nunney (James Archdale & Co., Ltd.), Mr. A. Shaw (William Asquith, Ltd.) and Mr. T. D. Yarwood (H. W. Kearns & Co., Ltd.).

The presentation was attended by Dr. B. V. Bowden, principal of the Manchester College of Science and Technology, Dr. W. Johnson, head of the Department of Mechanical Engineering, and Dr. Koenigsberger. In introducing Mr. R. D. G. Ryder, past-president of the M.T.T.A. and managing director of Thos. Ryder & Son, Ltd., the chairman, Mr. C. A. Sparkes, director of H. W. Kearns & Co., Ltd., apologized for the absence of Mr. J. C. Snow, president of the M.T.T.A., who had had to attend a meeting of the F.B.I. Export Council for Europe.

Mr. Ryder expressed his own pleasure in deputizing for Mr. Snow, and mentioned that he had been closely assosciated with the scholarship scheme from its inception. He pointed out that although the machine tool industry, like all others, had its faults and deficiencies, it offered a challenging career, with real opportunities for progress and responsibility. Some four years ago, it was felt that design and development based solely on ex-

perience and practical judgment would not suffice, and that there was a need for engineers who could tackle new problems analytically, with the background of a systematic study of technological principles, and with the aid of the tools of mathematics and engineering science. It was considered that there were many able and possibly brilliant young engineers among the design staffs of the industry who would benefit from study at a university college with specialized knowledge, interest, and experience of machine tools. The M.T.T.A. scholarships were the result of happy and fruitful co-operation-not for the first time-between the machine tool industry and the Manchester College of Science and Technology, which was thought to provide the finest education in the country in the particular subjects required.

Continuing, Mr. Ryder expressed the thanks of the Association to Dr. Bowden, Dr. Johnson, Dr. Koenigsberger, and their staff for their foresight in meeting the needs of the students, their elegant treatment of the course, and their enthusiasm. He pointed out that sacrifices had been made by the college in providing the necessary facilities, by the employers of the students who had lost the services of some of their best young designers for two years, and by the students and their families due to intensive study, separation, and dislocation of family life.

A brief reply to Mr. Ryder was made by Mr. Brian Hodgson on behalf of the recipients of certificates, in which he expressed thanks to the M.T.T.A. for the opportunity for advanced study which had been made available.

It may be of interest to give some details concerning the course in machine tool technology and design. All M.T.T.A. scholarship holders are treated as a group, and the first year is devoted to the more academic aspects, including lectures and laboratory work relating to performance requirements, design specifications, and basic design and calculations for machine tools; electrical engineering and electronics; hydraulics; vibration; friction and lubrication; control engineering; properties and behaviour of engineering materials; standardization; metrology; ergonomics; safety regulations; automation; and kindred subjects.

During the second year of the course, the students are sub-divided into smaller groups for work on a design project. The subjects are chosen to ensure that the members of each group are concerned with machine tools outside their previous experience, and that each member carries out work on some new aspect of design. For example, a

student previously concerned with milling machines may be allocated to a group engaged in the design of a gear grinding machine, and if his previous work has been related to gearboxes, he may be made responsible for the design of the main structure. During this second year, lectures are given by machine tool specialists from a range of firms in the industry, and students have the opportunity of discussing, and obtaining advice on, any particular aspects of the design they are undertaking. When completed, the design has to be defended by the students against the criticisms of a committee.

Students are also given certain tasks to perform in connection with the research projects undertaken by the college. During the two long vacations, it is arranged for each sudent to work with a company engaged in the building of machine tools different from those made by his own firm, first, in this

country, and then abroad.

Journal of Production Research

The first issue of the International Journal of Production Research has recently been published by The Institution of Production Engineers, 10 Chesterfield Street, London, W.1. The Journal will be issued quarterly in English, French and German, and Professor N. A. Dudley, Ph.D., Department of Engineering Production, University of Birmingham, has been appointed editor, and Dr. S. Corlett, Department of Engineering Production, University of Birmingham, and Dr. S. Eilon, Imperial College of Science and Technology, London, associate editors. In addition, a panel of consulting editors has been appointed, representing Australia, India, Norway, Spain, Sweden, Switzerland, the U.K., the U.S.A., and West Germany.

In the editorial in the first issue, Prof. Dudley has explained that the journal is primarily intended "to provide a vehicle for the publications of those university and other research workers whose primary interest is in advancing the science of production, and for whom, until now, there has been no single and appropriate journal." Papers and reports prepared by university and industrial research personnel will be published in the journal which will cover all aspects of production in a variety of technologies, for the guidance of others engaged in research, also lecturers at universities and colleges. For example, it is hoped that ergonomists will submit papers for publication on the performance characteristics of workpeople, to assist those engaged in operational research who are frequently required to make assumptions of such performance, also on the nature of human control systems which it may be of advantage to simulate for the design of automatic control

arrangements. Moreover, it is hoped that research reports will be received for publication on the psychological and sociological, as well as the economic and technical aspects of production.

In the first issue, papers are presented by authors in this country, the U.S.A. and Australia, under the headings:—two inventory control models; an electrical analogue for solving transportation problems; selective assembly—its analysis and applications; research in machining high strength materials at elevated temperatures; a note on a method of estimating the precision of time study observations; estimation of service requirements for production purposes; and optimal revision periods.

The Editorial Committee of the Institution is responsible for the administration of the journal, and correspondence relating to subscriptions should be addressed to:—Miss M. S. C. Bremner, International Journal of Production Research, 10 Chesterfield Street, Mayfair, London, W.1.

Supports for Measuring Standards

In Machinery, 99/944—25/10/61, an article was published describing the new SIP type CLP-10 photo-electric comparator, and details were given of the means whereby a line standard to be checked is supported at the Bessel points. Enquiries have been received requesting more detailed information on Bessel points, and it may be of interest therefore to consider the various supporting systems which are set out in Vol. XXI of Les Travaux et Memoires de Bureau International des Poids et Mesures, Sèvres, Paris, France.

Bessel Points.—Supports at these points are employed when checking line standards, since they ensure the minimum shortening of overall length. The supports are usually cylindrical, and their centres are calculated from the formula d=0.5594 L, where L= the total length of the standard and d= the centre distance of the supports.

AIRY POINTS.—Supports at these points are used for checking end standards, since they ensure that the tangents to the curves at the extremities of the standard are horizontal. As a result, the defining ends of the standard are vertical and parallel. The formula is $d=0.5774\ L$.

It may also be noted that the formula $d=0.5537\ L$ gives the centres of supports that ensure the minimum deflection. Such supports are not normally used for standards work, but are of value in machine tool design, where it is necessary to minimize the curvature of a slideway, for example.

Finally, supports placed at centres calculated from the expression d = 0.5505 L will ensure that the tangents to the curves immediately above the support points are horizontal.

NEWS OF THE INDUSTRY

Manchester and District

reh the

ors the ecns;

at

sti-

ns:

on

is

al,

ıld

er-

10

cle

P-

ere

be

ts.

re

ay

p-

of

ial

re

ey h.

eir 94

nd

ed

at

of

he

_

re

ot

to

e.

ed

at

ne

B. & S. Massey, Ltd., Openshaw, Manchester, 11, report an increasing flow of orders for their range of drop hammers, and forging and trimming presses. Because of long experience in this field (this year marks the centenary), the company has been requested to act in a consultant capacity by a number of drop-forging concerns abroad. A large proportion of the output is exported, and current orders include several from overseas, including India and Yugoslavia, for the supply of complete forging plants.

Crossley Brothers, Ltd., Crossley Works, Openshaw, Manchester, 11, are still busy with the manufacture of the range of diesel engines for which they are well known. The company exports a high percentage of the production. Marine engine orders have recently been completed for Holland, Poland, Finland, the Persian Gulf, Hong Kong and several Commonwealth countries. Stationary engines recently built have included units for India and Ghana. Among orders lately executed for the home market were some for the supply of engines for use in connection with atomic power-stations.

The general engineering department of the company is busy on contract work, and customers are taking advantage of all the services offered by the department, which include machining, fabrication, assembly work, and a foundry in which casting in Meehanite up to 20 tons can be produced. A recent development within the Crossley Group is the acquisition of Furnival & Co., Ltd., who specialize in the production of guillotines for the printing industry. All the plant and facilities have been transferred to the Reddish factory of the Group.

FRY'S METAL FOUNDRIES, LTD., Hargreaves Street, Manchester, 4, operate a branch foundry for the Group and specialize in the refining of tin and lead alloys from which solder in ingot and stick forms, and printing metals are made. The branch, it is stated, is fully occupied in meeting the demand. Associated products produced elsewhere in the Group are also stocked, and include fluxes, wire-type solder, and printer's melting equipment.

WILLIAM E. CARY, LTD., Redbank, Manchester, 4, are well-known for road springs for motor vehicles and associated equipment such as suspension components, and are suppliers to most of the leading vehicle manufacturers, as well as various public transport undertakings.

The Laminaire system of suspension which the company introduced three years ago is becoming increasingly popular, both as original equipment and for replacement. With this system, it is

The foundry pattern here illustrated, for rotary compressor unit bodies for Cooper-Stewart Engineering Co., Ltd., Letchworth, Herts., was recently cast in Araldite epoxy resin by J. Hobkirk, Sons & Co., Ltd., Bedford. A considerable saving in time was achieved by the use of this material instead of casting the pattern in aluminium, owing to the reduction in the amount of finishing required. In addition, it is stated, Araldite has much better wearing properties than aluminium.



claimed, constant ride characteristics are obtained, whether a vehicle is unladen or fully loaded.

Full production is also being maintained in the company's forge, and forks, which are supplied to most of the leading fork-lift truck manufacturers, account for a large proportion of the work in progress. Forks weighing up to 4 cwt. each are made, as well as comparatively small sizes. The press shop, which has equipment of capacities up to 1,000 tons, is busy on a wide variety of pressings, and a contract for the production of railway plates, and rail chairs, has just been completed. In the fabrication shop, cabs and lifting arms for earthmoving equipment are being manufactured.

Sheet metal work is undertaken by another department, and whereas work of a general nature is occupying some of the capacity, the section specializes in producing cable trunking, for which a steadily increasing demand is reported. Other products of the company include agricultural and industrial conveyors, which are marketed by their associates, Cary-White, Ltd., and for this equipment also, it is stated, there is a satisfactory call.


This firm, which was founded 113 years ago, has always maintained a progressive outlook, and at various times reorganizations have taken place, to provide for increased efficiency. The latest addition to the facilities is a spacious tool-room and development department. Plant recently installed in the manufacturing departments has included a 30-cwt. hammer in the forge, and a 1,000-ton press in the press shop.

G.P.A. Tools & Gauges, Ltd., Harper Road, Wythenshawe, report that they have a well-filled order book covering press tools, jigs, fixtures, plastics moulds, precision components, and special equipment.

Re-organization over the past 18 months has made it possible to accept a greater volume of work and maintain satisfactory deliveries.

Considerable new plant, which includes Lang, V.D.F., and Holbrook lathes, a Deckel KF12 diesinker, Kearney & Trecker and Cincinnati vertical millers, and a Churchill VD8 surface grinder with 42- by 16-in. table, has been installed to increase capacity and provide improved facilities for high class tool work. All the shops have been requipped with modern fluorescent lighting which provides practically shadow-free, high-intensity, illumination at working level.

Johnson Metal Co., Ltd., Sharp Street, Manchester, 4, report a brisk demand for the Swissbuilt Schlatter resistance welding machines for which they are agents. Machines are offered in sizes from 1½ kVA. to 850 kVA. in the standard range, and larger welders of special design can be provided if required. Machines were recently supplied for butt-welding support ropes for the Forth Bridge. The company is also agent for the range of German-built Niehoff wire-drawing equipment, and units are available for drawing wires down to 0.0006 in. diameter. Large quantities of this equipment have been sold in this country,



The above graphs show the values of machine tool orders and deliveries for the twelve months ended September 1961, also the values of orders in hand

much of it to the leading cable manufacturers. Other items marketed by the company include tungsten carbide and diamond drawing dies, also machines for polishing these materials.

J. J. MARKLEW.

The South

oad.

lled

res, cial

has

of

ing,

die-

ical

vith

ase

igh

re-

ich

ity,

an-

iss-

for

in

ard

an

tly

he

he

ip-

res

of

ry,

INDUSTRIAL IMPREGNATIONS, LTD., Poyle Trading Estate, Colnbrook, Bucks., are now established in recently built works situated at a short distance from their original premises. With a floor area of 12,000 sq. ft., the new factory affords improved facilities for the impregnation of porous castings with polyester resin. Work in progress at the time of our visit included the impregnation of motor vehicle oil pump bodies, sumps for diesel engines, supercharger casings, food machinery parts, machine tool castings, crankcases for 6-cylinder diesel engines for railway traction purposes, and a variety of parts for Government Departments.

It is now customary for many firms to send all castings of certain types, for example engine crankcases, for impregnation, to ensure that any porosity, either apparent or undetected, is sealed. Castings are impregnated in a fully machined condition and after this process do not require any further treatment before use. Threaded holes and machined cavities, it is stated, are left free from residue on completion of the impregnating cycle, and treatment can be undertaken, by arrangement, as an emergency service. An autoclave of 6 ft. diameter by 7 ft. 6 in. deep enables large parts to be treated.

This company has established a new factory for the impregnation of castings in Sparkbrook, Birmingham, and similar services are shortly to be provided in Milan, Italy; Calcutta, India; and

Buenos Aires, Argentina.

BEANSTALK SHELVING, LTD., Industrial Estate, Chichester, Sussex, have a good order book for a wide range of wire products which find numerous applications in industry. A recent addition to the Beanstalk series of wire trays is the Stacko-Rack which is available at present in two sizes. These trays are designed for stacking, and can be nested when empty, the erected height then being reduced by about two-thirds. A stack of the larger type has a maximum load capacity of 600 lb. and for the smaller size the corresponding capacity is 360 lb.

It is reported that a firm is using Stacko-Rack containers to transport scissors between different processing stations in a factory. The scissors are suspended in the mesh openings which are of similar dimensions for each container, and a ready and accurate means of checking batch contents is thus afforded, without tedious counting. An additional benefit is the avoidance of damage to the scissors through repeated handling. The extra hanging space for long-bladed scissors has been provided by modifying the rest bars, to enable alternate trays in a stack to be inverted.

A good demand is reported for Beanstalk Jacko-Rack 3-tier and 4-tier trolleys with heavy-duty wheels. The wire trays are provided with removable separators which enable compartments of different sizes to be formed, as may be required for transporting mixed batches of parts in stores and workshops.

W. E. SYKES, LTD., Staines, Middlesex, are still very busy with orders for machine tools for gear production and we are informed that there is a sustained demand for V 10 B vertical gear generators; also for Sykomatic vertical machines, which are widely employed for the quantity production of internal and external gears. Sykes machines are installed in many motor car factories in this country and other parts of the world, and we may note that an important vehicle manufacturing firm has incorporated one of the universal gear finishing machines in an automatic link line.

SYKES MACHINE TOOL Co., LTD., Staines Middlesex, are experiencing a satisfactory call for various special purpose and standard machine tools. demand for heavy-duty lathes is well maintained and growing interest is reported in Boehringer machine tools. In this connection we may note that two crankshaft lathes of this make have been ordered by a well known company in this country.

F. W. HERRIDGE.

Research and Productivity Exhibition

An Industrial Research and Productivity Exhibition is to be held at Bingley Hall, Birmingham, from 10 a.m. to 6 p.m. daily, from May 23 to 31, 1962, under the sponsorship of the Birmingham Productivity Association, and it was recently announced that some three-quarters of the space allocated for display purposes had already been booked.

So far, D.S.I.R. and four other research organizations, also 14 well-known industrial firms from the Midlands and other areas, have agreed to participate in this exhibition, which is intended to focus attention on the work of research laboratories and the advantages to be gained by employing modern production techniques.

The largest display will be staged by the West Midlands Gas Board, and will draw attention to some of the applications of town gas in a number of industries and for different forms of heat treatment.

Conferences on various subjects, to be announced later, and industrial film shows will be arranged, and it is anticipated that parties from the works of many of the 200 member firms of the Birmingham Froductivity Association will visit the exhibition. Organized visits by students from colleges and grammar schools will be encouraged, and in this connection it may be noted that on a number of stands attention will be drawn to the training facilities available to young people embarking on industrial careers.

Applications for the remaining stands and stand sites in the exhibition building may be made by firms operating in the Midlands and elsewhere to W. G. Appleyard, 71 Broad Street, Birmingham, 15 (telephone, Midland 8073), who is organizing the exhibition on behalf of the B.P.A.

Boulton & Paul Fabricating Plants

The accompanying illustration gives a general view of a mechanized fabricating plant for structural steel which has recently been supplied by Boulton & Paul, Ltd., Riverside Works, Norwich, and installed in the London works of the subsidiary Moreland Hayne & Co., Ltd. In the foreground is seen the vertical saw supplied by Clifton & Baird, Ltd., behind it, to the right, the Archdale 12-spindle horizontal drill for flange holes, and in the background, the 6-spindle vertical drill for web holes, also by Archdale.

Boulton & Paul, Ltd., have also recently com-

pleted a plant of this type for export to Australia. This plant is destined for the South Melbourne works of Johns & Waygood, and has been specially designed to meet that company's requirement. Costing approximately £100,000, it occupies a floor area of about 21,000 sq. ft., and the complex system of powered conveyors and transfer benches is controlled from three push-button stations. The 13th to be built by the company since it was decided to offer such equipment for sale in 1955, this latest plant has a capacity for sawing and drilling steel sections up to 36½ in. by 50 ft.

Exporting to Western Germany


Information concerning the export of British products to Western Germany was given by four German marketing experts at a recent London conference, which was arranged by the London School of Marketing, Ltd., Newspaper House, Great New Street, E.C.4.

Attention was drawn to some similarities in the British and German economies. It was pointed out, for instance, that there were inflationary tendencies in both countries, and shortages of skilled labour. At present, some 500,000 vacancies existed in German industry, which operated on a basic 44-hour working week.

On the subject of advertising, it was stated that some 85 per cent was accounted for by newspapers

and periodicals, and that the remaining 15 per cent was divided almost equally between television, commercial radio, and posters. A speaker emphasized that advertisements for British goods should quote metric measurements, and that prices should be given in German cur-Attention was rency. drawn to the importance of studying the German market carefully, and it was explained that it was inadequate merely to translate sales literature and advertisements.

In connection with the legal aspects of selling in Germany, a German lawyer explained some differences between German and British commercial law.



Mechanized structural steel fabricating plant supplied by Boulton & Paul, Ltd., to their subsidiary, Moreland Hayne & Co., Ltd.

Eclipse Tool Department Extension

To provide additional space and machine capacity for the Engineers' Tool Department of James Neill & Co. (Sheffield), Ltd., to enable the increasing demand for tools in the Eclipse range to be met, a new 4-storey block has recently been brought into use at the company's Napier Street, Sheffield, premises, which has increased the floor area available to the Department by 44 per cent. This new block has been erected on the site of a single-storey building, which housed the material stores and the heavy milling and heat treatment sections, and alterations to previously existing

buildings have been carried out.

ia.

ne

llv

nt.

ex

es

he

as

5.

nd

sh

u

n-

ol

W

d

es

at

rs

at

e

n

In the new block, the various floors are served by a lift system of ample capacity, and incoming raw material, such as castings, and steel bar, sheet and strip, is received and stored in a section on the ground floor, where provision is for accommodating the largest road transport vehicle. Also on the ground floor there is a machine shop, in installed which are singleand 6-spindle automatics, a large number of capstan lathes, and heavy vertical milling machines and shapers. Other machine shops are situated on the first and second floors, the second-floor shop, a general view of which is given in Fig. 1, being equipped for light secondary operations' such as milling, shaping, turning, drilling, and tapping. The heat treatment section, on the third floor, is seen in Fig. 2, and it may be noted that the furnaces have pyrometric temperature control, and that hardness testing equipment is provided. Complete tools are assembled on this floor, and are tested and finally inspected, before being packed for despatch to the company's warehouse.

The flow of work in progress is controlled by way





Fig. 1 (above). General view of the light machine shop, on the third floor of a new 4-storey block, which has been provided for the Engineers' Tool Department of James Neill & Co. (Sheffield), Ltd.

Fig. 2 (left). The heat treatment shop on the third floor of the new block

of a store on the second floor, in which a stock of finished components is held for issue to the assembly section, and the planning office is situated on this floor. There are other offices on the first floor, together with a general store and the maintenance and cutter grinding sections.

Particular attention has been paid to working conditions, and the block is spacious and welllighted. Heating is provided by a temperaturecontrolled system, and in the heat treatment section, there is a fume extraction system.

Industrial Notes

Burflex, Ltd., 7 Canal Street, Brierley Hill, Staffs. (telephone 77136) will undertake the regrinding of carbide burrs of a wide range of shapes and of any make. Normally, it is stated, the burrs can be reground and returned in a few days.

George Cohen Sons & Co., Ltd., inform us that their Engineers' Tool Department has been moved to the machine tool headquarters at 23-25 Sunbeam Road, London, N.W.10 (telephone, ELGar 7222). A large stock of tools and fine measuring equipment is carried, and the counter service will be continued at the new address.

J. A. Crabtree & Co., Ltd., Lincoln Works, Walsall, Staffs., recently opened new showrooms at 230 Tottenham Court Road, London, W.1, where examples of the company's Closegang and other wiring accessories, including 13 amp. socket-outlets, and type C-50 circuit breakers, are on view, also lighting fittings by C. M. Churchouse, Ltd.

HERBERT HUNT & SONS, LTD., Elsinore Road, Old Trafford, Manchester, recently received an order for three reamer flute milling machines from the Morse Twist Drill and Machine Co., Mass., U.S.A. Based on the company's standard designs, these machines will be modified to suit the customer's requirements.

The British Industrial Truck Association, York Mansion, 94-98 Petty France, London, S.W.1, are offering to the winner of their annual competition a place at the 9th Material Handling Training Course to be held at Lake Placid, U.S.A., in June, 1962. The closing date for the competition is March 15, and particulars and application forms can be obtained from the above address.

The Midland Electric Installation Co., Ltd., Cyprus Works, Upper Villiers Street, Wolverhampton, recently announced that further development work is now in progress in connection with their range of Hotfoil flat element heating tapes. It is planned to introduce flame-proof types, also tapes for temperatures up to 1,000 deg. C. Silicone rubber impregnated tapes suitable for heating to temperatures up to 250 deg. C. are already available.

RAPID DELIVERY OF GRINDING MACHINE TO FRANCE.—
To obtain an order in competition with a stock delivery machine, Burton Fils, Paris, the agents for A. A. Jones & Shipman, Ltd., Leicester, recently arranged for the despatch of a Jones-Shipman precision grinder by charter aircraft. This machine, which was taken from the reserve held for this agent at the maker's works, was installed in the cus-

tomer's factory in Paris within 24 hours. An incidental advantage of this method of transport was that the machine could be sent unpacked, with a minimum of preparation.

UNION CARBIDE, LTD., Kemet Division, 8 Grafton Street, London, W.1, are now marketing solid tantalum capacitors which are claimed to offer considerable advantages from the standpoints of space and weight saving and reliability. These capacitors are at present being imported, but it is planned to start production at the factory at Aycliffe, Co. Durham, in the early summer of 1962.

The Argall Machine Tool Co., Ltd., 162 Buckingham Palace Road, London, S.W.1, the newly-formed machine tool company of the Chamberlain Group, have been appointed sole agents in the United Kingdom and the Commonwealth for the German-built range of Bochumer section-bending machines. There are eight machines in the range, and capacities cover angle sections from 2 by 2 by $\frac{3}{8}$ in. to 8 by 8 by $\frac{7}{8}$ in.

TEDDINGTON AIR GAUGING EQUIPMENT.—The gauging divisions of Teddington Industrial Equipment, Ltd., have been transferred as a unit to Teddington Aircraft Controls, Ltd., Cheapside Chambers, Cheapside, Reading, Berks. (telephone, Reading 55235), and all correspondence concerning Teddington air gauges should in future be sent to this address. Increased manufacturing, development, and design facilities will thus be afforded to meet the growing demand for these air gauges.

DORMAN MACHINERY SALES, LTD., Woodside Hill, Chalfont St. Peter, Bucks., inform us that they have recently been appointed sole United Kingdom agents for the complete range of machines built in the U.S.A. by The Lees-Bradner Co., Cleveland, Ohio. This range includes single spindle gear hobbing machines up to 16 in. diameter capacity; high production rotary hobbers with numbers of spindles from 3 to 8; horizontal spline hobbers; and thread milling machines.

BOWTHORPE HOLDINGS, LTD., Gatwick Road, Crawley, Sussex, and the Deutsch Co. of Banning, California, have agreed to form a jointly owned company, HELLERMANN DEUTSCH, LTD., in which the former will have a 51 per cent holding. The new company will manufacture and market the range of Deutsch connectors for electrical conductors, also the range of connectors and auxiliary equipment made hitherto by the Connectors Division of Hellermann, Ltd. A factory for the new company is to be built at East Grinstead, Sussex, and will be completed during 1962.

ORDERS FOR ENGINEERING AND ELECTRICAL GOODS.—The total volume of net new orders received by the industries producing engineering and electrical goods (Order VI of the Standard Industrial Classification), locomotives and railway track equipment, railway carriages and wagons, heavy commercial vehicles and wheeled tractors, in September, was 5 per cent more than a year earlier. New export orders were 4 per cent higher, and home orders, which had fallen during June to August, rallied in September and were 6 per cent more than in September, 1960. In the third quarter new home orders were 2 per cent less and new export orders 3 per cent more than in the corresponding period of 1960. With deliveries rising during September there was little change in the orders-on-hand position, an increase in export orders having been offset by a fall in the figure for home orders.

de un sta

Ch

Es "

ite in K

av pij ha all

tu fu we

pr hy pl

H n ai ci

BSh

ti

n 1 0 T

r c l f

Trade Publications

tal

ne

on.

et,

ors

m

tv.

is

Ŧe,

m

ne

en

he

er

in

2

ng

ve

ls.

cs.

ce

be

p-

et

11,

ly

he

he

es

er

of

ad

ve

nt

et

d.

of

s,

n

w

er

e

IMPERIAL CHEMICAL INDUSTRIES, LTD., Heavy Organic Chemicals Division, Millbank, London, S.W.1. Brochure giving full information on the properties and applications of Thermex heat transfer medium for temperatures up to 400 deg. C.

Pantak, Ltd., Vale Road, Windsor, Berks. Folder, describing the company's 300- and 400-kV mobile X-ray units. Each unit comprises an X-ray tube carried on a stand of parallel link arm design, which, in turn, is mounted on a truck.

PHOTOELECTRONICS (M.O.M.), LTD., Oldfields Trading Estate, Oldfields Road, Sutton, Surrey. Brochure entitled "Photoelectronics in Industry" in which a wide range of equipment is illustrated and briefly described. These items include, for example, an industrial smoke density indicator and alarm.

Parkinson Cowan Industrial Products, Fitzalan Streets Kennington Road, London, S.E.11. Booklet describing the range of Parkinson-Schwank gas radiant space heaters for industrial and commercial applications. Types are available for wall, horizontal, and angle mounting, and for pipe suspension.

AEI-BIRLEC, LTD., Tyburn Road, Erdington, Birmingham, 24. Folder describing the Birlec JFC Mk.II electrically heated furnaces for accurate heat treatment at temperatures up to 700 deg. C. These general purpose, batch type furnaces, of vertical cylindrical design, are available with work baskets of 10 in. diameter by 10 or 20 in. deep.

FAWCETT PRESTON & Co., LTD., Bromborough, Cheshire, Publication FP122 describes the company's 10-ton, hand-operated, bench type laboratory hydraulic press, also 50-ton hand-operated, upstroking platen and stereo hydraulic presses. Another publication (No. 123) is concerned with hydraulic presses for compression and transfer moulding of plastics, with capacities from 50 to 400 tons.

SCOTT BADER & Co., Ltd., Polyester Division, Wollaston, Wellingborough, Northants. The company's Polyester Handbook, 1961 edition, comprises 130 pages with numerous illustrations and a comprehensive index. There are chapters devoted to general characteristics; chemistry; curing and general formulations; reinforcements; Scott Bader polyester products; ancillary products; mould release agents; gel coats; methods of fabrication; applications; design considerations; quality control; visible flaws and common defects; machining, finishing and repair; and properties.

STEWARTS & LLOYDS, LTD., Broad Street Chambers, Birmingham, 1. Well-produced 38-page brochure (ref. S & L 872) concerned with standard square and rectangular hollow steel sections, which are available in hot-finished welded and hot-finished seamless ranges. Squares from 1 to 3\frac{1}{6} in., and rectangles from 1\frac{1}{6} by \frac{1}{6} it to 5 by 2\frac{1}{6} in. outside dimensions, are included in the welded range. The seamless range covers squares of 4, 4\frac{1}{6}, and 5 in., and rectangles of 5 by 2\frac{1}{2}, 6 by 3, and 6 by 4 in. Sections of both types are available in various wall thicknesses. Numerous applications in the engineering and building fields are illustrated.

MACHINERY'S ENQUIRY BUREAU

For many years Machinery has provided an enquiry service not only for subscribers and advertisers but for all engineers in need of such information as the names of makers—or their agents—of machines or equipment for performing particular operations, suppliers of various classes of material, firms with facilities for undertaking certain types of work, owners of trade names, and agents for foreign machine builders. If you have such a problem write (Machinery, Enquiry Bureau, Clifton House, 83-117 Euston Road, London, N.W.1) or telephone (Euston 8441, 2 lines). This service is, of course, entirely free.

The Price of a Subscription to MACHINERY is 52 Shillings per annum, post free, to any part of the world.

Subscribers are not bound for any definite period of subscription. We send MACHINERY, post free, each week until told to stop. Subscribers can pay yearly, half-yearly, or quarterly, pro rata. (Cash with order.)

To MACHINERY, National House, 21 West Street, Brighton 1.

Please send me/us MACHINERY every week until I/we tell you to stop, for which I/we enclose remittance of 52 Shillings per annum or pro rata

Name	 	
Address	 	
*Position	 	
*Firm	 ing records only	
MACHINERY through your le	by single copies or	subscription
		13/12/61

MANUSCRIPTS FOR BOOKS covering all branches of engineering production will receive careful consideration and should be sent to the Manager, Book Dept., MACHINERY, National House, 21 West Street, Brighton, 1.

CONDITIONS OF SALE AND SUPPLY.—MACHINERY is sold subject to the following conditions:

That it shall not, without the written consent of the publishers first given, be lent, resold, hired out or otherwise disposed of by way of trade except at the full retail price of 1s. 3d. and, that it shall not be lent, resold, hired out or otherwise disposed of in a mutilated condition or in an unauthorised cover by way of trade; or affixed to or as part of any publication or advertising literary or pictorial matter whatsoever.

Matched Machining or Selective Assembly?

(Continued from page 1351)

piston is also stamped automatically in accordance with the skirt size classification. In addition, for ease of selection at assembly, pistons of different size grades are segregated as they are discharged from the machine.

To complement these two machines there are others for automatically gauging and classifying connecting rods and cylinder bores, and it is evident that for a very modest addition to the manufacturing cost, such an installation enables a high standard of product quality to be maintained without unreasonable demands on the machine shops.

It is likely that both matched machining and automatic gauging for selective assembly will be increasingly employed in the future to solve the problems of obtaining extremely close fits without

prohibitive cost.

Extended Gear Cutting Facilities

Campbells & Hunter, Ltd., Saynor Road, Hunslet, Leeds, a subsidiary of the R. W. Crabtree Group, are extending their gear cutting facilities to cover smaller sizes than have been handled hitherto. To this end, additional equipment is to be provided and a special Sykes HV14 hobbing machine has already been installed, to permit high output of batches of precision gears. This machine is arranged to enable worm wheels down to 3:1 ratio to be machined by hobbing or fly-cutting. Climb or conventional hobbing can be employed for the production of spur and helical gears, splined and serrated parts, and sprockets, with diameters from $\frac{1}{2}$ in. to 14 in.

Personal

MR. B. PRINGLE, M.B.E., consultant and manager, Industrial Applications Engineering Department, Motor and Control Gear Division, Associated Electrical Industries, Ltd., Crown House, Aldwych, London, W.C.2, has retired after 47 years' service.

The following new appointments have been announced:—
MR. VERNON H. WILLEY, as marketing manager (stainless steels) for Firth Cleveland Steel, Ltd., Rotherham, Yorks.

MR. E. R. HENSCHKER, A.M.I.MECH.E. and Mr. R. M. L. ELKAN, B.Sc. (Eng.), A.M.I.Mech.E., as directors of The Loewy Engineering Co., Ltd., Bournemouth.

Mr. G. Mogford, as works manager of the Croydon factory of Remploy, Ltd., the national organization for employing severely disabled people.

Mr. Hedley Gardiner as Contracting Department manager for Arco Rewinds, Coventry Road, Sheldon, Birmingham, He will be responsible for providing plans and drawings for complete wiring installations for new factories and other buildings. Mr. C. A. Griffin, as chief engineer (cars) for The British Motor Corporation, Ltd., Longbridge, Birmingham. He has been deputy chief engineer of the Corporation for the past two years.

Mr. W. Crossland, A.M.I.E., as director and general manager of Uni-Tubes, Ltd., 197 Knightsbridge, London, S.W.7, and the subsidiary Portland Plastics, Ltd., and Mr. John Fisher, as sales manager of Uni-Tubes, Ltd.

MR. K. J. COLEMAN, B.Sc. (Eng.), A.M.I.Mech.E., A.M.I.E.E., A.F.RAe.S., as chief engineer of Ketay, Ltd., Eddes House, Eastern Avenue West, Romford, Essex, a member company of the Plessey Group.

Mr. G. D. Sparrow, M.I.Prod.E., general manager of the mechanical and works engineering departments, as a director of Atlas Lighting, Ltd., Thorn House, Upper St. Martin's Lane, London, W.C.2.

MR. F. J. EVEREST, M.Sc., M.I.Mech.E., as managing director of Vickers Sperry Rand Limited, New Lane, Havant, Hants., (formerly Stein Atkinson Vickers Hydraulics, Ltd.). He succeeds Mr. C. H. Williams, who has resigned from this office, but continues to hold the position of chairman of the board.

Obituary

Mr. W. H. Heron, group works engineering director of Raleigh Industries, Ltd., Nottingham, has died at the age of 65, after being ill for several months. A native of Halifax, he had completed more than 40 years' service with the company. For the first 11 years he worked as a press tool maker, rate fixer and estimator, and subsequently held various positions of increasing importance.

Scrap Metals

MIDLANDS.—Although there has been no general improvement in the demand for ferrous scrap, one Midland steelworks has been able to take slightly higher tonnages of basic steel material. The increase in allocations may only be temporary, but in the circumstances prevailing, local merchants are glad of any outlet, however small, for disposal of processed scrap. Except for a few special orders for first quality short heavy material, merchants are without markets for foundry steel, and lower grades such as shovelling scrap are only being bought at steelworks prices. Movement of chipped and bushy steel turnings is still limited and it is unlikely that prices will improve as demand for export is equally poor.

Cast iron scrap continues to move reasonably well. Demand for the lighter material is not as strong as formerly, but merchants have found that as one market closes another opens, and material is cleared at fairly stable prices.

The position at many merchants' yards, with stocks increasing in spite of reduced buying prices, is causing concern, and it is to be hoped that allocations will be considerably increased early in the New Year.

Offers for scrap from local factories for next year are now being made, and it is likely that prices will take second place to guarantees of regular clearance by the merchants who secure the contracts.

Machine Tool Share Market

The

m.

for

ral

on,

IR.

E.,

ay,

rd.

of

s a

St.

ing

ne,

Ty-

has

ion

of of of order of order of order of order of order ord

and s of nlv ocal for ders out ling oveand exvell. rly, ther ocks sing connow lace who

The undertone of stock markets was firm during the period under review, but quiet conditions prevailed in most sections. Buying interest was selective, and, in general, price changes were small and irregular.

After it had remained steady for the most part, there was a reaction in the gilt-edged section, and British Funds, together with home corporation and Dominion loans, finished with small declines.

A satisfactory tone was maintained in the commercial and industrial markets. Although there was some irregularity in price movements, the majority of changes were to slightly higher levels. Towards the close, however, an easier tendency developed.

Among machine tool issues, Abwood Machine Tool advanced 3d. to 1s. 6d.; Arnott & Harrison, 6d. to 12s. 6d.; British Oxygen, 1s. to 15s.; Clarkson (Engineers), 4½d. to 7s. 3d.; Coventry Gauge & Tool, 1s. to 32s. 7½d.; and Samuel Osborn, 6d. to 53s. On the other hand, Edgar Allen lost 6d. at 31s.; Birmingham Small Arms, 6d. at 18s. 6d.; Greenwood & Batley, 10½d. at 16s.; John Harper, 4½d. at 7s. 10½d.; H. W. Kearns, 1s. at 20s. 3d.; Kerry's (Gt. Britain), 3d. at 8s.; and Ambrose Shardlow, 1s. 3d. at 53s. 9d.

CHARLES CHURCHILL & Co., LTD. Interim dividend 81 per cent (same).

Ambrose Shardlow & Co., Ltd. Interim dividend 4 per cent (same).

New Companies Registered*

LEAMINGTON PATTERN (ENGINEERING), LTD., Queensway Trading Estate, Leamington Spa. Registered November 28, 1961. To carry on the business of precision engineers, etc. Nom. cap.: £5,000. Directors: L. A. T. Willis, R. W. Mousley and F. G. Wiggins.

Arnott & Harrison (Toolmakers), Ltd.—Registered November 28, 1961. To take over the business of engineers and manufacturers carried on at Willesden, London, N.W.10 by Arnott & Harrison, Ltd. Nom. cap.: £100,000. Directors: J. C. Jones, F. W. Halliwell, L. Bunn and S. C. Clifton.

Necchi (Great Britain), Ltd., 9 Cavendish Square, London, W.1. Registered November 27, 1961. To acquire a licence or agency for the importation, manufacture and sale of the Necchi sewing machine in the United Kingdom. Nom. cap.: £50,000. Directors to be appointed by subscribers. Subscribers: G. K. Goddard and J. Black, 9 Cavendish Square, W.1.

* From the lists compiled by Jordan & Sons, Ltd., Company Registration Agents, 116-118 Chancery Lane, London, W.C.2.

COMPANY		Denom.	Middle Price	COMPANY		Denom.	Middle Price
Abwood Machine Tools, Ltd	Ord	1/-	1/6	Herbert (Alfred), Ltd.	Ord	٤١	64/-
Allen (Edgar) & Co., Ltd	Ord	(1)	31/-	Holroyd (John) & Co., Ltd	" A " Ord	5/-	20 /- xd
Allen (Edgar) & Co., Ltd	5% Prf	اع	13/3		"B" Ord	5/-	17/9xd
Arnott & Harrison, Ltd	Ord	4/-	12/6xd	10 90	B Ord	3/-	17/930
Arnott & Marrison, Ltd	Ora	-/-	12/6×0	Jones (A. A.) & Shipman, Ltd	0-4	5/-	25/-
Asquith Machine Tool Corp., Ltd	Ord	5/-	101-	Jones (A. A.) & Snipman, Ltd	Ord	5/-	4/6xd
Asquith Plachine 1001 Corp., Ltd	6% Cum. Prf.	£1	16/6	Kearney & Trecker-C.V.A., Ltd	7% Cum. Prf. 5‡% Red.	£1-	
Birmingham Small Arms Co., Ltd	Ord	10/-	18/6	Mearney & Frecker-C.V.A., Ltd	31% Ked.	2,1	8/9
Birmingham Small Arms Co., Ltd	Ord	10/-	10/0	11 11 11	Cum. Prf.	21	12/0
	FO/ C	61	121	W (11 141 10 C 11	Prefd. Ord	£1 5/-	13/9
99 99 99 444	5% Cum. "A" Prf.	£I	13/-	Kearns (H. W.) & Co., Ltd	Ord		20/3xd
	"A" Prf.			Kerry's (Gt. Britain), Ltd	Ord		8 /-
99 99 99 ***	6% Cum. B" Prf.	13	16/6	Macreadys Metal Co., Ltd	Ord	5/-	15/-
				Martin Bros. (Machinery), Ltd	Ord	2/-	2/6
	4% Ist Mort.	Stk.	904xd	Massey (B. & S.), Ltd	Ord	5/-	11/-
	Deb.						200
British Oxygen Co., Ltd	Ord	5/-	15/-	Newall Engineering Co., Ltd	Ord	2/-	7/-
				Newman Industries, Ltd	Ord	2/-	71-
99 99 99 **********	6% Cum. Prf.	El	18/6	10 11	6% Prf. Ord.	5/-	5/-
Brooke Tool Manufacturing Co., Ltd.	Ord	£1 5/-	7/74	Noble & Lund, Ltd	Ord		5/6
Broom & Wade, Ltd		5/-	22/-	Norton, W. E. (Holdings), Ltd	Ord	2/-	9/6xc
broom a vvade, Ltd	40/ Cum Del	13	16/-	Osborn (Samuel) & Co., Ltd	Ord	5/-	53 /-xc
Brown (David) Corporation, Ltd	6% Cum. Prf. 54% Cum. Prf.	61	14/-		Crd		
Brown (David) Corporation, Ltd	54% Cum. Pri.	£1 £1 5/-	17/-	9-11 /F \ F 11	51% Cum. Prf.	£i	22/-
Buck & Hickman, Ltd	6% Cum. Prf.	2.1		Pratt (F.) Engineering Corporation,	Ord	5/-	14/6
Butler Machine Tool Co., Ltd	Ord	5/-	15/-	Ltd.			
		£I	12/6	Sanderson Kayser, Ltd	Ord	10/-	34/3
Churchill (Charles) & Co., Ltd	Ord	2/-	8/71	. 11 11	61% Cum. Prf.	£ì	16/3
	6% Cum. Prf.	£I	25/711	Scottish Machine Tool Corporation,	Ord	4/-	7/9xc
Clarkson (Engrs.), Ltd	Ord	1/-	7/3	Ltd.		0	
	Salar Sa			Shardlow (Ambrose) & Co., Ltd	Ord	£I	53 /9
Cohen (George), 600 Group, Ltd	Ord	5/-	9/6	Shaw (John) & Sons, Wolverhamp-	Ord	5/-	14/44
	44% Cum. Prf.	13	12/-	ton, Ltd.			
Coventry Gauge & Tool Co., Ltd	Ord	10/-	32 74	Sheffield Twist Drill & Steel Co., Ltd.	Ord	4/-	21/9x
		(1)	16/3		5% Cum. Prf.	(13/3
" " " "	Red. Prf.		1010	Stedall & Co., Ltd	Ord	5/-	7/6
Craven Bros. (Manchester), Ltd	Ord	5/-	8/44	Sykes (W. E.), Ltd	"B" non-	10/-	
Elliott (B.) & Co., Ltd.	Ord		2/9	37 Kes (**. E.), Ltd	voting Ord.	10/-	24/4
Emott (b.) & Co., Ltd	Org	1/-	2/3	Tap & Die Corporation, Ltd	Voting Ora.	5/-	19/-
	41% Red.	£I	11/3xd				
49 99	Cum. Prf.	2.1	11/3XG	25 99 59	41% Deb.	Stk.	814
	Cum. Frt.			Marable Lad	1961-1977	1	
Stat Bassa Task Lad	401 0 0-0	-	100	Wadkin, Ltd.	Ord	10/-	26/-
Firth Brown Tools, Ltd	4% Cum. Prf.	£I	10/6	Ward (Thos W.), Ltd	Ord		65 /-
Greenwood & Batley, Ltd	Ord	10/-	16/-	10 90	5% Cum.	13	13/6
		1			lst Pref.	1 500	
Harper (John) & Co., Ltd		5/-	7/101	19 99	5% Cum.	£I	20/-
39 39 30		13	9/6		2nd Pref.		
	Cum. Pref.	1.		Willson Lathes, Ltd	Ord	. 1/-	2/6

Pig Iron* (10 tons or over)

MAKERS' PRICES

PRICES OF MATERIALS All prices per ton except where otherwise stated.

BASIC PRICES FROM

Pig Iron* (10 tons or over)	- 1	MAKERS' PRIC	ES	BASIC PRICES FROM
Foundry and Forge		Hexagon Steel Bars1		LONDON STOCK
No. 3, Class 2 Middlesbrough £21	17 0	Sizes in inches from 1 in. up to 2:21 and 2:41 a/f ex work	to	Free Cutting Steel
Birmingham (10 tons or over) £21	9 3	2 tons basis	£42 17 61	Bright cold drawn:
Phos. Over 0.1 up to 0.4%		Free cutting black	£46 14 6†	(Usaspead) over 1 to 2 in. £59 4 6; Lead bearing (Usaled) £63 11 0;
	5 0	Reeled Steel Bars ¹		Lead bearing (Usaled) £63 11 0‡ Precision ground, 1½ in. £84 14 6‡
		Single-reeled, 14 in. upwards f.o.t. works (+ usual extra	3	
Hæmatite		for sizes) Free cutting	£43 9 0† £47 7 0†	Bright Drawn
N.E. Coast (made in N.E.) £23 Scotland (made in Scotland, zone S.I.)		Precision-ground Mild		M.S. bars (M.M.C.) over 11 to 2 in. £56 10 01
Scotland (made in Scotland, zone S.1.) £24 Sheffield £25	5 6 9 0	I-in. diam ± 0.00025-in.	Stee!	Square edge flats (Usaflat) £73 6 6;
Birmingham £25	13 0	4-ton lots, per cwt.	124s. 6d.†	M.S. angles (Usaspead) £100 6 6‡
S. Wales (made in Wales) £23 (19 0	Bright Ground Stainle Steel Bars ³	ss	Case hardening (EN) (Usacase) over 1½ to 2 in. £62 10 0;
Steel Products*		EN56AM (martensitic, free cu	itting)	M.S. bars (EN3B) (Usamild) over I to 2 in. £58 16 6;
Medium plates (50 tons and over) £43 I		EN58AM (austenitic free cutti Prices are basic, subject to	£304 10 0	Carbon manganese semi-free cutting case hardening (EN202) (Usaspead
(50 tons and over) £40 Boiler plates (50 tons and over) £42		High-speed Steel	extras.	202) over 1½ to 2 in. £71 5 0; 35/45 ton tensile (EN6) (Usen)
Flat bars, 5 in, wide and under		Black random length bar. Al	Il prices basic	over I to I in. £67 3 0;
(50 tons or over) £39 Round bars, under 3 in. (50 tons		per lb., subject to extras:		0.4 carbon normalized (Usaspead "40") over 1\(\frac{1}{2}\) to 2 in. £69 5 0\(\frac{1}{2}\)
or over) £39	10	Molybdenum " 66 "	6s. 5d.	0.45 carbon normalized EN9
Billets, rolling quality, soft U.T. (100 tons or over) £31 1	5 6	Molybdenum " 46 " 14 per cent tungsten	6s. 3d. 6s. 11d.	(Usaspead 55) £69 15 0‡
		16 per cent tungsten	7s. 4d.	Carbon manganese steel to Speci- fication EN16T (Usaspead
Phosphor Bronze		18 per cent tungsten	7s. 9d.	fication ENI6T (Usaspead 5565), per ton £127 6
Ingots (288) (A.I.D.) d/d £312	0 0	22 per cent tungsten	9s. 2d	Ground Flat Stock
C		5 per cent cobalt	10s. 10d.	18-, 24-, and 36-in. lengths (Usa-
Cash (mean) £228 1	7 6	4.75/5.25 molybdenum + 6.0/6.75 tungsten +		spead). List prices plus 10 per
Cold rolled and hot rolled sheets		1-75/2-05 vanadium per cent	6s. 7d.	cent. less 5 per cent.
4 ft. by 2 ft. by 10 SWG £303 Rods, 15 in. to 1 in. diam £320	0 0	(5-6-2)		Oil Hardening Cast Steel
Tubes, It in. bore by 10 SWG,	. 1 2 d	Precision-ground, High Free-turning B	Brass Rod ²	Non-shrink (Usaspead N.S.O.H.).
(1-13 in.), English £244	7 6	§-in. diam. ±0.00025-in., 2 t lots, per lb.	2s. 7åd.	† in. to 2‡ in. per lb. Is. IId. Non-distorting heavy duty (Usaspead H.C.H.C.), † in.
Zinc		Grey Iron Rod		to 21 in., per lb. 4s. 2d.
Refined, minimum 98 per cent purity, current month (mean) £70	8 9	Die Cast ⁴ in random leng 26 in. rough machined a above listed size, according	in. to to in. to to in.	Silver Steel (0·194-in. to [4-in.).
Brass		Extra for shorter lengths.	, delivered.	Genuine Stubs quality, per lb. 4s. 10d. less 274%
Tubes, solid drawn, basis per lb. Is.	91d.	Mark I	Mark III	M.M.C. quality, per lb. 2s. 8d. + 64%
Tubes, solid drawn, basis per lb. Is. Strip 63/37, 6in. by I0 SWG coils, ton lots £253 5 0—£256 Rods, ⅓-3 in. diam. (59 per cent		l or l in. 208s. 0d. 11 to l in. 145s. 6d. 115s. 6d. 112s. 6d.	266s. 3d. 181s. 6d. 132s. 6d.	Boxes of 16 assorted sizes, 1 in. to 1 in. diam. 7s. 6d.
copper) 2s	. 0d.	2 to 3 in. 96s. 6d. 3 to 14 in. 90s. 9d.	112s. 6d. 105s. 0d.	Stainless Steel
Yellow Metal		Continuous Cast ⁵	1035. 00.	KE40AM (free cutting), per lb. 3s. 4d.
Condenser plates, per ton £184	0 0		nd +0.010 in.	Glacier Machined Bronze Bars
Rods, per lb. 2s	. Id.	10-ft. lengths centreless group Extra for hardenable alloy i	cwt. net. 08s. 4d.	Phosphor bronze (288) Prices on application
Aluminium		14 to 14 in. 14	16s. 3d.	, application
Ingots, min. 99-5 per cent Canadian d/d £186	00		12s. 7d. 97s. Id.	High-speed Steel
Tinplates		Stellite ⁶ Welding Rods, plain		18 per cent tungsten. Prices on application Toolholder bits:
**U.K. Home trade:		in. diam., per lb.	30s. Od.	Usaspead "Super" List price
Cold reduced, f.o.t. makers		Toolbits	303. 04.	" Cobalt 10
works (15-50 tons) £3 7 U.K. Export: hot dipped	84	in. sq. × 4 in., each	22s. 3d.	Shimstock
Cold reduced (strip	. 04			Steel assorted, per tin 3s. 6d.
mill), basis 73s. 6d.—76	s. 00.	1 Colvilles, Ltd., Glasgow, and Street, London, W.I. 2 Pratt, I Ltd., Chester. 3 Spartan Steel 8	Levick & Co.,	Brass ,, ,, 7s. 3d.
Gunmetal		St. Stephens Street, Birmingham	1, 6. 4 Metals	6 Macready's Metal Co., Ltd., Pentonville
	0 0	St. Stephens Street, Birmingham & Alloys (Birmingham), Ltd Sutton Coldfield. 5" Flocast," Ha Sheepbridge, Ltd., Halesowen. lite, Ltd., Highlands Road, Shi	rold Andrews Deloro Stel-	6 Macready's Metal Co., Ltd., Pentonville Road, N.I. Subject to confirmation by London Office. Delivered free by van in London area.
 Subject to increase of I per cent. Subject to allowances and extras. 		lite, Ltd., Highlands Road, Shi † Plus I per cent.	rley, Solihull.	‡ Plus I per cent.

Myford MG 12

(5"×12")

precision grinding ...costs less with a Thyford CYLINDRICAL GRINDER

The cost is low . . . it can be used for plain, internal, taper, conical, face grinding etc. . . . is regularly used for surface finishing down to one micro-inch . . . has a repetitive accuracy of 0'00005 inch.



it's the lowest priced "honestly built" grinder available



51

ì

1

1

11


1

d.

d.

Myford

BEESTON NOTTINGHAM TEL:NOTTINGHAM 254222



SOME MAIN FEATURES

Two speed table traverse handwheel... swivelling work table for taper grinding... precise setting to infeed stop... automatic wheel spindle lubrication... multi-speed workhead.

OPTIONAL EQUIPMENT

Swivelling workhead...internal grinding attachment... wheel dressing attachments for angular and radius forms ... centre pointing attachment ... chucks, collets etc.

For further information please write

CROWN



BRITISH MADE BY:

SURFACE

GRADE 'A'

Hand scraped and surfaced to within 0.000 lin. to 0.0003in, from a mean true plane over whole surface according to size.

GRADE 'B'

Smooth planed finish accurate 0.001in to 0.003in, according to size.

Sizes up to 4ft. by 2ft. have three-point support.

Sizes 4ft. by 3ft. to 6ft. by 4ft. have five-point adjustable support.

Sizes 8ft. by 3ft. to 12ft. by 6ft. have sixpoint adjustable support.


Our Grade 'A' tables conform to B.S.S. 817-1938 in all respects.

WINDLEY BROTHERS LIMITED

CROWN WORKS · CHELMSFORD · ENGLAND

When answering advertisements kindly mention MACHINERY.

BOSCH Hydraulic and Pneumatic Equipment



COMPLETE SYSTEMS FOR EVERY INDUSTRY

Hydraulic power units. Gear pumps. Piston pumps and motors, Electric motor coupled hydraulic pumps for A.C. and D.C., Electromagnetic and hand-operated control valves, Hydraulic rams. Filters, Relief and Non-return valves, Pneumatic cylinders, compressors and valves.

Our industrial division will forward complete details to Engineers




BOSCH LIMITED

CARLISLE ROAD, HENDON, LONDON, N.W.9

THE ELECTRICAL PHONE TONDON THE COURSE OF THE

When answering advertisements kindly mention MACHINERY.



ADVISORY SERVICE:

Radyne Ltd are leaders not only in the theory of induction heating but also in the best ways of using it in practical, down-to-earth industrial problems. We will be happy to discuss your problems without obligation.

Please use the coupon below.

A line of R.F. induction heaters in service with the Ford Motor Company, Basildon, Essex.



RADYNE

IMPROVED METHODS OF INDUCTION HEATING

Many high production processes are best carried out by radio frequency heating . . . best because of its inherent controllability; best for blunt indisputable facts of economics.

INDUCTION HARDENING

R.F. heating will harden components locally with the greatest precision, and is far quicker and cheaper than conventional methods of surface hardening, localised through hardening, and tempering.

SOLDERING AND BRAZING

Soldering and brazing by induction are quicker and cleaner than by conventional methods. Localised heating restricts the flow of solder to the joint area. Both parts to be joined are raised to working temperature together. Scale and discoloration are reduced to a minimum.

THROUGH HEATING


In forging, stamping, and other processes, rapid through heating to forging temperature saves time and space, reduces scaling and in consequence wear and tear on dies, improves dimensional accuracy, and gives better working conditions.

ANNEALING

Localised annealing between processes can be carried out with greater speed and control by induction methods than by any other.



Across new frontiers



RADYNE

WOKINGHAM BERKS ENGLAND

Telephone: Wokingham 1030 (12 Lines) Cables: Radyne England



I am interested in the industrial applications of induction heating

NAME.....

COMPANY

P6303

The finest reference book in the world for all those engaged in all metal-working industries

Just Published Completely up-to-date Enlarged to 2104 pages

The latest edition with its new features, additions and revisions is absolutely up-to-date, and because the old tried and proved features of fundamental value are retained, MACHINERY'S HANDBOOK is of greater practical value than ever before.

Whether your interest is engineering, design, or production, this book, enlarged to 2,104 pages, gives the latest facts, formulas and dimensional data available for ready reference.

Profusely illustrated with easy-to-read diagrams. Written by practical engineers who explain not only "how" but "why."

Handsomely bound and produced to give years of everyday use. Over 1,250,000 years of everyday use. Over 1,250,000 copies of this remarkable book have been

Thumb indexed into 14 quick reference sections: Log tables; Trig tables; Mechanics; Strength of materials; Gearing; Screws; Threads; Limits and fits; Small tools; Speeds, feeds; Steels; Non-ferrous alloys; Weights; Measures;

AN INVITATION TO INSPECT without deposit or obligation

You can handle and examine a copy quietly in your own home. Just sign and post this coupon and the latest edition will be sent post free by return. No deposit of any kind is required. Could any offer be fairer? Sign the coupon—NOW! Free examination scheme applies to U.K. and Eire only.



To MACHINERY, National House, 21 West Street, Brighton I, Sussex.

Please send me MACHINERY'S HANDBOOK

I, For which I enclose CASH for £4.16.0

2. By C.O.D., for which I will pay postman £4.16.9 on delivery

3. For FREE INSPECTION. In which case I will return it to you in five days or pay
(a) CASH £4.16.8 in full within 10 days from

invoice date, or

(b) 106s. by INSTALMENTS of 16s. in 10 days and 18s. monthly.


SIGNATURE	
NAME	

FIRM


WRITE FOR COMPLETE BOOK CATALOGUE.

NOTE Overseas orders must be accompanied with cash price, plus 4/- postage.





Lubrication problems? Consult Tecalemit for design, supply, installation and routine servicing



Strippable
Hot Dip
PROTECTIVE
COATING
UNDIPPED

The "Gloscoat" is a plastic protective packaging material for the protection of tools, machined parts and simple assemblies, and is applied by a simple dipping method. It is easily removed by peeling, leaving on the surface a thin film of lubricating oil.

The "Gloscoat" is melted in a suitable tank, electrically heated and thermostatically controlled. The articles are dipped in and out and in a few seconds the coating has chilled enough for the

article to be put down.

★ REDUCES MAN-HOURS It reduces packing time by at least 60% in Man Hours. ★ RESISTS CORROSION, RUST, etc. Adequate protection for the coated article against all forms of corrosion, rust, etc. ★ PROTECTS FROM ROUGH HANDLING Protection against abrasion, mishandling during transit. ★ PROTECTS FROM HEAT AND COLD Protection under all conditions. Particularly in hot, humid atmosphere or in extremes of cold.





Manufactured by

GLOSTICS LTD., TUFFLEY CRESCENT, GLOUCESTER, ENGLAND
For full details write Dept M Sole Distributors in the U.K.

J. M. STEEL & CO. LTD.

LONDON: 38-38 Kingsway, London, W.C.2. Tel: HOLborn 2532/5 MANCHESTER: 73/79 King St., Manchester 2. Tel: Deansgate 6077/9 BIRMINGHAM: 45 Newhall St., Birmingham 3. Tel: Central 6342/3 GLASGOW: 144 St. Vincent St., Glasgow C.2. Tel: Central 3262

In answer to your enquiry

VARLEY DOUBLE HELICAL GEAR PUMPS

will pump efficiently in any position up to 100 gal./min. up to 500 p.s.i.

Self-priming . . . will pump fluids from petrol to heavy oils . . . used for flood and forced lubrication, oil fuel transfer, coolant feed, hydraulic control, etc. . . . available in many sizes and any form of drive.



Yours faithfully VARLEY FMC LIMITED

Subsidiary of Food Machinery and Chemical Corporation U.S.A.

FERRY LANE BRENTFORD MIDDX. Tel.: ISLEWORTH 3922 (6 lines) : Grams: PARACYCLIC BRENTFORD TELEX

When answering advertisements kindly mention MACHINERY.

he is

ng, ed nd

he

ate

n, nst AT

ot.

K.



DOUBLE-ACTING DROP HAMMERS

for high speed production of accurate forgings

Massey Double-Acting Drop Hammers are made in two ranges, the 'Ram' type and the 'Piston Rod' type. Due to the high blow velocity achieved by these machines, the blow energy as compared with gravity drop hammers, is much higher which, coupled with the increased number of blows per minute available, ensures far greater production. Available in sizes from 10 cwt, to 8 ton.



20 cwt. 'Ram' type Double-Acting Drop Hammers. Messrs. Austin Motor Co. Ltd.

MASSEY DESIGNS INCLUDE :-

Steam and Compressed Air Hammers, Pneumatic Power Hammers, Friction Drop Hammers, Double-Acting Steam and Compressed Air Drop Hammers, Counterblow Hammers, Forging Presses, Use Rollers, Trimming Presses, Tyre Fixing Rolls.

BAS. MASSEY ED OPENSHAW . MANCHESTER . ENGLAND

MAKERS OF THE WORLD'S GREATEST RANGE OF FORGING AND DROP FORGING PLANT





Heavy Duty

NDSAWING

and Bandfiling Machine

- Equally suitable for toolroom or production line.
- Illuminated working area covered by optical magnifier.

Available with hydraulic infinitely variable feeding attachment which incorporates rapid return.

- Rapid changeover from bandsawing to bandfiling.
- Built-in butt welder with grinding wheel for removing welding flash.

. 22in. by 23in. Table tilts (3 sides) . to 15° Max. thickness of work loin. Throat depth . . . 14jin.

EARLY DELIVERY

Available through your local stockist.

NRP 3308




UP TO 1250 PIN HOLES PER HOUR!

CORONA

PIN-DRILLING
MACHINE

- Capacity up to ¾in. dia.
- Continuous Automatic Cam Feed
- Three Spindle Speeds
- Three Feed Ratios

Especially designed for high production drilling of retaining pin holes on a wide variety of components, this machine has continuous automatic cam feed. Loading and unloading is simple and all stations are easily accessible. This machine can be supplied with fixtures and cams to suit your own production needs, and we will gladly supply production estimates on request.





FREDK POLLARD & CO LTD

CORONA WORKS, LEICESTER, ENGLAND. TEL: LEICESTER 67534 (5 line

London Office:

COASTAL CHAMBERS, 15 ELIZABETH STREET, BUCKINGHAM PALACE ROAD, S.W.I Tel: SLOANE 8880
Scottish Representatives: Walter S. LANG & CO., 48 OSWALD ST., GLASGOW, C.I. TEL: CENTRAL 2539
North East: HODSON MACHINE TOOLS LTD., 150 NEW BRIDGE STREET, NEWCASTLE-UPON-TYNE.



Let's get

No more trial and error methods of sharpening.

With a Hunt Drill Point Grinder you get a perfect point every time, with the minimum of waste.

Drill points can be changed to suit different requirements quickly and easily, without the need of a skilled operator.

For longer drill life, more accurate holes and faster rates of penetration invest in a Hunt Drill Point Grinder.

Ask for details of our range.

down to the

point

of

Drill



MACHINE TOOLS

TWIST DRILL POINT GRINDING MACHINE

HERBERT HUNT & SONS LIMITED MACHINE TOOLS

Elelaure Read, Old Trafford, Manchester 16 Tal: Trafford Park 0663/4 Grame: HUNTING, MANCHESTER 16

Aluminium Alloy HANDWHEELS

- Range of sizes: 2in. 34in., 5in., 6in., 64in. 7in., 9in., 10in. (dias.).
- Supplies ex-stock (un-machined boss).
- Supplied WITH or WITHOUT Standard Pattern Handle. (5in., 7in., 10in. sizes only).
- Outer circumference and handle machined and polished (except 2in. size).
- Handwheels can be supplied with boss un-machined or machined to customer's requirements.
- Any quantity supplied.

Send for our Brochure-detailing prices and maximum dimensions for machining.

* We can also supply you with your Gravity and Pressure Diecastings.



MAGNAL PRODUCTS LTD YATE

BRISTOL

:4



... when everything depends on a nut

Some nuts do a tougher job than others and carry a bigger load of responsibility. When you describe a nut that way you practically specify a Nyloc—the self-locking nut with the resilient nylon insert that locks it anywhere on the thread, come oil, water, corrosives, shock or vibration.

Nylocs are complete in one single unit, so they save you time and



SIMMONDS
AEROCESSORIES
LIMITED

TREFOREST, PONTYPRIDD, GLAMORGAN Branches: London · Birmingham · Manchester · Stockholm Copenhagen · Ballarat · Sydney · Johannesburg · Naarden Milan · New York · Brussels and Mannheim

A MEMBER OF THE FIRTH CLEVELAND GROUP



D



... suits both user & supplier

ADVANTAGES

- ★ To the user—Increased productivity with increased working capital. Economies made possible by scrapping obsolete machinery.
- ★ To the supplier—Will not lose customers by failing to offer credit facilities.
- ★ To both—Progressive expansion by the maximum use of the MUTUAL PLAN.

Write for a copy of this booklet NOW

MUTUAL FINANCE LIMITED



A Mercantile Credit company
ELIZABETHAN HOUSE, GREAT QUEEN STREET,
LONDON, W.C.2, AND BRANCHES
Member of Finance Houses Association.


PEHAKA

COMBINED BANDSAWING AND BANDFILING MACHINES

Made in 3 sizes with Throats 15", 23" and 354"

> IMMEDIATE DELIVERY

EXCLUSIVE DISTRIBUTORS IN THE U.K.



THE TIMES MACHINERY CO. LTD. Poyle Road, Colnbrook, Slough, Bucks: Colnbrook 2442

ed ble

ng


ise

PNEUTOMATION

says MR. SQUINCH

.. was made for the worker with the boss-class in mind







Pneutomation operating a Transfer Station

The boss-class have it easy. Come at nine, go at five, live on the fat.

So the man at Lang Pneumatic invented PNEUTO-MATION ® to carry the burden for the hewers of wood and drawers of water who live by the sweat of their brow.

PNEUTOMATION ® stretches the long arm, puts shoulder to the wheel, works hammer and tongs with might and main, straining every nerve. Bossclass jubilant, production up, costs down, profits rising. Camaraderie, esprit de corps, bonhomie—everywhere.

Lang Pneumatic Ltd

(ASSOCIATED WITH DESOUTTER BROTHERS (HOLDINGS) LTD)
VICTORY WORKS · OWEN ROAD · WOLVERHAMPTON TELEPHONE: 25221-2-3 TELEX: 33193

Sensitive TAPPERS



★ High quality precision machines at reasonable cost.

★ Capacity 10 B.A. to ¼in. in steel. 10 B.A. to ¼in. in brass.

* Four spindle speeds:

forward: 375-2330 r.p.m. reverse: 430-2695 r.p.m.

★ Extremely sensitive control by friction clutch.

by DAVID

DOMFING

FOR SPEEDY, ECONOMICAL PRODUCTION

DAVID DOWLING LIMITED

BATES ROAD · HAROLD WOOD ROMFORD · ESSEX · ENGLAND

Telephone: Ingrebourne 43904

NUCLEAR, CHEMICAL, MARINE, GAS, OIL, WATER, STEAM, ELECTRIC, TRANSPORT, BUILDING & GENERAL ENGINEERING INDUSTRIES



HEXAGON HEAD BOLTS,
NUTS, SETS, STUDS AND
SPECIAL PARTS in
bright, high tensile
heat-treated carbon
and alloy steels.
Sizes from ‡ in. to
3 in. dia.

"CREEP" RESISTING
STUD BOLTS with
suitable nuts. Specialised products that
give maximum resistance to embrittlement
and retain a good
tensile strength when
exposed to conditions
of high temperature
and pressures. Sizes
from in. to 3 in. dia.



All the above supplied with Whitworth B.S.F. or Unified threads to the relevant British Standard Specifications. Larger sizes supplied to specific requirements.



Steel Bars

Bright drawn, heat-treated, carbon and alloy steel bars in Hexagons, Squares and Rounds, in all sizes up to 3½ in. dia. Special qualities and-or special sizes can be supplied.

Price List on request.

W.MARTIN WINN LTD.

DARLASTON, SOUTH STAFFS.

Telephone: JAMES BRIDGE 2072 (5 lines).
Telegrams: MARWIN DARLASTON.

RT.

above Whit-Inified elevant

andard Larger

specific ments.

bars and up to alities an be

PD.

N.

FS.

SELFEEDRIL

AT.MOC.2588

Prokuan Selieedrils


A system of self feeding air operated unit heads which will work any material—metal, wood or plastics—with a full range of mounting clips for very close centres or the widest deployment.

Single hose supply

- Automatic return
- Rapid approach
- Break through control

Photograph by courtesy of Richard Sutcliffe Ltd.

The 'Selfeedril' is a self' contained unit head with
built in forward and reverse
mechanism, rapid approach and
feed speed adjustment. Only
one air hose is needed to supply
each unit, and control is by a
single elementary on-off valve.
Maximum chuck capacity 4" dia. Forward
feed 14" and 24"



Parkside Works
ROTHLEY

LEICESTER

Phone: Rothley Park 691-892

For further details of this unique system write for Leaflet SFM.4



D



The Foremost Name in ABRASIVE WHEEL GUT-OFF MACHINES

SMOOTH, RAPID AND ACCURATE CUTTING OF ALL KNOWN MATERIALS, WITHOUT OVERHEATING AND WITH MINIMUM BURR

L. J. H. BALLINGER LTD

STATION ROAD

WOODCHESTER STROUD

Telephone: AMBERLEY 2186-7

GLOUCESTERSHIRE

BENCH **ENGRAVING MACHINES**

> FOR 2 AND 3 DIMENSIONAL WORK

For full details write:

DAVID DOWLING LTD

BATES RD HAROLD WOOD ROMFORD ESSEX


TELEPHONE

INGREBOURNE 43904 3



A first class machine at a

really low price MODEL 848
Reduction range 2:1 to 4:1.
Vertical adjustment to suit workpiece height. Coverage from 5in. × 3in. to 2½in. to 1½in.




fast as ordinary writing. Exceptionally sensitive balanced pantograph, giving automatic withdrawal of

For 3D work MODEL 242

cutter and tracer.

Compact - Sturdy - Large capacity -for fine engraving, mould and die work. Pantograph range from 2:1 to 8:1.



IRE

from nables arly as otiongraph, al of

d die



Material cost per item is less than that of other non ferrous metals.

Clean modern appearance.

Can be anodised-clear or colour.

Automatics can operate at maximum feeds and speeds.

Small chips eliminate swarf "build up" at tool tip.

Write TODAY for Full Technical Details.

Specify
ALMINAL
152

FREE MACHINING BAR

Southern Forge LTD

MEADFIELD ROAD · LANGLEY · BUCKS

Telephone: LANGLEY 301

ALUMINIUM AND ALUMINIUM ALLOY EXTRUSIONS TUBES AND FORGINGS

Dec

PRESS EQUIPMENT

for decoiling and rewinding

This wide range of coil reels includes free-running and motorised models for coils up to 48" wide and 15,000 lbs. weight. Mandrel expansion can be hand or power operated.


Motorised machines have electric clutch and/or stepless variable speed control. Reels are available with lateral spindle adjustment, tensioning device, coil loading car equipment, and powered track mounting.





CHOPPERS







PRESS EQUIPMENT LIMITED

HUNTERS VALE, BIRMINGHAM 19.

Manufacturers of Press Mechanisation Equipment

Telephone: NORTHERN 4823.


BAKER "STERIMAG" BINOCULAR MICROSCOPE

x 10 and x 20 instruments. Complete with Spot Lamp generally available from stock at

each

FRIGOLUX LL1 **ILLUMINATED MAGNIFIER** WITH COLD CATHODE TUBE

Magnification x 2 or with prismatic Microscope x 9 and 14 all at a working distance of 6in. Ideally suitable for the examination of printed circuits, small precision components and semi-blind orifices.





We Welcome Your Problems


OPTICAL-MECHANICAL

(INSTRUMENTS) LIMITED

36a Station Road - Egham - Surrey TELEPHONE: EGHAM 3988/9

Two instruments from a very wide range of microscopes, precision tools and opto-mechanical measuring instruments.

AJAX AJ4 RADIAL for Tool Room Accuracy!



Photograph: courtesy of Bayliss, Jones & Bayliss Ltd, Wolverhampton



rev

ents.

TWO GOOD NAMES
TOGETHER



SEND FOR AJAX BROCHURE NOW!

at BAYLISS, JONES & BAYLISS LTD.

Yet another important user of AJAX Radials—Messrs. Bayliss, Jones & Bayliss Ltd, a member of the famous G.K.N. Group, who manufacture a wide range of engineering products for many industries.

The AJAX Radial in their tool room is used for drilling, reaming and boring of jigs and tools for use on the production lines—again it's AJAX for accuracy and dependability.

BRIEF SPECIFICATION

- * 3" drilling capacity in steel
- * 4' 6"; 5' 0"; 5' 6" arm
- & Spindle No. 5 M.T.
- * Rotary gear speed change
- * Choice of three speed ranges
- * Coolant equipment as standard

AJAX MACHINE TOOL COMPANY LIMITED

WEST MOUNT WORKS, HALIFAX, YORKSHIRE, ENGLAND

Telephone: 5395/5 Telegrams: Ajax, Halifax.

Dec

THE TELESCOPE is the basic instrument required for every possible application in Optical Tooling. It is used for establishing a highly accurate reference line (line of sight) for setting, or checking, ALIGN-MENT—PLANES—SQUARENESS.



SPECIFICATION AND PERFORMANCE DATA:

MAGNIFICATION at Infinity Focus X34 with Standard Eyepiece, X43 with High Magnification Eyepiece, FOCUSING RANGE Zero to Infinity. IMAGE Erect. MICROMETERS, Built-in Optical Micrometers enable measurement of target displacement to Telescope line of sight in a direction at 90° to each other. Range, ± 0.050 in. ($\pm 1, 2$ mm.) in graduations of 0.001 in. (0.02 A click-stop indicates zero reading.

LOCATING TUBE Herdened and stabilised steel. Outside diameter 2.2495—2.2498 in. (57,1373—57,1449 mm.). Cylindrical within 0.0002 in. (0,005 mm.). Tube length—

10 in. (254 mm.).

OPTICAL AXIS. Concentric with and parallel to outside diameter of tube within 0.00025 in. (0,0064 mm.) and 3 secs. of arc tolerance.

ACCURACY OF READINGS AND TARGET SET-TINGS. Within ± 0.002 in. $(\pm 0.05$ mm.) at 100 ft. (30 metres) and proportionately for longer or shorter distances

distances.

FIELD OF VIEW 2 in. (50 mm.). at 5 ft. (1,5 metres-24 in. (610 mm.) at 100 ft. (30 metres). Proportional for all other distances.

OVERALL LENGTH 17.62 in. (448 mm.) nominal.

'TALYVEL' Electronic Level

Quick response, easy to read precision level, completely portable with battery operated transistorised circuit. For use as an absolute level or comparator. Three ranges can be shown on the meter — plus or minus 50 seconds, 100 seconds and 8 minutes of arc. Accurate to better than one second of arc (a change in level of one part in 200,000). Units can be separated by up to 300ft. (90m.) of cable for remote operation.



TAYLOR, TAYLOR & HOBSON A Division of RANK PRECISION Industries Ltd.

LEICESTER. ENGLAND





ROTARIX

SWISS SLIDING HEAD AUTOMATICS

Made by Robert & Schneider S.A. Nr. Moutler, Switzerland.

In Three Sizes

R505 Arin. dia. by 23in, length. R507 Arin. dia. by 23in. length. R510 3in. dia. by 23in. length.


All models have latest built-in safety devices, nitrided camshaft, turret-type collet mechanism, loose zero dials, carbide pressure peds, needletype headstock bearings.

Full Range of Auxiliary Attachments, including: Three Spindle attachment with 2 threading spindles. Back Drilling Attachment.

Details on request from

12 QUEENS ROAD · COVENTRY

Tel: Coventry 23889



NT

out-

SET-0 ft. orter



Rolled Thread Screws



Take no chances about your supplies of Rolled Thread Screws — specify ORMOND and so make sure of both quality and quantity—delivered right on time and straight from our extensive stocks. For your individual requirements, we will gladly submit special quotations. Send for lists, which in addition to detailing Brass, Steel and Light Alloy Screws in Rolled and Cut Threads, aiso feature Grub-screws, Nuts, All-threads, Hexagon Bolts and Set-screws turned from bar and Cold Headed Grades "A", "B" and High Tensile. The repeti-

tion parts range covers single and multi-spindle automatics up to 1½" diameter.



THE ORMOND ENGINEERING CO. LTD.

Ormond House : Rosebery Avenue : London, B.C.1

Telephone: TERminus 2888

Telegrame: " Ormendengi, Cent"


De

Me, **Automate P**

START AUTOMATION THE EASY WAY ... WITH NICKOLS AUTOMATIC SEQUENCE-CONTROLLED CONVERSION EQUIPMENT INSTALLED ON YOUR OWN CAPSTAN LATHES

Ask for a demonstration

AUTOMATICS LIMITED OLDS BUILDING, WINDSOR ROAD SLOUGH, BUCKS. Phone: Slough 26441



You ought to Mate!

2 SPEED DOUBLE ENDED **GRINDING MACHINES**

10" 12" 14" 16" & 20" MODELS

14" MODEL ILLUSTRATED

Our grinders are designed to give maximum work to wheel accessibility - incorporating heavy duty spindles running in double row self-aligning radial roller bearings.




Also Manufacturers of:-

High Speed Power Hacksawing Machines

INDUSTRIES LTD. NORTON

STAFFORD HOUSE, NORFOLK STREET, STRAND, LONDON, W.C.2
Phone: Temple Bar 0681. Grams: Nilmach, Estrand, London





carbide lamination tools ground from solid

AT SHARPE & WRIGHT LTD., HOVE

IΔG

ELECTRO

- ★ ENABLES THE MOST DIFFICULT FORMS IN TUNGSTEN CARBIDE TO BE PRODUCED WITH EASE AND ACCURACY ★ FREE FAST CUTTING WITHOUT HEAT GENERATION ★ WHEELS RETAIN THEIR ORIGINAL SHAPE THROUGHOUT THE WHOLE OF THEIR LIFE

In addition to these features, the Diagrit Electrometallic coated diamond wheels can be employed without coolant, which enables them to be used for generating intricate profiles on optical form grinders. Sharpe & Wright Ltd., have effected great economies in the production of these solid carbide punches: there is little to be lost in putting our claims to the test and investigating the advantages to be gained from a similar reduction in your own tool making costs.




Our new catalogue post free on eceipt of is compon



DIAGRIT DIAMOND TOOLS LTD., Station Rd., Staplehurst, Tenbridge, Kent. Tel: Staplehurst 479. Grams: Diagrit, Staplehurst

De





FOR ALL PURPOSES

SHEETS, STRIPS, PADS, WASHERS, OIL SEALS,

JOINTINGS, ETC., PIPE LAGGING FELT

FELT POLISHING BOBS

HARDY & HANSON LTD.

SUMMIT WORKS · LONGLANDS ROAD · DEWSBURY

Telephone: 2353

Telegrams: SUMMIT, DEWSBURY



early delivery of all models from stock

Products of over 30 years development by HUMPHRIS, these proved machines are the modern effective approach to medium duty, relatively high speed applications on coiled strip of medium thickness (say .030")

illustrated are the following:

CD.10-6

for coils of 1,000ib. x 40" x 6" x .080" up to 1,000 ins. per min.

CD.20-10

for coils of 2,000lb. x 40" x 10" x .080" up to 1,000 ins. per min.

CD.20-16

for coils of 2,000lb, x 40 $^{\prime\prime}$ x 16 $^{\prime\prime}$ x .080 $^{\prime\prime}$ up to 1,000 ins. per min.



exponents of advanced mechanisation

HUMPHRIS & SONS LTD. - POOLE - DORSET

TELEPHONE: POOLE 1800


TELEGRAMS: HUMPSONS



SCREWCUTTING

Do you still use chalk =

In the same way that the chasing dial has superseded the old method of marking chuck, headstock, leadscrew collar and bracket; the AINJEST HIGH SPEED SCREWCUTTING ATTACHMENT has established a further major advance in screwcutting techniques. Its use on standard centre lathes allows the automatic engagement and disengagement of the leadscrew at the highest spindle speeds of which the machine is capable.



- * The cut is stopped accurately so that external or internal threads can be cut tight to a shoulder at high speeds.
- * Tungsten cerbide tools can be used with great advantage.
- Chasing dial is eliminated.
- * The attachment remains in position, ready for use, without restricting the versatility of the lathe.





High Speed SCREWCUTTING ATTACHMENT

Stockists of carbide threading tools
Write for details and prices to Dept. A.S.C.

SAUNDERSON & COSTIN LTD. . HIGHCLERE . NEWBURY . BERKSHIRE . ENGLAND Tel: HIGHCLERE 448



MANLOVE ALLIOTT & CO LIMITED
BLOOMSGROVE WORKS NOTTINGHAM

FROM NOTTH, 75127 (Slines) GRAMS: MANLOVES, NOTTH, SLONDON OFFICE: 4) X42 PARLIAMENT ST, WESTMINSTER SW.I. Phone: WHITEHALL 5931-2

S,



This Catalogue should be on your This Catalogue should be on your desk. It gives full details of wheel dressing and wheel forming diamond tools; diamond tools for turning, boring and hardness testing: diamond impregnated wheels and laps, in fact everything you need for selecting the right diamond tools for your operations. Send for your FREE copy now!



If you had a diamond mine of your own, you'd make quite sure that only the very best diamond was selected for your job. Indusmond does just that. Indusmond can work with you, for you. You can trust the expert knowledge of Indusmond-gained over a period of almost a quarter of a century-to guide you in the selection of the most economical and efficient tool for your work. You have confidence in Indusmond, it's like having a diamond tool works on your own desk.




INDUSMOND (DIAMOND TOOLS) LTD., 26-29 ST. CROSS STREET, HATTON GARDEN, LONDON, E.C.1

 $\textbf{\textit{Telephone: CHAncery 7608. Northern Office: Sussex Street, Sheffield 4. Telephone: 20701 and in Birmingham, South Wales and Scotland Scotland$

TRIPET MAR 200 For really Precise Grinding-Swiss Universal Hydraulic Cylindrical

Tolerances of .00004' can be held and both bore and face ground at the same work setting, ensuring perfect squareness. Particularly suited to internal work, yet fully universal. The work head swivels through 90° for taper grinding and rotary surface grinding. Work head drive is steplessly variable from 0 to 1900 r.p.m. Automatic feed is from .00004" to .0004" and semi-automatic diamond dressing compensates for wheel wear. Internal grinding spindles are quickly interchangeable for diameters .040" to 2". Table reciprocations can be as small as .080°.



SOLE U.K. DISTRIBUTORS



DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W 14 Tel: WESTERN 8077 48 lines) fales: 33183 Grams: ACCURATOOL LONDON TELEX Grinding capacity, internal .040" to 2" Grinding spindle speeds,

(internal) 18,000 to 120,000 r.p.m. (external) 3350 to 5000 r.p.m.

SPECIALISTS

in used and reconditioned machine tools

AUTOMATICS

ACME-GRIDLEY 1§in. Six-Spindle Bar. ACME-GRIDLEY 2[in. Four-Spindle Bar. ACME-GRIDLEY 5[in. RAC Six-Spindle Chucking. B.S.A. ACME-GRIDLEY 3[in., 1§in., Four and Six-Spindle Bar. B.S.A. †in. and No. 48 Single Spindle. WICKMAN 15 in. Sliding Head.

GRINDERS

B.S.A. Nos. 7 and 8 Centreless.

CHURCHILL ' HCY ' and ' HBY ' Internal.

LANDIS 4 x 12, 4 x 18 and 6 x 18 Type C Plain

NEWALL 12 x 36 and 10 x 72. ORCUTT 20in. Spline

HONING

B.S.A. No. 50H. KITCHEN & WADE Nos. 0 and 2.

DRILLING

ARCHDALE Multi-Spindle.
BECKER Unit Head Vertical, Multi.

List revised 20/11/61.

The above offered subject to prior sale. All machines motorised suitable for 400-440 volts, 3 phase, 50 cycle supply.

We offer good prices for your surplus plant. Send us details—we will inspect immediately and make a firm offer. Write, wire or phone . .

ARCHDALE, CORONA, HERBERT, J & S 1-2-3-4 POLLARD 21A Vertical (Indexing Table).

LATHES

B.S.A. 6 x 12, 6 x 20, 6 x 28 Multi Tool.
BOLEY Fine Turning.
BRYANT Symonds Diamond Turning.
GISHOLT 1L and 2L Capstan.

BORING

EX-CELL-O Fine Borers. HEALD Fine Borers.

MILLING

ARCHDALE 14 x 20 Horizontal. HERBERT No. 1 Auto Mill and Nos. 10 and 158

RIFLING

PRATT & WHITNEY.

GEAR

BARBER & COLEMAN No. 3 Hobber.

B. G. MACHINERY

MONTGOMERY STREET · BIRMINGHAM

TEL: VICtoria 2351

TELEG: REBUILT BIRMINGHAM



... because Colt created the right climate



An installation of 11 Colt 18" Powered Extractors at the Stonebridge Park Depot of T. Wall & Sons. Architect: J. Kennedy Hawkes, FRIBA Contractors: Leslie & Co Ltd



An atmosphere thick with exhaust gases and acrid fumes throughout the day...it could happen at any depot where diesel trucks start up from cold every morning. It does not happen at the Stonebridge Park Depot of T. Wall & Sons (Ice Cream) Ltd, because Wall's planned wisely ahead and called in Colt to design a ventilation system. You will find Colt systems at work throughout British industry, creating conditions in which men can work contentedly and efficiently. Colt's practical experience of ventilation problems that arise in every branch of industry could prove useful to you. Ask your Secretary to write to the Information Officer for the free Manual of Colt Equipment and Service.

industrial ventilation

COLT VENTILATION LTD · SURBITON · SURREY · TEL: ELMbridge 0161


Get more out of your surface grinder!

LIBERTY High Speed

Especially designed for giving the high speeds necessary for precision grinding recesses, slots and surfaces in awkward places. Easily fitted to most surface grinders and invaluable for grinding gauges, small jigs and fixtures and special tools. Speeds up to 23,500 r.p.m.

HORIZONTAL MODEL, AS ILLUSTRATED PRICE £32 . 10 . 0

VERTICAL MODEL
ALSO AVAILABLE
PRICE £49 . 12 . 0



FULL DETAILS FROM DEPT. M.2. WRITE TODAY . . .

HENRY CHALLIS LTD.

DEVONSHIRE HOUSE VICARAGE CRESCENT, LONDON, S.W.II.
PHONE: BATTERSEA 9581

Increase Productivity with WESTON

rates are infinvariable from I er min. upwards

Feed rates are infinitely variable from I in. per min. upwards on 0 and I Models, and ½ in. per min. on Model 2. Special tables with feed rates down to ½ in. per min. are made for heavier work. The production unit cylinder is cushioned on return stroke. Work Transfer Units have cushioned cylinders working against adjustable dead atops, stationing one component under the fool whilst another is being loaded.

PAST	FIED	-	
-		•	
	-		

Diagrammatic illustration showing some of the many cycles available.

AIR HYDRAULIC

PRODUCTION UNITS

. . . GIVE FAST APPROACH AND RETURN SPEEDS FOR MILLING, DRILLING, TAPPING, BORING, ETC.

TRANSFER UNITS

FOR 2, OR EVEN 3 POSITIONS

4 STANDARD MODELS AVAILABLE

MODEL O MODEL IA MODEL IB MODEL 2

Recommended air line pressure: 70/100 lb. per sq. in. Other movements made to customer's requirements

THE WESTON MACHINE TOOL CO. LTD.
212 BRACEBRIDGE STREET, ASTON, BIRMINGHAM 6
Telephone: ASTON Cross 1788

ND

NG.

TC.


EL 2

TD.


How costs are cut with SALTER RETAINERS

Salter retainers simplify design of air, water, steam union, with great savings





THE OLD WAY Air, water, steam union involved drilling, threading and milling operations. Maintenance was difficult.



THE SALTER WAY Salter retainers permit rapid, simple assembly and maintenance with a reduction in manufacturing costs.

MATERIALS SAVED

decreased wall thickness of housing 2/9‡
eliminated bearing lock nut and washer 7‡

MACHINE

OPERATIONS ELIMINATED

bore, undercut, and tap capend of housing 1/4 locate cap on arbor and chase threads 1/drill spanner wrench holes 4½ cut thread on rotor for lock nut 3¾ mill slot in thread for tang on lock washer drill spanner wrench holes in rotor 4¼

ASSEMBLY

OPERATIONS ELIMINATED

install lock washer, tighten lock nut, bending assemble cap into housing

TOTAL SAVING WITH SALTER RETAINERS

4 SALTER
RETAINERS
simplify
design,
assembly
and
maintenance
with a
saving of
8/6½ per unit

NEATER - MORE POSITIVE - PERMANENT RETAINING

8/61

SALTER





Circlips



Fasteners




Retainers



Fixes

Geo. Salter & Co. Ltd., West Bromwich. Spring Specialists since 1760





Call it what you like

Reel, Winder, Coil Holder, Uncoiler, Swift, Coil Stand, Feeder, Decoiler, Spulenhalter, Dispositif d'amenage automatique, or "That thing you put the coil of steel on."

but use one made by:-

W. T. ATKIN (TOTTENHAM) LTD

178, St. Ann's Road, London N.15 Phone: STAmford Hill 6686-7 Overseas Cables
"Pressing London, N. 15".

THINK OF SAWING



"RAPIDOR" HEAVY DUTY HACKSAW Capacity 6" x 6" and 8" x 8"

Designed and built for hard service, these machines incorporate many features counting for fast and accurate cutting.

Rigidly guided saw frame, automatic relief on the return stroke, saw frame loading indicator, blade tension indicator, suds equipment, heavy duty vice, are all standard features.

TWO OR THREE SPEED MODELS AVAILABLE

EDWARD G. HERBERT LTD.
LEVENSHULME . MANCHESTER 19 . ENGLAND



PRODUCTION
—LONGEST LIFE
always use "RAPIDOR"
H.S.S. BLADES



TURNING, FACING & BORING MACHINE

- * ENSURES MAXIMUM ECONOMY ON SMALL CHUCKING WORK
- * TURNING, BORING & PROFILING TO PRECISION LIMITS
- * DUPLEX HEADS, VERTICAL AND HORIZONTAL TOOL SLIDES

The remarkable versatility of this automatic cycling machine enables quite small as well as large series to be produced at a most economical rate. Turning, facing, boring and profiling can be carried out without special tooling. Spindles are completely independent as regards speed and direction of rotation. The combination of vertical toolslides and horizontal toolposts gives wide scope for tooling. Table has an infinitely variable feed range from ½" to 20" per minute over a 6" stroke with rapid approach and return. Spindle speeds 250 to 3,500 r.p.m.

SOLE AGENTS:

JAUGHAN ASSOCIATES LIMITED

Write for fully descriptive brochure

4 QUEEN STREET · CURZON STREET · LONDON W.I ·

Tel: GROsvenor 8362

Midland Office and Demonstration Room: WILFRED CRESCENT, NOTTINGHAM Tel: Nott. 88008



Sheet Metal Working **Machinery Specialists**

- * GUILLOTINES
- * FOLDERS
- * PLATE BENDING ROLLS
- * SWAGING MACHINES
- * SPECIAL MACHINES (HAND OR POWER)




ILLUSTRATION SHOWS ANGLE BENDER & FOLDER 8ft. by Jin. CAPACITY, WITH SWING OUT BEAM

FROST (ROCHDALE) LTD

EAGLE IRON WORKS ROCHDALE



... it's all one - to the

Speetog PUSH PULL CLAMP


Patent 749367



This is the first Clamp designed to carry out both "push" clamping and "pull" clamping without adjustments or re-fitting to the clamp itself. No nuts, bolts or split pins to remove for this dual-purpose clamping.



clamping. Neat and compact.



Plan view of above. Reverse position for "pull" clamping.

LITERATURE SUPPLIED

VEREKER HOUSE, GRESSE ST., LONDON W.1. Museum 1039/1099.

NRP 9076

成者の以下於韓城然為情於

SETTING THE PACE ON DRILLING

STATE OF THE STATE

At the WillesdenWorks of A.E.I. (Rugby) Ltd., the 5ft. high speed medium duty radial is one of many ARCHDALE machines setting the pace on drilling and tapping. The machine illustrated is drilling and tapping in. B.S.F. holes in fabricated cable boxes.

ARCHDALE high speed radials have 17 spindle speeds, from 15 to 1,500 r.p.m. with six or twelve feeds. Normal drilling capacity is up to 3in. diameter in mild steel. Sizes range from 3ft. 3in. to 8ft. spindle radius.

Many other models are available from light type to heavy duty hydraulic pre-select radials. Ask for complete details.

A STATE OF THE STA

ARCHDALE

JAMES ARCHDALE & CO. LTD.

BLACKPOLE WORKS · WORCESTER · Worcester 27081 (7 lines)

Sole Selling Agents: ALFRED HERBERT LTD · COVENTRY · Telephone: COVENTRY 89221





- FRAMES OF HARDENED MILD STEEL RIGID & UNBREAKABLE MCOO Range 0-.195 MCO Range .385-.570 MCOOX Range .195-.385 MCOX Range .570-.760 MCOOX Range .195-.385 Produced to American Standard Specification CS8/51
 - First class reconditioning service available



Pin and Plug gauges too

- A complete range of pin gauges to U.S.A. specification CS8/51 and plug gauges to BS1044
- Surface finish of less than one micro-inch
- Any accuracy including class XX
- Range from 0-010" to 0-750" pin gauges (CS8/51)
- 1-21 inch TAPER LOCK TYPE (BS1044)
- 1-44 inch TRILOCK TYPE (CS8/51)

YORKSHIRE PRECISION GAUGES, LTD. : I HATFIELD : Nr DONCASTER YORKS : Tel Hatfield Woodhouse 303 Telegrams: Precision Doncaster

Stag Major*

Superweld Tools


The flash - butt welded STAG MAJOR super high speed steel tip on a carbon steel shank gives maximum performance with an exceptionally long cutting life. Our stock of these famous tools covers all standard shapes and sizes, we will gladly send you an illustrated tool chart.

Write for your copy today,



Stockists Agents for London and the Southern Counties

QUEENHITHE . UPPER THAMES STREET . LONDON E.C.4 Telephone: CENtral 7751





VERTICAL BORING & TURNING MILLS

From 8ft. Oin. diameter capacity. Side Head, Profile Copying, Preselection of Speeds, Rotary Planing. Constant Cutting Speed Control, etc. (10ft. 0in. Mill illustrated).

ALSO

Planing Machines

Roll Grinding Machines

Horizontal Boring and Milling Machines

Gear Hobbing Machines

High Speed Tube Boring and Trepanning Machines

Railway Wheel Lathes

Railway Axle Lathes

Rotary Crankpin Machines

LATHES

Of all types from 16in. height of centres, including Break Lathes, Combined Turning and Boring Lathes, Roll Lathes, Crankshaft Lathes, Lathes of Unit Construction, etc. (33in. Centres Roll Lathe illustrated.)

CRAVEN BROTHERS (MANCHESTER) LIMITED VAUXHALL WORKS REDDISH STOCKPORT ENGLAND

Engraving

3 SCRIPTA ENGRAVERS

cover all requirements







TYPE S.D. for straightforward engraving
 TYPE S.R. 2D for heavy duty work
 TYPE S.R. 3D for mould making and three dimensional work

Write for fully Illustrated leaflets ACBARS LTD. 331-3 WALWORTH ROAD · LONDON · S.E.17
Telephone: RODney 7822 · Telegrams: Acfirb, London, S.E.17.

Conf.
TRAPALGAR WOIL Teleg

All types of press work up to 150 tons — any metal

Deep draw work a speciality

Also milling, drilling, capstans and assemblies

Corfield & Buckle Ltd

TRAFALGAR WORKS • MERTON ABBEY • LONDON S.W.19
Telephone: Liberty 1144 (7 lines)



a shot in the arm

Perhaps British Wagon can give it. This may be just what your business needs to help it to grow. By using British Wagon's Finance Plan you are able to acquire whatever new plant or machinery you need with only a small capital outlay. You simply buy out of income. Our terms are economical and flexible. For friendly and practical advice on the B.W. Finance Plan, backed by over 90 years' sound financial experience, get in touch with your local branch manager...



... or write for our leaflet 'Financing the Cost'. It gives you full details of how the British Wagon Finance Plan can help you.



Head office: Moorgate, Rotherham, Yorkshire Tel. Rotherham 5466

Southern Head Office: Rotherham House, Grosvenor Crescent, London, SW.1 Tel. Belgravia 8000

Est. FINANCE 1869

Member of the Finance Houses Association

INSPECTION EQUIPMENT

OF THE

HIGHEST QUALITY



SURFACE PLATES AND TABLES IN CAST IRON OR GRANITE TO B.S.817/1957 WITH OR WITHOUT CABINETS

REFERENCE SQUARES

ENGINEERS PARALLELS

STRAIGHT EDGES

LAPPING PLATES

CYLINDRICAL **SQUARES**

FEELER GAUGES

ADJUSTABLE PACKINGS

PRECISION SCREW **JACKS**

LOAD DEFLECTION



'B' (BALL) BLOCKS FOR SUPPORTING CYLINDRICAL COMPONENTS



SURFACE ROUGHNESS COMPARISON SCALES

RUBERT & Co. Ltd.

ACRU WORKS · DEMMINGS ROAD CHEADLE . CHESHIRE

Tel: MANCHESTER GATLEY 5855

M.A.S.S.

TOOLS LTD.

Specialists in **Tooling Equipment And Special** Purpose Machinery

Jig-Boring, Press Tools, Jigs and Fixtures; Special Purpose Machines, etc. Manufacturers of Small Precision Mechanical Devices. Precision Grinding, Internal and External

Patterns and Castings in any Quantities.



A.I.D. Approved



RIDGE ROAD CORNER. STONECOT HILL. NORTH CHEAM SURREY 9 'Phone: Fairlands 8861/2.




We are specialist manufacturers of needle roller assemblies and rollers and pins for all types of box tools as listed on right. Made from highest quality tool steel, bores are lapped to 0.0003in., pins to 0.0002in. 12-page Catalogue No. M. I and Price List on request.

request.

As supplied to ROLLS ROYCE LTD

L. & T. I. BROCK & CO. LTD., PRECISION ENGINEERS BURNSALL ROAD . CANLEY . COVENTRY Telephone: Coventry 74285/6



The Butterley range of sheet metal machinery includes geared and ungeared power presses, guillotine shears, press brakes and general machinery for the hot and cold working of metals. All castings are made by the "Meehanite" process in our own well-equipped foundries. The Butterley foundries are available for the production of high-grade "Meehanite" castings to customers' requirements. We invite your enquiries for "Meehanite" castings of all grades up to 20 tons.


The word MEBHANITE is a registered trade mark.

Full details of Butterley Sheet Metal Machinery supplied on request.

THE BUTTERLEY COMPANY LIMITED

Ripley • Derby • England Tel: Ripley 411 (9 lines) London Office: 9 Upper Belgrave Street, S.W.I. Tel: BELgravia 2212/5

SM 24



Designed for use with either the twenty or eight ton capacity Flexi-Force ram and the standard or quick-acting pump, this press may be purchased as a complete independent unit, or in the form of frame and we blocks only, as a valuable extension to existing Flexi-Force equipment. The ram and pump can be mounted or removed from the press frame in a few minutes.

Choice of seven press table heights easily accommodates all jobs—the self-retracting capacity of the ram being ample for withdrawing the heaviest dies or tools. Sensitive release valve and optional pressure gauge ensures accurate control of all operations and a wide range of Plexi-Force adaptors gives outstanding versatility.

SPECIFICATION OF PRESS FRAME.

Maximum Daylight Opening . . . 33" Minimum
Maximum Working Length of Table
Width of Table.
Table Gap.
Fam Stroke Capacity 8 Tons 6
Ram Stroke Capacity 20 Tons 5 23" 6" or 12" 5" or 12"

£72

complete with standard pump, 20 ton ram, and vee-blocks.



EPCO LIMITED . STAR WORKS . LEEDS 7 Tel: 27471. Grams: EPCO. LEEDS.

14 DAYS' FREE TRIAL

EX-M.O.S.

PRECISION TOOLS

TOOLROOM CLINOMETERS (Micrometer Bubble Type)

An Engineer's Clinometer of great precision. Main scale is divided 0-20° in 1° divisions and angles to within ½ minute can be read speedily on the micrometer thimble. For their original military purpose a clip was fitted to the base but this clip can easily be removed in the Machine Shop. Net weight 22 ozs. Length of 35/-

GERMAN DRAWING INSTRUMENT SETS
Brand new in velvet lined case

TIME & MOTION STUDY STOP WATCHES
Cost approx. 47. Offered in perfect condition - Also available Ex-M.O.S. High quality 55/-

OPTICAL TEST SET with 30 assorted lenses, prisms, polaroids &2

We are disposing of our collection of chronometers—
recognised as being one of the finest in the world.
Full details on request.

CHARLES FRANK LTD. Phone: BELL 2106/7
67/75 [SALT MARKET, GLASGOW, C.1. Ett. 1907
Britain's greatest*stocks of new, used and Ex-Government Optical
and Scientific Equipment. Send for illustrated catalogue.



STANELCO

TOGGLE PRESS

- Steps up production with less fatigue on small precision parts.
- Consistently accurate
- Simple ram adjustment
- Compression approx.
- Suitable for female op-

STANELCO 100 WATT SOLDERING IRON

- Industrial iron with stainless steel side plates and flat copper bit for any application
- Good heat transfer and long life
- 12v., 50v., 100/110v., 200/220v. and 230/250
- An ideal general purpose iron

All enquiries to

Standard Telephones and Cables Limited INDUSTRIAL SUPPLIES DIVISION


FOOTSCRAY, SIDCUP, KENT. FOOtscray 3333

961


tigue

ted

Turn to economy with SANDVIK Mechanical Tubing







For you, as a manufacturer of ring shaped and cylindrical parts, it will pay to use SANDVIK Mechanical Tubing as your basic material. In this way you will save material and time—you will reduce wear on tools and machines. You will make machines and labour available for other operations.

Today, with increasing frequency, design and production offices specify SANDVIK Mechanical Tubing also for larger elements in heavier constructions.

72 standard sizes in Specification EN6, and 16 selected sizes in Stainless (EN58E) Steel are available for immediate delivery from stock. Request a copy of our brochures, E.370 and E.376,

SANDVIK SWEDISH STEELS LTD.


Manor Lane, Halesowen, Birmingham Telephone: Halesowen 2121 (10 lines) Telex 33164

Scottish Warehouse at
Blackbraes Road, Nerston Industrial Area,
East Kilbride, Glasgow Telephone: Murray 429

NAMEPLATE MARKING SIMPLIFIED

Make the job of nameplate marking quick, neat and easy with the special Pryor equipment—Interchangeable steel type, logotypes and an automatic numbering head. Write today for the Free Leaflet No. 62 en-





BROOM ST., SHEFFIELD ENGLAND PHONE: SHEFFIELD 23161 GRAMS: PRYOR, SHEFFIELD



BROADWATER WORKS, GARMAN ROAD, TOTTENHAM, N.17

FLEXICON LTD
Head Office: 72 Vicar Lane BRADFORD
Tel: 26182

BALL, ROLLER, TAPER

ROLLER & NEEDLE BEARINGS

Also at: 70 Foleshill Road, Coventry Tel: 27108
61 St. Benedict's St., Norwich Tel: 21795
24 Leytonstone Rd., Stratford, London, E.15
Tel: Maryland 4491

961

ND




Press tools cost far, far less in

D.B. TOOLFO

Press tools made of D.B. Toolform can be prepared more quickly and without highly skilled labour for as little as a third of the cost of the steel equivalent. No machining is required and no special equipment is needed. Tools are durable yet light. They can be cast with great accuracy and easily modified at any time.

WHY D.B. TOOLFORM IS QUICKER AND CHEAPER

D.B. Toolform is not only quicker and cheaper than toolmaking in steel. It is also cheaper and quicker than toolmaking with other plastics. This is because it is already formulated and no weighing, measuring or proportioning are required, each grade being designed for a particular purpose. It is only necessary to add hardener to resin and pour into a prepared mould.





Please send me literature giving further details of the applications and advantages of D.B. Toolform for press tools.

NAME


COMPANY

Post to THE KENILWORTH MANUFACTURING CO

WEST DRAYTON, MIDDLESEX . WEST DRAYTON 3731



SHARDLOW MICROMETERS LIMITED PETRE STREET - SHEFFIELD 4 Phone: 386951/2 Grams: MICROMETERS SHEFFIELD



LEYTOOL WORKS . HIGH ROAD . LEYTON . LONDON . E.10 Phone: Leytonstone 5022 3-4



AXMINSTER, DEVON

Eliminate manual measuring operations with 'Deltameter' dimensional control!

Your older machines can produce to .00005" tolerances with the continuous reading 'Deltameter'

MACHINE SHOP FOREMAN SAYS:

The Johansson 'Deltameter' provides a continuous dimensional check during manual or automatic grinding operations. Operating from any factory air supply above 25 p.s.i. pressure, the 'Deltameter' provides an immediate dimensional check while the component is being produced. Electrical contacts operate a coloured light signal system, or provide automatic control through a relay unit.

"' Deltameter' installations brought older machines into operation again, eliminated rejections, and saved hours of manual checking by conventional methods. What's more, as the component size is continually shown on the face of the instrument, I can use less skilled operators."

The Johansson 'Deltamatic' is a universal instrument for machine control. It includes the basic 'Deltameter' measuring head and visual indicator, plus a built-in relay unit.



CEJOHANSSON LTD.

Specialists in threading and precision measurement.

SOUTHFIELDS ROAD, DUNSTABLE, BEDS. TELEPHONE: DUNSTABLE 62422 (4 lines)

SPEED UP your BAR WORK with ACCURATOOL CAPSTANS



Lever operated compound slide swivelling up to 45°. Unusually sen-

sitive and versatile. Lever operated collet (air operated collet extra). Eight spindle speeds 75-3000 r.p.m. Single lever selects High or Low speeds Forward and Reverse. Many useful items of optional equipment.



Write today for fully illustrated folder M/II8b.

DOWDING & DOLL LTD

346 KENSINGTON HIGH STREET, LONDON, W.14 fel: WESTERN 8877 (S lines) Telex: 23192 Groms ACCURATOOL LONDON TELEX ACCURATOOL SECOND **OPERATION LATHES** for work up to nearly 3" diameter

1186

FOR ACTUAL SIZE

SOLE WORLD DISTRIBUTORS:

TAPER PLUG GAUGE

for positive, direct indication of metal to be removed

This new gauge offers a means of control of hole diameter and feed well before the finished size. Readings can be taken from 0-014in. below nominal diameter, thus enabling an operator to advance feed progressively and speedily, at the same time avoiding the possibility of an over-size hole. Sets up to jin. and lin. are available in \(\frac{1}{2} \) in, steps and single plugs can be supplied up to \(\frac{1}{2} \) in or 75 mms. Readings are possible to 0-0002in. actual and 0-0001in. comparatively.

Ask for complete details and prices.

PATENT NO. 799, 830.

OPTICAL-MECHANICAL (INSTRUMENTS) LTD. 36A STATION ROAD . EGHAM . SURREY

Tel.;-EGHAM 3988/9

CUT COSTS KEYWAYS **KEYWAY BROACHES** "Cut perfect taper or parellel Key-ways with any type of hand press, without skilled labour or elaborace set up. No. 0 Set for 1/2-3/2 with guide diameters 1/2-3/2. No. 1 set for 1/2-1/2. No. 2 Set for 1/2-1/2, with guide diameters 1/2-2. No. 3 Set for 1/2-3/2. No. 3 Set for 1/2-3/2. No. 2 Set for 1/2-3/2, with guide diameters 1/2-2. No. 3 Set for 1/2-3/2. Set for 1/2-3/2, No. 2 Set for 1/2-3/2. Set for 1/2-3/2, No. 2 Set for 1/2-3/2. No. 2 Set for 1/2-3/2, No. 2 Set for 1/2-3/2. No. 2 Set for 1/2-3/2. No. 3 Set for 1/2-3/2. No. 2 Set for 1/2-3/2. No. 3 Set for 1/2-3/2. No. 2 Set for 1/2-3/2. No. 3 Set for 1/2-3/2. No. 2 Set for 1/2-3/2. No. 3 Set

W. H. MARLEY & CO. LIMITED


NEW SOUTHGATE WORKS, 105 HIGH RD., LONDON, N.11 TELEPHONE: ENTerprise 5234, 5578

961

rly

5

1.11



INVESTMENT IN EXPANSION

If capital expenditure is worrying you, get in touch with Unifinance. Unifinance specialises in financing all types of industrial equipment. This British company which is associated with American finance organisations, can offer you more flexible terms, geared to your own business needs—a new, more personal level of service.

UNIFINANCE

M(U.K.) LIMITED

103 MOUNT STREET . LONDON W.1

Telephone: Grosvenor 7918

You design it ... we can make it

Prototype and production quantities of precision made components. Sheet Metal Work and Metal Spinning. Plastics, Press and diecasting tools. Complete tool-room facilities including jig-boring, shaping, milling, grinding and planing etc. All forms of welding, including argon-arc. Press work, including deep drawing.

Cornercroft provide as complete an engineering service as you will find—not only tool-room facilities, but sheet metalwork, spinning, moulding, etc., plus every necessary ancillary service. If you want a prototype, experimental assemblies, special components, etc., we welcome the opportunity to discuss how we can help you—many of the leading tool, motor and aircraft manufacturers use our service and we would be glad to help you, too.

CORNERCROFT

GORNERGROFT LTD. (The Cornercroft Group of Companies) Ace Works, Coventry. Phone Coventry 23391 (A.L.D. and A.R.B. approved);



"SENIOR"

PRECISION MILLING MACHINES OF OUTSTANDING VALUE

FINE LIMITS-SUPERB FINISH



'JUNIOR' MODEL Table 20 by 4\frac{1}{4}in. £277-7-0

'M.I' MODEL

Table 26 by 61 in. £365-10-0

'MAIOR' MODEL

Table 34 by 64in. £435-7-6

All prices include standard 3 phase motor and push button starter, suds pump & fittings, cutter arbor.

Full range of attachments available, all at very attractive prices.

Full information on request from:—

TOM SENIOR (LIVERSEDGE) LTD., ATLAS WORKS · LIVERSEDGE · YORKS · ENGLAND



Every year thousands of skilled hands are stilled for weeks, even months, by dermatitis. It's all so unnecessary. Working hands can be protected. Among the recognised measures is the application of a Rozalex Barrier Cream before work. There are 12 of them for use according to the industrial irritant encountered.

AFTER WORK new Rozalex Industrial Skin Cleanser removes contaminants quickly and safely.

Other specialised Rozalex products include Stain Removing Cream, Resin Removing Cream and Waterless Skin Cleanser.

ROZALEX

Keeps Hands HEALTHY

Write for details to ROZALEX LIMITED The Pioneers of Barrier Creams
10 NORFOLK STREET, MANCHESTER 2 - BLACKFRIARS 1122-4

TGA RISE

Tie up the loose ends

Capacities:

Machine	6	10	12A	16	20A
Zinc Ib	1	24	6.3	13-6	25.7
Alum Ib	-	14	2.1	4.5	_
Max. die	81× 91	16× 10	20× 124	28¼× 16‡	351×
Platen stroke	44	6	8	11	13

with an E.M.B. diecaster!

Parts with awkward machining problems like carburettor bodies or those items like star nails for woodwork, where large quantities are the main consideration-or to take the case in point-Vulcan sewing machines, where the parts must go together with the absolute minimum of machining.

Are you sure we can't help you? You're under no obligation by making sure!



With acknowledgements to Sydney S Bird & Sons Ltd., of Poole, Dorset. Makers of Vulcan Miniature Sewing Machines.





Mossner

Table 30in.× 32in. Throat depth 37in. Maximum height of material admitted 16in.Cutting speeds, infinitely variable, 50-3,000ft. per min. with high speed range of 7,700ft. for fusion cutting.


EARLY DELIVERY



MACHINE TOOL COMPANY LIMITED

172-178 VICTORIA ROAD · ACTON · LONDON W.3 · Tel: ACORN 5555 Midlands Showroom: 1075 Kingsbury Road, Birmingham, 24 Tel: Castle Bromwich 3781/2

NRP 2613C







THE HOSE THAT MAKES **ALL OTHERS OBSOLETE**

TEGAL FMIT

HIGH PRESSURE NYLON HOSE

Following in the great pioneering tradition of their extruded nylon tubing, Tecalemit now proudly present a new High Pressure Hose-equalling those precision limits of Tecalemit Nylon Tubing already so well known to industry.

Tecalemit High Pressure Nylon Hose consists of:

A precision extruded flexible nylon core tube

High tenacity braiding

An outer sheath of flexible nylon tube

This structure gives the hose its characteristic pliability, with minimum inside bend radii of from lin. to 4in. according to size.

Tecalemit High Pressure Nylon Hose has these advantages:

Greater durability . Longer life . Ease of assembly Re-usable end fittings · Clean finish and appearance Greatly reduced wall thickness—therefore far smaller external diameters and much lighter complete assemblies. And all at highly competitive prices.

If you wish to substantiate these claims, Tecalemit will provide sample standard lengths of hose assembled with common forms of coupling, so that test rigs can be undertaken. Tecalemit High Pressure Hose is supplied in five sizes †", †", †" and †" internal diameter, to meet the needs of industry for hydraulic and pneumatic systems. Write for full technical details of Tecalemit High Pressure Nylon Hoses and their use on hydraulic and pneumatic systems for:-


Agricultural Machinery · Earth-moving Plant Mechanical Handling Plant · Machine Tools



LIMITED (SALES MY) PLYMOUTH DEVON

D

MACHINES FROM OUR DWN STOCK



ASQUITH 34" Floor Bores

SELECTION

PEARN RICHARDS Horizontal Borer & Facing Machine, Facing Head 28" Dia.

WEBSTER & BENNET 36" High-Power Vertical Borer. CHURCHILL Hydraulic Plain Grinder. Swings 20" x 84". LANG 20" Swing x 5ft. Between Centres SS & SC Straight Bed Centre Lathe.

GISHOLT 3L Combination Turret Lathe 4%" H.S.

SMART & BROWN &" Capstan Lathe L.16.

Two STEINEL Model SH4D Horizontal Milling Machines. RICHMOND Model M.V.1. Vertical Miller. Table 30" x 10". Speeds to 1000 r.p.m.

ADGOCK & SHIPLEY 2V Vertical Milling Machine. Table 36" x 10". Speeds to 1500 r.p.m.

WICKMAN MOULTON ATM1 Thread Milling Machine.

OPEN SATURDAY MORNINGS

MACHINE TOOL CO. LTD.

4 minutes from London Airport.

POYLE RD · COLNBROOK · SLOUGH · BUCKS TELEPHONE: COLNBROOK 2442/3/4

PROFILE GROUND **FORM TOOL**

. . in High Speed Steel and Carbide Tipped

We design and manufacture complete tooling for all turret type and Swiss-type automatic screw machines. Cam blanks supplied ex-stock. Cams machined to

customers drawings.





MOSER CAMS & TOOLS LTD. 465 HORNSEY ROAD, LONDON, N.19 Telephone : ARCHWAY 1766 & 7017



- HARD THREADS IN SOFT MATERIALS
- **NEW THREADS IN DAMAGED COMPONENTS**


FULL RANGE OF SIZES AND THREAD STANDARDS IMMEDIATELY FROM STOCK

CROSS MANUFACTURING CO. (1938) LTD. BATH, SOMERSET. TEL: COMBE DOWN 2355-8. GRAMS: CIRCLE, BATH Specialists in the manufacture of Jet Engine Labyrinths, Circlips, Spring Washers, Springs, etc.

HEAVY PLATE MACHINES

EX **LONDON STOCK**

This is an exceptional offer of two very fine machines which can be inspected at the FJE Machine Centre in London.



Fin. capacity GUILLOTINE with a cutting width of 8ft. 43in. Complete with hold-down and calibrated rack and pinion adjusted back gauge.

The press brake is illustrated.

200 tons PRESS BRAKE with a forming capacity in mild steel of in. by 13ft. 11in. over a 2in. vee die opening, or in. by 65in. over a die opening of 4in. All-steel construction.

Both machines are motorised for 415 volts, 3 phase, 50 cycles supply.


Fuller details are available on illustrated specification sheets; please ask for copies.

dwards Ltd

Edwards House, 359-361 Euston Road, London, N.W.I Telephones: EUSton 5000 Tel Telex: 24264 A/B Bescotools Ldn Telegrams: Bescotools London NWI

Lansdowne House, 41 Water Street, Birmingham, 3
Telephones: CENtral 7606-8 Telegrams: Bescotools Birmingham 3

D



No shearing action

with the Horstmann Caliper Gauge


The Horstmann Caliper Gauge incorporates "Go" and "Not Go" Gauges in one instrument. Limits can be checked in one rapid action — saving time without loss of accuracy. A special feature is the radiused thread face on the anvil, which eliminates all shearing action and is particularly useful when gauging soft metals. The absence of projections from the side of the Caliper frame makes it suitable for gauging shouldered work. Models available in a full range of B.A., American, Unified, Whitworth and Metric thread forms.

The Horstmann Test House in fully approved by the Ministry of Aviation and by the War Office, and it is authorised to certify and release gauges of any manufacture.

Enquiries are invited



HOOTERS FOR WORKS ENGINE ROOMS, ETC.



143 Whitfield Street, London, W.1 Euston 5888

We thank our customers for their

urenco

business during the past twelve months.

May we take this opportunity of wishing them all the compliments of the season

MURRAY'S (PRETORIA)
ENGINEERING CO. LIMITED
26/28 PRETORIA RD., ROMFORD, ESSEX
TEL: ROMFORD 42/380



REGISTERED DESIGN 751914

PERFECT PROTECTION WHEN GRINDING OR MACHINING, COMFORTABLE TO WEAR.

STANDS CLEAR OF THE FACE ADJUSTABLE TO ANY ANGLE.

Obtainable from all Engineers Merchants or direct from:—

J. & E. FERRIS LTD.

33 MUSEUM ST., LONDON, W.C.I Telephone: Museum 2876

else jefce face screen for Motor Cyclists Non-Splinter front easily renewable.



Production Tapping and Threading
HAGEN & GOEBEL MACHINES

Hand or Pitch Controlled Feed, spindle reversal by opposed friction dutches, vertical head adjustment.
Bench or floor models available, also an automatic tapping version.

Send for data: MODELS FROM 5/64" to 21" TAPPING CAPACITY



Feed, ction nent. able, sion.

MODEL HG 23 N 5/64* dia. in steel

MORTIMER HOUSE, Acton Lane, London, N.W.10 Tel. ELGar 3834


130 SHAFTS FACED AND CENTRED PER HOUR

Facing $\frac{1}{8}''$ off each end and drilling $\frac{7}{16}''$ centres in $2\frac{1}{2}''$ diameter Electric Motor Shafts in a floor to floor time of 27 seconds, is typical of the high production which can be achieved on the —

HEY No. 3 DOUBLE ENDED CENTRING & FACING MACHINE

- Perfect alignment of centres
- True faces and accurate lengths
- Turned finish on faces
- Eliminates subsequent facing down to centres or recentring





We also manufacture Rotary Cam and Profile Milling Machines, Short Thread Milling Machines, Multiple Drilling Heads and Machines. Tapping Machines, Gear Tooth Rounding Machines, Special Machine Tools for High Production. Face 5" diameter: Standard Vices for maximum bar capacity of 6½" or 8" diameter. Minimum length handled 3". Standard bed length to take work up to 24", 48", 72" or 108" long.

007153

TECHNOIMPEX

MODEL VF222

VERTICAL MILLING MACHINE

- TABLE 65in. by 15¾in.
- FEEDS 47¼in. by Ilin. by I6in.
- 20 SPEEDS UP TO 1500 R.P.M.
- 14½ H.P.
- NET WEIGHT 4 TONS


IMMEDIATE DELIVERY

Exclusive Selling Agents in U.K.



THE TIMES MACHINERY CO. LTD.

Poyle Road, Colnbrook, Slough, Buck Telephone Colnbrook 2442 3 4



NEW The



SELF-FEEDING SHEAR

AIR OR ELECTRIC

This new addition to the range of Duplex Portable Shears is specifically designed to eliminate the hard work and operator fatigue in cutting across wide mild steel sheets from 12 to 7 S.W.G.—and thicker gauges of light alloy sheet. Send for cetails of this outstanding development.

DUPLEX ELECTRIC TOOLS LTD · HIGH ST · PURLEY · SURREY

TELEPHONES: UPLANDS 3731 & 8621

PLIERS & NIPPERS

PARALLEL ACTION
SIDE CUTTING PLIER 495

DIAGONAL
CUTTING
NIPPER 299

END CUTTING
NIPPER 301

PLIERS 486

There's a pair
for every need!
Write for illustrated price list
showing our complete range

MAUN INDUSTRIES LTD., MANSFIELD, NOTTS.

Shockproof Jewelled Movement

AN IDEAL INSTRUMENT FOR THE ACCURATE MEASUREMENT OF INTERNALS PARTICULARLY GROOVES, e.g. CIRCLIP GROOVES

Model Range 51 2'-6' 52 -4'-8' 71 -4'-1-2' 72 -8'-1-6' 73 | 12'-2-0' 74 | 1-6'-2-4' 75 | 2-0'-2-8' 76 | 2-4'-3-2' 75 | 2-4'-3-2' 75 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-2' 76 | 2-4'-3-3' 76 | 2-4'-3-3' 76 | 2-4'-3-3' 76 | 2-4'-3



Platen Type

DEMAGNETISERS

This is a useful type of demagnetiser for quickly dealing with ordinary components in workshops. It is only necessary to pass the magnetised pieces over the platens and they instantly loose the magnetism



J. H. HUMPHREYS & SONS LTD.
BLACKRIDING ELECTRICAL WORKS
WERNETH OLDHAM.

TELEGRAMS: HUMPHREYS OLDHAM TELEPHONE: OLDHAM MAIN 6067

BUCK & RYAN LTD

ESTABLISHED 1824

ENGINEERS' TOOLS

LARGE STOCKS OF

FINE TOOLS

Micrometers Height Gauges Verniers Etc.

CUTTING TOOLS

Milling Cutters Taps Dies Reamers Etc.

LIGHT MACHINE TOOLS Lathes Millers Drillers Etc.


HAND TOOLS

A VERY LARGE SELECTION

DEPT. S

310 312, EUSTON ROAD, LONDON, NWI AND AT 261; EDGWARE ROAD, W2

Telephone: EUSton 4661





Imagine the reduction in nervous tension amongst your employees when you reduce vertical vibration by 80%. Imagine the reduction in machine wear, too, Yet an 80% reduction is perfectly feasible for many types of machinery with the Croid-Cooper method of installation, where the machine is simply stuck down on a felt base with a holding power of 80 lbs. to the square inch. May we send you details?

OF MACHINE FIXING
DAMPS VIBRATION

CROID 65
MACHINE FIXING GLUE
COOPERS


3357

COOPER & COMPANY (Birmingham) LIMITED

Head Office and Works:
BRYNMAWR, BRECONSHIRE
SEARCH Office and Works:
SEELEY'S ROAD, BIRMINGHAM 11 TELEPHONE: VIC 5417

Dec

Are you wasting Floor Space?



It takes up less than 3 square feet.

It gives 7½ square feet of shelving.

It gives 3½ square feet of yale secured shelving space.

Made from heavily enamelled mild steel.

Size 39in, by 18in, by 15in.



TYPE 27A

Note how the door folds back out of the way!

This is achieved by a cunning door design which folds back twice and turns in a radius of 8ins.

Send for illustrated leaflet

JAMES BEDFORD & CO. (HALIFAX) LTD.

Globe Works, Victoria Road, Sowerby Bridge, Yorkshire.

Phone: Halifax 81800.



STRANDS DRILLING MACHINES

ofter SPEED plus RIGIDITY

plus ECONOMY!

Built by specialists in drilling machines, these economical models offer all you need for reliable drill work — at the right price. There is a wide range of Bench and Floor Models—ask us for full data.



Mortimer House, Acton Lane, London, N.W.10 Telephone: ELGar 3834 NRF5141





MACHINERY'S SMALL ADS
BRING BIG RESULTS!



compact

greatest strength for weight

most efficient and reliable

Mollart Engineering universal ball joints, used everywhere in fields as widely dissimilar as aircraft and agricultural machinery, are made by the latest specialised plant under rigorous control. Sliding and fitting surfaces are ground to a tolerance of 0.0005°. Mollart Engineering supply single, double, "Heoke's"-type, and light series universal ball joints in standard sizes. Non-standard and special types are supplied to customers' requirements.

A.R.B. approval of design and materials

THE MOLLART ENGINEERING CO LTD

KINGSTON BY-PASS SURBITON SURREY
TELEPHONE: ELMBRIDGE 0033-7 TELEGRAMS: PRECISION SURBITON

P5527

If you're expanding then you're borrowing...

More permanent capital is what you need —
I C F C can provide long-period loans on fixed terms, and share capital, to businesses in Great Britain.

Set up by the English and Scottish Banks in 1945, Industrial & Commercial Finance Corporation Ltd has provided £70 million to nearly 1000 companies.

'CAPITAL FOR BUSINESS'
which explains what the
Corporation can do
will be sent on request.

(ICFC)

LONDON

7 Drapers' Gardens, EC2 National 8621/5

and branches in industrial centres.

D

CLASSIFIED

ADVERTISEMEN

LINE (All type, except Situations Wanted), Col. width 14 in., 13 lines per inch, min. 4 lines, I line averages 6 words, 2/6 per line single insertion (series discounts on request). "SITUATIONS WANTED," I/II per line, min. 4 lines.

RATES: DISPLAY (with or without blocks), £2 6s. 0d. per inch single column and pro rata (series discounts on request).

Box Nos. 2/- extra. Classified advertisements can be accepted at London Office up to Wednesday preceding following Wednesday's issue.

CONTRACT WORK

• • • DESIGNS

NOW!! SPARK EROSION TO THE TRADE On Precision Swiss Eleroda Machine

Reduce Press Tool costs **EARBIDE-FORGING-EXTRUSION** IMPACT EXTRUSION DIES

We also modify existing tools

PRESS TOOLS


JIGS-FIXTURES PROTOTYPE MACHINING

Designing-Short Order Work-Sub Assemblies Completely Tooled JIG BORING AND PRECISION GRINDING LANDEN (ENGINEERS) LTD.

la, Aubert Park, Highbury, London, N.5 Phone: CANonbury 1075

TOOL DESIGNERS AND HANUFACTURERS

JIGS FIXTURES - GAUGES PRESS TOOLS FORM TOOLS AND SPECIAL MACHINES



Viking Works, London Rd., Romford, Essex. Tel: Romford 61991/2







W.R.SOUTHWELL (DESIGNS) LTD 30 ST. DUNSTANS HILL, CHEAM SURREY 'Phone: FAIRLANDS 3617 & 7548

DESIGN & PLANNING

PRESS TOOLS JIGS & FIXTURES
SPECIAL PURPOSE M/CS DIECASTING MOULDS PLASTIC MOULDS PIPING, DUCTING, ETC

Export Enquiries Invited

"DESIDRACE" Offer a Design, drawing and tracing service in light mechanical, electrical, electrical, electronach calculations, electronic engineering. Experienced draughts-nem,—Telephone: Maryland 9002.

By WHALES, Irn., Rear of 128, 014 Dovernem,—Telephone: Maryland 9002.

• ENGINEERING BUYERS NEED MACHINERY'S ANNUAL BUYERS' GUIDE

Classified Advertisements (CONTRACT WORK, contd.)

MANUFACTURERS OF THE FINEST QUALITY GEARS. SPUR. HELICAL. STRAIGHT BEVEL AND EPICYCLIC

HENRY MEADOWS LTD FALLINGS PARK WOLVERHAMPTON

GEARS. SPUR GEARS **GROUND OR SHAVED** 0.50" TO 40.00" DIA. 3 D.P. TO 40 D.P. EVERY CARE AND SKILL IS EXERCISED

IN THE MANUFACTURE, RESULTING IN PERFECT TOOTH FORM.



• • GEARS

Gears . . Worms . . Any Quantity
Instrument Gears a speciality. A.I.D.
Approved. #in. to 10 in. dia. 5DP-120DP.—
CLARKE OLSEN (GRARS) LTD., 194 Heeler
Rd., Birmingham 29. Phone: Selly Oak 0267

Gears Cut or Machined Complete. One-off or production runs— F. W. BAGGETT & CO., Ltd., Heath Mill Road, Wombourne, Nr. Wolverhampton. "Phone: Wombourne 2403.

Gear Cutting Work Wanted.
Immediate capacity No. 3 type Barber
Colman up to 12 DP and Fellows No. 7 Gear
Shaper.—BOX D431, MACHINERY, Clifton House,
Euston Road, N.W.1.



G. H. TURNER & Co. L. oli Street, WOLVERHAMPTON Phone 20852 (3 lines)



GEARS We are Specialists

F. M. IILLICH (GEARS) LTD

OXGATE FARM WORKS
COLES GREEN ROAD CRICKLEWOOD, N.W.2.

Telephone: GLAdstone 6322
SPIRALS SPURS WORMS & WHEELS BEVELS SPROCKETS
CAPACITY LIST ON APPLICATION



SERVICES

Plough Grinding—Plate and Components—Ground Blanks supplied— BRUNSWICK ENG. CO., 120. Ewell Ecoal Surbiton, Surrey. ELMbridge 5872. and

De

Plough Grinding

ANY QUANTITY . MAXIMUM SIZES 60" x 18" RECIPROCATING TABLE

48' DIAMETER ROUND TABLE . HIGH SPEED SERVICE TOOL COMPANY LIMITED

MAPLE ROAD SURBITON SURREY TELEPHONE ELMBRIDGE 1135-6-7





GENERAL HEAT TREATMENT

CASE HARDENING AND CYANIDE HARDENING ON PRODUCTION BASIS OR SINGLY

SHOT-BLASTING

CROYDON TOOL AND CASE HARDENING SPECIALISTS LIMITED

UNION ROAD WEST CROYDON Tel. THORNTON HEATH 5222



(A.I.D. approved)

for PROTOTYPES AND PRODUCTION

FINE PRECISION ENGINEERING

12, OVAL ROAD, LONDON, N.W.I. GULliver 2353 · 4085

HEAT TREATMENTS ABBEY LTD. PLAZA WORKS, HIGH STREET, MERTON, S.W.19 FOR ALL TYPES OF HEAT TREATMENT WE COLLECT-WE DELIVER

A.I.D. A.R.E.

TELEPHONE: CHErrywood 2291

Hydraulic and Pneumatic Problems? Let us help you. We are design
and production experts. Also repairs and maintenance. Fabricated units of all types.
Hydraulic Division.—WILLIAM MOSELEY
(ENGINEERS). LTD., Bedfont Road, Feltham,
Middlesex. Feltham 4071.

D.I. Arm.

CASE HARDENING and HEAT TREATMENT

Quick Deliveries

ATTERY OF FURNACES INCLUDES SALT BATH FURNACES 6" o" DEEP AND M" WIL

HEAT TREATMENT OF HIGH SPEED STEELS AND DIES BY CARBO-NEUTRAL PROCE

ANNEALING AND CARBURIZING CYANIDE HARDS AUSTEMPERING

ON A.I.D. LIST

HOLT BROS (HALIFAX) LIMITED HOPE STREET, HALIFAX

EST 1840 PHONE: HALIFAX 40341

A.I.D. and A.R.B. Approved

HARDENING CO., LTD. DAVIS ROAD, CHESSINGTON, SURREY

> HEAT TREATMENT **SPECIALISTS** HARDENING OF **EVERY DESCRIPTION** AND SANDBLASTING

> > Tel.: ELMBRIDGE 6556

tonebridge PLOUGHGRINDING Service 707 Tudor Estate, Abbey Road, Park Royal, London, N.W.10. ELG. 5353. GROUND BLANKS SUPPLIED.

Cylindrical and Internal Grinding up to 10in. O.T. Production Milling. olmaking capacity available.—BEDWARD BAKER, Avenue Works, The Avenue, wton Abhot. Tel.: 2312.

EAT TREATMENT
CASE HARDENING, CARBURIZING & MARTEMPERING AND
HARDENING & GEARS A SPECIALITY & A.I.D. APP.

FLAME HARDENING . ALAN KEIR LTD.,

NORTH ACTON ROAD, LONDON N.W. 10. Elgar 2612

Classified Advertisements (CONTRACT WORK, contd.)

A.I.D.

-THE-- ELGar 5057/8 HEAT TREATMENT

PEOPLE OF LONDON

G.R.M. Heat Treatments Ltd., Coronation Rd., Park Royal, N.W.10

INTERNAL HONING

A stock removing process combined with close tolerance control and any required surface finish, using Fulmer Honing Machines.

We offer capacity for honing bores lin.—12in. diameter up to 54in. long.

PERFECTION ENGINEERING LTD. COLESHILL, BIRMINGHAM

AUTO CAPACITY

6in. and 4in. Chucking. approved.

HUNTLEY & SPARKS LTD

James Estate, Western Road, Mitcham, Surrey

Capacity available for AUTOMATICS Single Spindle and Multi Spindle from Bar in.-Iiin.

Also CHUCKING AUTOS. BRYCE LTD

Kelvin Works, Hackbridge, Surrey Tel: Franklin 1101

INDUCTION HARDENING AND BRAZING

CYANIDE HARDENING, PACK CARBURISING Shot-blasting

PRECISION HEATING LTD., Island Farm Avenue, West Molesey, Surrey Phone: MOLesey 4231

IMMEDIATE CAPACITY AVAILABLE

Heavyand Light Sheet Metal Work, Weld-ing Fabrications, Press Work up to 75 tons, Milling, Turning and General Machine Shop Work, also Spray Painting and Dipping. Send enquiries to: C.P.E. LTD. High Street, Cranieigh, Surrey. Tel: Cran 911/2

PRESS TOOLS - JIGS & FIXTURES
SPECIAL PURPOSE MACHINES - PROTOTYPE WORK PRECISION GRINDING TO FIRE LIMITS.

NEWCOMBE & HASTINGS LTD.

ARLBOROUGH YARD, MARLBOROUGH ROAD HOLLOWAY, N. IS

Capacity Available for Assembly Fabrication work and 60/100 ton Press work by Engineering Company having two factories in West Riding of Yorkshire. Contact in first instance Head Office:—

BENTHAM TYRE MACHINERY
LTD.,
Prospect Works, Allerton, Bradford.

HIGH CLASS REPETITION WORK CENTRE LATHE TURNING THREAD MILLING HARDENING CARBURIZING MILLING SHAPING DRILLING ETC Write and ask for Prices BAYLISS ENGINEERING

TAN & TURRET WORK A SPECIALITY

CENTRE

CASTINGS

ECLIPSE FOUNDRY

& ENGINEERING CO. (DUDLEY) LTD SEDGLEY ROAD WEST TIPTON . STAFFS.

GREY IRON ALUMINIUM FERROUS MAZAK

PROTOTYPES & SPECIAL PURPOSE MACHINES REPAIRS AND SALVAGE BY DEPOSITION MACHINING FORGING & FABRICATING GEORGE MILLS (ENGINEERS) LTD.
Beckenham, Kent. Tel.: Sydenham 5255

Immediate Capacity Available castings, non-ferrous, die, shell moulded sand, etc. Also machining and stove enameling.—MILLS ENGINEERING PRODUCTS. LTD., Barnet. Phone: Barnet 6744.

• • MACHINING

AUTO TURNED PARTS

FINE TOLERANCES, MAX. DIA. I II INDEX SS & GRIDLEY MULTI AUTOS THREAD CHASING MANUFACT'RS ROLLER BOX TOOL HOLDERS BENTON ENGINEERING CO., LTD.

Tonbridge Road, Harold Hill, Essex Ingrebourne 43864/5.

LATHE CAPACITY available up to 3ft.
dia. to toolroom limits. Particular attention
given to individual requirements.—R.E.H.
PRECISION ENGINEERS, BAGSHOT ROAD,
BRACKNELL, OR 'PHONE BRACKNELL.

COMPREHENSIVE

CAPSTAN WORK REQUIRED on Herberts, Maxnovo and Minganti up to 2gin. dia. Bar and Chucking.

Commercial or Approved. Quick delivery guaranteed.

Christchurch Engineering Co. Ltd. Broom Read, Parkstone, Derset Parkstone 5251-2

Centreless Grinding Capacity. Infeed Plunge, Int. o 4in.—CHISWICK ENG'G., Ltd., Pluckington Place, Southall, Middx. Tel.: Southall 2247.

for PROTOTYPES

DESIGN & CONSTRUCTION OF SPECIAL MACHINERY

ALSO CONTRACT WORK, MEDIUM AND SMALL PRECISION MACHINING, GEAR CUTTING AND COMPLETE ASSEMBLIES

ORSMAN ROAD SHOREDITCH LONDON N.1

Telephone: Shoreditch 7811/7815

Telegrams: WILMAKET, London N.I

PRECISION TURNED PARTS

D.G.I. and A.R.B. APPROVED AUTO & CAPSTAN QUANTITIES d your specification to:

AYLESBURY TURNED PARTS (True Screws) Limited

Britannia St., AYLESBURY, Bucks. Telephone: AYLESBURY 2424 (3 lines)

Automatic and Capstan Capacity Available up to 2in. dia.— WILLIS ENGINEERING LTD., 55, High Street, Hampton Hill, Middlesex. Molesey 1121 & 2.

Automatic Capacity Available on single spindle machines.—BARMAC
ENGINEERING COMPANY, Bridge Works,
Iver Lane, Cowley, Middlesex.. Telephone:
Unbridge 39839.

Automatic Capacity Available.

Swiss Machines up to in. dia., also small
and miniature cylindrical grinding.—POTTER,
WALLES & CO., 46, Beaumont Road, Chiswick,
W.4. Telephone Calswick 2703.

Capacity Turning, Capstan milling, drilling, die and tool making.
—MILS ENGINEERING PRODUCTS, LTD., Barnet. Tel.: Baknet 6744. Capstan

Automatic Capacity Available, Index single spindle Autos. up to 2 in. diameter. Centreless Grinding Capacity, in. to 6in. diameter.

JAN PRECISION SCREWS, 629, Spur Road, Feltham, Middlesex. Telephone: Feltham 4282/3.

Multi-spindle and Single-spindle Multi-spinule and single-spindle
Auto. Turning up to 2in, her capacity,
capatan turning from the bar up to 24in, dis.,
chuck work up to 14in, dis., thread milling,
milling, shaping, drilling, etc., capacity available. Any tolerance and quantity. Satisfaction
absolutely guaranteed.—UNICORN PRODUCTIS_LTD., 119-121, Stanstead Road, Forcat
Hill, 8.E.23. Phone: FORest Hill 7888 (3 lines).

Automatic Capacity Immediately available. Swiss type machines up to #in. dia.—E. V. IRONS, Clovelly Works, \$72 Actea Lane, Chiswick, W.4. CHiswick 1007.

Capacity Turning, Centre Lathe, Capstan, etc.—WILBAR ENGINEERING CO., 97, Queens Road, Nuneaton. 'Phore 4863.

Automatic Capacity Available, Index Autos, up to 2 in, diameter. Chucking up to 5 in.

JAMES HARRINGTON, Magda Works, Walton-on-Thames. Tel.: 26099 & 25614.

Capstan Capacity Immediately
Available, 8 BA-1 in. Steel or Brass.
Large stocks of raw materials.

SACRON, LTD., 7. Chiswick High Road, W.4. Tel.; CHIswick 3595

High Precision Grinding of Tungsten Carbide and Steel Tools. Accurate profile grinding and progression tools a speciality.—8. T., LTD., 22-26, Upper Mulgrave Road, Cheam, Surrey. Phone: Vigilant 0074/5.

Capstan Capacity Immediately available 10 BA to 1 in. B.M.S. Stainless, Brass, etc. All materials in stock.—CHISWICK ENG. LTD., Pluckington Place, Southall, Middleser. Tel.: Southall 2247.

CENTRELESS GRINDING SPECIALISTS

BAR GRINDING

A.I.D. APPROVED Tain. TO Sin. DIA. UP TO 15ft. LONG all types of infeed, through and plunge

IMMEDIATE CAPACITY ON CAPSTAN, MILLING CENTRE LATHES, AUTO AND ALL TYPES OF GRINDING

REDCAR ENGINEERING CO. LTD. Tel: POPESGROVE 1005/6/7

8 STATION YARD GROSVENOR RD TWICKENHAM MIDDX

AIRCRAFT UNIT ENGINEERING CO.

A.I.D., A.R.B., AND LIMITED A.R.B., DESIGN APPROVAL

Turning, Copstan and Centre Lathe. Milling, Universal, Profile. Grinding, universal, surface, centreless, etc. (up to 86in. x 15in. dia. Plain Cylindrical)

Screw Cutting (Cridan machines) and Thread Milling General Assembly Work Modern plant producing High Quality work

18-19, Greenhill Parade, Great North Road, New Barnet, Herts.
Telephone: BARnet 6471 and 7479

Capacity Available on Single spindle Autos up to 14 in. Capatan 2in.
Small gear cutting, milling, grinding, etc.
M.O.A. approved inspection.—S.M.E., Ltd.,
Steyning, Sussex. Phone: Steyning 2228.

Automatic Work up to 1in. immediate capacity available.
TRUE ENGINEERS, LTD.,
Wharf Lane, Bourne End, Bucks. 'Phone 1316.

WE MAKE TANKS, FRAMES, DUCTS, INSTRUMENT PANELS AND CHIMNEYS Let us have your enquiries for welded fabrications large or small. And we can press 200 Tons, guillotine bend and cylindrical roll in plate.

HELMERDINE & MULLEY LIMITED EDGWARE ROAD, CRICKLEWOOD N.W.2. Tel: GLAdstone 7677-8.

CAPSTAN CAPACITY IMME-301n. IlaTELY available from 0.050 dia. to 301n. In any specified material. Extremely rapid service.—R.E.H. PRECISION ENGINEERS, BAGSHOT ROAD, BRACKNELL. 'PHONE: BRACKNELL 1441.

Automatic Capacity Available, B. & S. up to 1iin. dia. — C.B. AUTO-MATICS, Bridge Works, Iver Lane, Cowley, Middlesex. Tel.: Uxbridge 33428.

Immediate Capacity Available on Single Spindle Automatics up to 14in.— HARRADINE AUTOMATICS, Forge Works, Pleasant Place, Hersham, Surrey. Phone: Won.T. 24918.

Gear Cutting, Auto Turret, Capetan and Centre Lathe Turning, Milling, Hardening and Grinding, Profile Cutting and Weiding.

SMITH & NETHERWOOD.

LTD.
Tanyard Road, Quarmby,
HUDDERSFIELD
Phone: MILNSBRIDGE 1865

Automatic Capacity Available on Index single spindle autos, up to 2in. dia
—ARTHURS ENGINEERING, LTD., Hersham
Trading Estate, Molesey Road, Hersham
Surrey. Phone: Walton-on-Thames 21277.

E. R. LATTIMER LTD AID & ARB APPROVED

Offer complete Service for PRECISION PROFILE MILLING, JIG BORING SHAKESPEARE

CENTRELES," SURFACE AND UNIVERSAL GRINDING LIGHT TO MEDIUM COMPONENT MANUFACTURE TOOL DESIGN & MANUFACTURE SMALL ASSEMBLIES, DIE & MOULD MANUFACTURE


SMALL PRESSURE DIE CASTING IN MAZAK ALLOY TO BS 1004 SUPER PRECISION HYDRAULIC COMPONENTS AND ASSEMBLIES FOR WHICH WE HAVE HYDRAULIC TESTING EQUIPMENT

STREET SOUTHPORT

Phone: 57696/7

61

Classified Advertisements (CONTRACT WORK, contd.)



CAM cutting

Ground Plate Cams for Cam Contour Boring Machines Barrel Cams, milled and ground-Index Cams Conjugates — Experimental Camshafts — Gangmasters Ground Pump Cams-Rings and Piston Cams

zephyr cams Itd.

Lowestoft 4271 Freemantle Road - Lowestoft - Suffolk

CUTTING TOOLS AND PRECISION GRINDING



TECHNITOOLS LIMITED 128, WINDHILL ROAD, WEST CROYDON, SURRE

TELEPHONE AND INLAND TELEGRAMS. THORNTON HEATH &

HORIZONTAL AND VERTICAL MILLING to Toolroom limits from 1 off to 100 off, from large fabrications to small ligs or fixtures.—R. E. H. PRECISION ENGINEERS, Bagshot Road, Bracknell.







and CYLINDRICAL GRINDING

External up to 12 in dia by 36 in . Internal up to 7 in by 84 in

MARSDEN & SHIERS LIMITED A DAVIS ROAD . CHESSINGTON . SURREY R D Telephone: Elmbridge 5333 (3 lines)

De

J. M. HARGREAVE & CO. LTD., CENTRAL AVENUE, W. MOLESEY, SURREY

MACHINING CAPACITY ... phone: KIN 6112

PRECISION & GENERAL ENGINEERING.
CAPSTAINS, TURRET LATHES, AUTOS, LATHES, MILLS, DRILLS, BORERS,
ALL GRINDING, FULL MACHINE SHOP SERVICE
COMPONENT & ASSEMBLY PRODUCTION IIGS, TOOLS, FIXTURES, PRESS, TOOLS

W.G. MARSDEN ENG. LTD.

UNRIVALLED EXPERIENCE -TOP QUALITY - KEEN PRICES 30 FIFE ROAD, KINGSTON - ON - THAMES, SURREY

SPECIAL ANNOUNCEMENT

We can now offer

IMMEDIATE CAPACITY

- Auto's, Swiss & Turret
- Centreless & External Grinding.
- First class Drilling & Tapping Section.

MURRAY SON & CO. LTD. 165, Tottenham Lane, London, N.8.

Telephone: MOU 3019-2261

TOOL AND CUTTER GRIND-ING Capacity immediately available. Very quick service and delivery.—R.E.H. PRECISION ENGINEERS, Bagshot Road, Bracknell. Phone 1441.



Spur Gear and Sprocket Cutting from blanks supplied or machined conplete. Phone: EUSton 1854.
TURNER BROS.
10, Pratt Mews, Camden Town, N.W.1.

Automatic Capacity Available, Index single spindle autos, up to 14in. dia—PRESS & PRODUCTION MACHINE. TIOLS, LTD., 97a, High Street, Teddington. TED Lock 4082.

LET US HELP YOU!

We are experts on Automatics. Design and Manufacture of Cams and Circular Form Tools is our Business. LET US MAKE IT YOURS! Cams machined to customers drawings. Excellent Delivery. Competitive Prices. We should be pleased to quote you!

ABRIDGE CAM & TOOL COMPANY, ABRIDGE, ROMFORD, ESSEX PHONE: THEYDON BOIS 3074

V. J. COPAS LTD.. Friar Park Road, WEDNESBURY, STAFFS.

Tel: Wednesbury 1051/3

Precision Engineers, Instrument Makers, offer complete machining and/ or assembly capacity for light to medium components in prototype or batch production quantity. All metals

Centre lathes to 6in. capacity. Capstans to 21in. capacity.

Milling, drilling and cylindrical grinding.

D.G.I. & A.R.B. fully approved.

Automatic Capacity available on Herbert No. 4, 3A and Junior Chucking Autos, reply to:-

WILDT MELLOR BROMLEY LTD. P.O. Box No. 68,

Adelaide Works, Aylestone Road, Leicester. Telephone: 33311.

Thread Milling for the Trade, up to 6in. O.D. and 5in. I.D. Any thread, any quantity. Keen prices for long runs. Satisfaction guaranteed.

UNICORN PRODUCTS, LTD., 119-121, Stanstead Road, Forest Hill, London, 8.E.23. Telephone: Forest Hill 7688 (3 lines).

AUTO CAPACITY, Multi and Single Spindle to lin. dia.; Chucking 6in, & 8in. CENTRELESS GRINDING CAPSTANS, MILLS, DRILLS ALLEN & SIMMONDS (LONGHAM) LTD., WIMBORNE, DORSET (Northbourne 582)

Grinding Capacity Available.

Surface, 18in. by 6in.

M. & W. ENGINEERING, LTD., 141a,

Hersham Road, Walton-on-Thames, Surrey.

Phone: W. O-T 23388.


Medium Engineering Co., King's Cross area, with toolroom, drawing office and production capacity, invites enquiries for Machining on autos, capstans, mills, etc. Short, medium or long runs. A.I.D. and A.R.B. approved inspection.—Replies to: TRE SIMCUP CO., L7D., 274, York Way, N.7. NOEth 1668-9.

INVESTMENT CASTERS

CAPACITY AVAILABLE IN PRECISION SMALL PARTS

A.I.D. (JEWELS) LTD. 24 Wheler Street, London, E.I. BIS 9884

PRESS



SUB-MINIATURE PRESSINGS

and multi-stage precision presswork
in all materials
PROMPT DELIVERIES

4. A. PRECISION PRODUCTS LTD
No. 2 Factory Darkes Lane,
Potters Bar, Middleex
Potters Bar 6895

Classified Advertisements (CONTRACT WORK, contd.)

SELIABLE SERVICE . COMPETITIVE PRICES . A.I.D. APPROVED

PRESS WORK

INCLUDING DEEP DRAWING, WELDING
AND SUB-ASSEMBLY

to any tolerance, shape or quantity

ECONOMIC STAMPINGS LTD., DISRAELI ST. LEICESTER Tel: 32233

•• TOOLMAKING••



WE DESIGN

AND MANUFACTURE

PRESS TOOLS

AND DO THE

PRESS WORK

A.I.D. & A.R.B. APPROVED

NAISH BROS. & CO. LTD.

KNAPPS LANE, ST. GEORGE, BRISTOL 5. Tel: 657204/5

Pressings in all Metals up to 60 tons. Press tools manufactured in our own toolroom. Light aswernbiles. Douestic Electrical and Mechanical All finishes. A.I.D. and A.B.B. approved. Advice and estimate given free. Inquiries to:—

METAL COMPONENTS, Ltd.,
Dolphin Road, Shoreham-by-Sea, Sussex.
'Phone: Shoreham-by-Sea 2224/5.

Pressings and Stampings, Ltd. Eccleston Road, West Ealing, W.13 Presswork up to 136 tons. Double action deer drawing guillotine 3ft. by 10 s.w.g. Spotwelding, Assembly. Toolmaking and electroplating.—Phone: EALing 3667-8.

Press Productions

Pressings on auto or hand fed presses. Immediate capacity up to 40 tons. Production from our or customer's tooling. A.I.D. approved.—Summersby Road, Highgate, N.S. TUDor 9851.

JIG BORING HORIZONTAL BORING FORM GRINDING

PRECISION MACHINING

@AUGES—PRESS TOOLS

MOULDS—JIES & FIXTURES

MEDIUM SPECIAL PURPOSE MACHINE

TOOLS

WELLVIL ENGINEERING CO. LTD., SPRING PLACE, EBENEZER ST. LUTON, BEDS. TEL. LUTON 3837 (3 lines)

COVENTRY GRINDERS LTD

AID, ARB Approved Phone 73344

Send us your enquiries for

GAUGES, FORM TOOLS, DIES, PROTOTYPE, COMPONENTS, MANDRELS, CRUSHERS, JIGS, GEAR CUTTING, OPTICAL FORM GRINDING, CENTRELESS INTERNAL, EXTERNAL, SURFACE, ALL SIZES
OF PRECISION
GROUND
GAUGEPLATE
IN STOCK
12 to 18in.
WIDE
12 to 14in.
THICK
18in. to 48in.
LONG.





ROMFORD 61981

MACDOWALL EQUIPMENT COMPANY LIMITED HORTH STREET ROMFORD, ESSEX

D



TOOLMAKERS

Barr St., BIRMINGHAM 19.

Literature on request

Sole Manufacturers of: CARBIDE TOOLS

PRESS TOOLS - IIGS-FIXTURES-

Tel: Northern 8421 (4 lines)





PRESS TOOLS, JIGS, FIXTURES AND GENERAL MACHINING

We have capacity available in our Harlow Trade Tool Room and delivery is prompt.

Enquiries to:

38 SOUTH ROAD, TEMPLEFIELDS, HARLOW Telephone: HARLOW 25943

FRACTIONAL H.P. GEARED MOTOR UNITS-

Enquiries to:

3 BUSH FAIR, HARLOW. Telephone: HARLOW 21245

or to London Office:

SENTINEL HOUSE, SOUTHAMPTON ROW, W.C.1

Telephone: HOLborn 0841/2

Quick Deliveries For:

FORM GRINDING TOOLS, GAUGES, PUNCHES, DIES, ELECTRODES. COMPONENTS



Precision Grinding Ltd., Mill Green Road, Mitcham, Surrey MITcham 3014-6



Press Tools, Press Work, Capstan Turning and General Machining. Components manufactured and assembled to specifications.—L. PERSON & SON, 63, Shaftesbury Street, London, N.1. CLE 7139.

SPECIALITIES

Tungsten Carbide Tool

Manufacturers of standard and special form tools in high speed steel and tungsten carbide. Our range includes reamers, cutters, work rest blades and wear-resistant parts.

Carbide supplied to customers' specifications and express service given for emergency tooling

DIAGRIT GRINDING CO., LTD., Station Road, Staplehurst, Tonbridge, Kent. 'Phone: Staplehurst 449.

DING-DONG Vari-Pitch Multi-Purpose

SOLD BY LEADING TOOL DEALERS

HACKSAW BLADES

MANUFACTURED BY CHARLES BAYNES LTD. KNUZDEN BROOK **BLACKBURN · LANCASHIRE**

MACHINERY

Classified Advertisements (SPECIALITIES, contd.)

ABOUT AMMUNITION BOXES THOUSANDS OF STEEL AND WOODEN BOXES OF ALL SIZES Ideal for all Types of Packing & Storage

purposes.

For particulars and prices apply:—
O.K. TRADING (B'HAM FACTORS) LTD.
78-84 MOAT LANE, B'HAM 26
STECHOOR 4351/2 P.B.X.

TIME RECORDERS-Sales

Rental Service: Tel. Hon. 2239.
TIME RECORDER SUPPLY &
MAINTENANCE CO., LTD.,
157/159, Borough High Street, London, S.E.1.

GIRCLIPS.

all types from stock

ELLISON SPRING CLIPS LTB., BINGLEY YKS. Tel: CULLINGWORTH 8836/7



Complete Box Banding Equipments, comprising machine, coil-holder strapping and seals, can be supplied in the following sizes: tin. gin. jin. gin. gin. lin. liin. & liin.

TAPERLOCK & TRILOCK GAUGE HANDLES

Engraving Service

& BLANKS Complying to B.S. 1044

Handles produced from aluminium material, anodised in various colours. Special length handles for deep bores. Blanks manufactured in cast steel hardened throughout tapers ground to size.



BRILHART LTD - HATFIELD - DONCASTER Tel.: Hatfield Woodhouse 202









WALTER SLINGSBY & CO., LTD WASK WORKS . KEIGHLEY

THE WORLD'S LARGEST SELECTION OF BRITISH, AMERICAN AND CONTINENTAL BEARINGS IN ALL TYPES AND SIZES IMMEDIATE DELIVERY FROM STOCK . KEENEST PRICES

- 9 2 1 FULHAM ROAD LONDON 5 W 6

PHONE: RENOWN 6174 (Ext. 24) **TELEX 23453** CABLES: RYE BEARINGS, LONDON

ANNOUNCEMENTS

BUSINESS OPPORTUNITIES

Export to the Common Market Young firm specialising in the sale of precision machine tools with offices or agencies in the most important industrial centres of Continental Europe can accept high quality engineering products to complete programme.—Write BOX D415, MacHanniav, Clifton House, Euston Road, N.W.1, giving details of products and countries of interest of

Rstablished Business Manufacturing washing machine spares. Steady cash turnover £40,000. Non-competitive. For sale. Stocks, tools, goodwill, knowhow.—BO's. D424, Machinery, Clifton House, Euston Road, N.W.1.

PHOTOGRAPHY

Miles & Kaye, Ltd., 102, Southampton Row, London, W.C.1. Rolborn 6858. Specialists in commercial and Industrial photography for over 60 years. All branches of photographic work undertaken.

Photographs by MACHINERY set the standard in engineering publicity. Our studio is one of the best equipped in the country. Ideal for really good photography of tools, attachments and portable equipment. Mobile units available for taking photographs in black and white or in-natural colour in your own or your customer's works. Specimens of work submitted on request—Full particulars from the SERVICE MANAGER, MACHINERY PUBLISHING COMPANY, LTD., National House, West Street, Brighton, 1.

· WORK TO PLACE •

500 to 1,000 Hours Per Week required Medium/Light General Machining Capacity, mainly small batches. Please and particulars of plant to BOX D356, MAGRIERERY, Clifton House, Euston Road, N.W.I.

PACKING AND SHIPPING

R. & J. PARK, LTD., Dominion Works, Chiswick, England, Export packers, shippers and forwarding agents. Specialists in packing heavy machinery.

TROPICAL PACKERS (CHE-SHIRE) LTD., Canal Street, Congleton, Cheshire. Export Packers and Forwarding Agents, on Ministry and Government Approved lists.

BUSINESS FOR SALE

FOR SALE

Small well equipped light engineering company situated in Mid-Kent. Full details from:—

Box D429 MACHINERY Clifton House, Euston Road, N.W.I

MATERIALS

All Grades Iron, Steel and Non-Ferrous scrap. Specialists Light Iron-Borings and Turnings—oversize cast. Collected or delivered works by road or rail.— CHICHESTER METALS LTD., Scrap Metal Merchants, 13, Kings Road, Gulldford. Tel.: 60123.

Roller Conveyor—Unused. 28 lengths. 1ln. dia. Rolls × 4½in. × 10ft. long at 10s. per foot.—ROLLS TOOLS, LTD. No. 1 Factory, Pyrford, Woking, Surrey-Byfleet 43252.

MATERIALS WANTED

£200,000

AVAILABLE FOR THE PURCHASE OF NEW BALL & ROLLER

REARINGS

OF ALL TYPES & SIZES

BY BRITAINS BIGGEST BUYERS

CLAUDE RYE BEARINGS 895-921 FULHAM RD. LONDON SW6 RENOWN 6174 (Ext 24), TELEX 2-3453

PLANT WANTED

WE WILL PURCHASE

Modern quality Machine Tools for cash.
Whole plants or individual items. Full details

to:—

HARRY KIRK ENGINEERING, Ltd
Machine Tool Division,
Brandon Road Works,
Brandon Road, Coventry.

Telephone: Walsgrave-on-Sowe 2253/6.

WANTED!

GOOD CLASS MACHINE TOOLS POWER PRESSES & SHEET METAL MACHINERY

EDWIN MILLEN & SONS LTD.

70 Clerkenwell Road, London E.C. 1 'Phone: CLErkenwell 6064 Wanted Urgently

Late Type Machine Tools

Best Prices are offered for latest types of Machine Tools. Send us details of what you have and our representative will call to inspect.

J. B. MACHINE TOOL CO. LTD. 312 BRADFORD ST., BIRMINGHAM 5 Telephone: MIDIand 4375

Wanted. Kick Presses Various sizes. Must be in good condition. State size and stroke.—THE TOWER ENGINEER-ING NORTHANTS LTD., Prince Street, Earls Barton, Northants.

Machine Tools, Power Presses, and Sheet Metal Machinery. Single machine or complete plant purchased. Immediate Inspection.—ALBERT EDWARDS (MACHINERY), LTD., 79/89, Pentonville Road, London, N.1.



USED MACHINE TOOLS

We offer generous prices for your plant of accept in part exchange for modern equipment

E-H-JONES (MACHINE TOOLS) LTD

48, HIGH STREET, EDGWARE

Telephone: EDGware 4488 Midland 5593 - Birmingham

Classified Advertisements (PLANT WANTED, contd.)

A. LAWRENCE & CO. (MACHINE TOOLS) LTD.

will be pleased to purchase your surplus Modern Machine Tools either on a cash or part exchange basis. Ask our representative to call and inspect.

Welsh Harp, Edgware Road, London, N.W.2

Telephone: GLAdstone 0033

WANTED

All types of modern



Chipping Sodbury 3311

NEWMAN INDUSTRIES LIMITED
YATE BRISTOL

Selling Machine Tools?

Hou get the RIGHT
price from...

GATE

HEAVY
DUTY

MACHINES

GATE MACHINERY CO.LTD

172-178 Victoria Road, Acton, London, W.I Tel: Acorn 8881/2 (7 lines) Telex: 21111

WANTED GOOD

Offer your Surplus Tools to us. We pay a good price.

M. WARD

(MACHINE TOOLS) LTD. I, KILBURN HIGH ROAD, LONDON, N.W.6.

Telephone: MAIDA VALE 1195-96.

Telegrams: Emwarneer, Kilb., London
One minute from Kilburn Park Station,
Bakerloo Railway.

JONES BROS.

VALUE SCRAP PROMPTLY
PAY FOR IT IN CASH
COLLECT IT RELIABLY
NEED IT URGENTLY

FOR TOP PRICES
CONTACT:
JONES BROS.

(Metal Merchants) Ltd.
DUDDEN HILL LANE,
NEASDEN, N.W.10
Tel DOLlis Hill 6999/5999

We require Index OR 12 serial No. 8400 or later and Index ON 12 Serial No. 6000 or later. Phone price etc. to Cobham (Surrey) 3301.

EXTRA .

GOOD PRICES

offered for quality second-hand

MACHINE TOOLS

Inspection arranged quickly

Modern Machine Tools Ltd., P.O. BOX 84, GOSFORD ST., COVENTRY, Telephone: Carenty 28/12/6



WE ARE KEEN BUYERS OF GOOD MODERN MACHINE TOOLS. INSPECTION WILL BE ARRANGED AT ONCE.

M. C. LAYTON LTD.

Abbey Wharf,
MOUNT PLEASANT
ALPERTON, MIDDLESEX
Telephone: WEMbley 9641-8

DOUGLAS

OF HIGH WYCOMBE

We Specialize in the Purchase of

USED "BRITAN" REPETITION LATHES

- * Highest Prices Paid.
- * Cash or Part Exchange Basis.
- * Inspection Arranged at Once.
- A. DOUGLAS CO. LTD.
 LINCOLN ROAD,
 HIGH WYCOMBE,
 BUCKS.

Tel: H.W. 4390 (5 lines)

Power Presses, Power Guillotines, Sheet Metal Machinery, urgently required.—STANCROFT, LIMITED, Lancaster St., Birmingham, 4. Aston Cross 3741 or 2236.

CENTAUR TOOL WORKS
Birmingham, 18, pay best prices for good
modern secondhand Machine Tools by first-class
makers. Write or phone and our representative
will call.—'Phone EDGBASTON 1118 and 1119.
'Grams: Capetan, Birmingham.

Albert Edwards

(MACHINERY) LTD.,

79/89 PENTONVILLE ROAD LONDON, N.I.

Telephone: TERminus 0167/8/9

We are buyers of good modern machine tools

SURPLUS MACHINE

OFFER YOUR MACHINES TO

J. E. RAISTRICK LTD.

POYLE TRADING ESTATE COLNBROOK, SLOUGH, BUCKS.

REQUIRED

TEL: COLNBROOK 2421

TOOLS

WHETHER BUYING OR SELLING **USED MACHINE TOOLS**

Contact: K.E.N.T. MACHINERY & ENG. CO.,

Datchelor Place Mews, London, S.E.S. Telephone: ROD 4149

WANTED MODERN MACHINE TOOLS

We pay cash for single machines or complete plants

SEND US DETAILS IMMEDIATE INSPECTION ARRANGED

SOUTHERN ENGINEERING AND MACHINERY CO.

CONNAUGHT RUILDINGS TANNERS BROOK, MILLBROOK, SOUTHAMPTON Telephone: Southampton 73101/2/3

B.G. MACHINERY, LTD.,
Montgomery Street, Sparkbrook,
Birmingham, 11, will pay good prices for
Machine Tools of first-class make and in good
condition. 'Phone: VICtoria 2351/9.

Wanted, Brown & Sharpe and C.V.A.8 Single Spindle Automatics.— MELBOURNE ENGINEERING CO., LTD., Melbourne, Derbyshire. 'Phone: Melbourne 232.

Surplus Machine Tools and Sheet Metal Machinery of modern design wanted by—H. BELL (MACHINE TOOLS), Ltd., Walter Street, Leeds, 4. Tel.: 63-7398.

11in. B.S.A. Auto Wanted.— ROLLS TOOLS, LTD., 154/6, Blackfriars Road, London, S.E.1. WATerloo 3131.

WANTED

Good Class Used MACHINE TOOLS

Write or phone

STANCROFT

BEDWORTH ROAD. COVENTRY

Telephone: Coventry 88072

Wanted. 1\(\frac{1}{2}\)in., 1\(\frac{3}{2}\)in., 2\(\frac{1}{2}\)in. Wickman Bar and 6in. Chucking Autonospection.—ROLLS TOULS, LTD., No. 1
Factory, Pyrford, Woking, Surrey. Byfiest
42522.

Longford Machine Tool Co., Ltd., Longford Road, Coventry, will pay good prices for any type of machine tool which is in good condition, and is of first class make. Only machines motorised 400/3/50 will be considered —Write or 'phone Coventry 87481/2.

Automatic Required, in. cap-acity. Single Spindle turret or Swiss type. Motorised. Repairs not objected to.—AUTO TOOLS, 175, Aston Road, Birmingham, 6. Tel: Aston Cross 201.

Wanted to Purchase, New Cylindrical grinding machine, length between centres 100-150 M.M. Also new Crowthorn or similar heavy duty lathe admitting between centres 18ft. 0in.—BOX D435, MACHINERY, Clifton House, Euston Road, N.W.1.

PLANT FOR SALE

HENRY BUTCHER & CO.

VALUATION AND SALE OF FACTORIES, PLANT AND MACHINERY 73 CHANCERY LANE, LONDON, W.C.2

TEL.: HOLBORN 8411 (8 lines) GRAMS: PENETRANCY, HOLB., LONDON

Wickman 5in. Patent Chucking auto with 5 air chucks. Late type in excellent condition.—BOX D434. MACHINEBY. | Delapena Induction 2 and 6 kVA. | For Sale. Covmac Forging 2 and 6 kVA. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Euston Road, N.W.1. | For further details apply C. Dodman, RALEIGH Clifton House, Raleigh Clifton House, Raleigh Clifton House, Raleigh Clifton House, Raleigh Cli

machine tools RING BELL

LEONARD ROTH

ST., KINGSLAND HIGH ST., DALSTON JUNCTION, LONDON, E.S

TERMS ARRANGED Tel.: CLIssoid 0513/4.

ALBA 18in. Shaper. £175.

WARD No. 7 Combination Turret Lathe, 12in. 3-jaw chuck. £425.

WILSON 7 in, Centre Lathe, 3 and 4 jaw chucks, faceplate, electric suds pump, etc.

COLCHESTER Student, 3 and 4-jaw chucks,

faceplate, suds pump. £395.

CARDIFF 17in. Lathe. 4ft between centres.

3 and 4-jaw chucks, 24in. faceplate, etc. £850.

etc. £850.
LITTLE-JOHN 5in. Lathe, 5in. 3-jaw chuck,
9 collets with drawbar. £145.
FORTIS 6\(\frac{1}{2}\)in. Bench Lathe on stand,
Norton gearbox, 3-jaw chuck, faceplate,

Norton gearbox, 3-jaw chuck, faceplate, etc. £75.

HENDY NORTON 8in. Lathe, 3 and 4-jaw chucks, belt drive, faceplate. £75.

C.Y.A. Centre Lathe, 4in. capacity, with 12 collets. £55.

LANDIS Plain Cylindrical Grinder, 18in. × 7in., power feeds, electric suds. £155.

LANDIS Plain Cylindrical Grinder, 24in. × 73in. £155.

ANDUS Pisin Cymaricsi Grinder, 28in. X 7 in. 5125.e Grinder, 39in. X 8 in. table, power feeds. £295. GLARESON Tool and Cutter Grinder. £85. STEEL 14 kVA Spot Welder. £45. JOHN HANDS 28 Ton Power Press, 1 in. stroke. £185.

ALL MACHINES MOTORISED
400/8/50.

Lorenz Gear Shaper. Model 8,0,0, Capacity 74in. PD × 2in. face. Motorised.—WILCOX & CO., Barr Street, Birmingham 19. NORthern 1234/5.

Cincinnati No. 3 Dial-type Horizontal Plain Milling Machine.—HI KIRK (MACHINE TOOLS), LTD., Bristol. Tel.: Chipping Sodbury 3081. HENRY

SELECTED MACHINES

CINCINNATI No. 1-18 Plain Automatic Milling Machine. Model EA. Speed range 50 to 1,500 r.p.m. Feed range in to 24in. per min. Complete with all pick-off gears and standard equipment. Serial No. 0,5708-14. 1959. In first class condition.

WARD No. 7 Capstan. Chucking Machine. Speed range 27 to 750 r.p.m. Power feeds to saddle and turret. Some turret tooling. WARD 2A. Capstan. Air-operated collet chuck. Bar feed, 2-speed motor giving apped range 48 to 2,040 r.p.m. Power feed to turret. Elec. coolant. Quantity of collets.

feed to turret. Efec. coolant. Quantity of collets.

BRYANT No. 5 Internal Grinder. Fully Automatic, max. grinding travel 2 jin., bore range jin. to 2 in. Max. angle of taper 30 deg. Excellent condition.

BROWN & SHARPE No. 10 Plain Cylindrical Grinder. Capacity 6 in. x 18 in. Hydraulic table feeds with plunge cut. Oscillating motion to grinding wheel. Excellent condition.

All machines motorised 415/8/50.

A. LAWRENCE & CO. (MACHINE TOOLS) LTD.,

WELSH HARP, EDGWARE ROAD, LONDON, N.W.2. Tel.: GLA. 0083

TRY LIBERTY 6644 FOR YOUR MACHINES

Our stock includes Myford MG12 Grinders, Eagle Surface Grinders, Myford Grinders, tages surrace Grinders, hylorod Lathes, Boxford AUD 4jin. Lathes, Willison 6jin. Lathes, Pacera Drilling Machines from jin. to 1jin. capacity, Startrite Bandsaws, Kennedy, Rapider and Q. & S. Hacksaw Machines, Center Milling Machines, 18in. Alba Shapers, Vices and Rotary Tables of all types.

LIBERTY ENGINEERING SUPPLIES

Colliers Wood High Street, S.W.19

Radial Drills

Asquith, 4ft., No. 4 M.T.
Asquith, 6ft. No. 6 M.T. 200/350 r.p.m.
LATHES
Wilson 12in. centres S.S. & S.C. Lathe, 12ft.

between.

between.
Capstan Lathe, Morey, SG, 1in. × 64in. bar
capacity, 6 tool, 7in. centres.
Coulthurst Heavy Duty, 94in. centres, S. &
S. 2in. hollow spindle, 21in. between centres.
Mitchell 9in. centres, S.S. & S.C. 6f., gap bed.
Barber 54in. centres, S.S. & S.C. 2 way tool
post, 21in. between centres S.S. & S.C., 36in. between.
A.C.E. 74in. centres S.S. & S.C., 36in. between.
4.2bn. between centres, 7in. centres S.S. & S.C., 42bn.

between centres.

D WATKINS (ENGINEERING), LTD.
ord, Glos. 'Phone: Coleford 2271 (5 lines). 42m. b

WIDDOWSONS

ALFRED HERBERT No.9a.

Heavy Duty Combination Turret Lathe. 201in. swing over bed, spindle speeds II to 809 r.p.m., well equipped.

CINCINNATI. Hydromatic Model 56-72

Hydraulic Plain Horizontal Production Milling Machine. Table 103in. by 26in., Spindle speeds 24 to 179 r.p.m.

REINECKER Model SSM.3.

External and Internal Spur Gear Shaping Machine, 2.d.p., by 120in. external dia., max. stroke 64in.

UNION BFT. 63

Horizontal Boring and Facing Machine 21in. dia. Spindle speeds 4 to 1,400 r.p.m. Excellent condition.

HERBERT WIDDOWSON & SONS LIMITED

Canal Street Works, Nottingham · Telephone: 51891 (4 lines) MEMBER OF B.A.M.T.M.

Classified Advertisements (PLANT FOR SALE, contd.)

ALLEN EYRE & COMPANY LIMITED

NEW MACHINE TOOLS FROM STOCK

RUSHWORTH 8ft. × \$in. All Steel Guillotine, 400/440 volts.

GRANOR 13in. Centre × 7ft. 6in. between M.L. Lathe, 400/440 volts.

BIRFIELD Somus ZIII Milling Machine. 400/440 volts.

CENTEC 2B Milling Machine, 400/440 volts.

CARDIFF 84in. × 48in. Senior Lathe, 400/440 voles

STAFFA Motorised 4in. Tube Bender, 400/440 volts.

NEW MACHINE TOOLS **DUE SHORTLY**

HARRISON 13in, Swing Lathe, 400/440 JANUARY, 1962. volts.

8in. MITCHELL × 9ft. bed, 400/440 FEBRUARY, 1962. volts.

VICTORIA U2 Rapidmil, 400/440 volts. MARCH, 1962.

COLCHESTER 'Student', 400/440 MARCH. 1962.

COLCHESTER 'Triumph' 400/440 MARCH, 1962.

COLCHESTER 'Mascot', 400/440 APRIL. 1962.

COLCHESTER 'Chipmaster', 400/440 MAY, 1962.

ALLAN EYRE & COMPANY LIMITED

Chatsworth Road, Chesterfield Telephone: Chesterfield 3287, 4 lines.

19/21 Woodstock Road, Oxford. Telephone: Oxford 57318.

22 Millgate, Newark Telephone: Newark 3131.

The "Coxeter" Revolving Centre from 70s. All sizes from stock. REVOLVING CENTRES, LTD., Oxford.

Wickman 4mm. Sliding Head Automatics, three off, for sale. Hardening treatment equipment, complete, for sale, comprising 1 gas numbe (Incandescent Heat Co.), i.d. 12h. deep. 9in. wide × 9in. high. Salt bath and Fyrometer (Gibbons, Askan, Bham), oil quench tank. Frice 260.

FUTTERS (LONDON) LDHTED,

Manor Works,

16, Acton Lane, London, N.W.10.

'Phone: ELGar 5000.

Choose from

HUNDREDS of MACHINE TOOLS

at the

FIE MACHINE CENTRE

Islington Park Street, London N.1. (on the A1, near Highbury Corner)

> Cash or monthly account, hire purchase, or by the FJE Machine Hire Plan

F. J. EDWARDS LIMITED 359-361 Euston Rd. London N.W.1

Murad 1A Capstan Lathe, 1in., 2250; Timbrell & Wright 1in. Capstan, £95; Denbigh Miller, 34in. × 10in. with Vert. Head and Sadi drive, £95; Churchill 6in×30in. Plain Grinder, motorised, £85; No. 3 Fly Press, £17; Ames 44in. Plain Lathe (Collet). £25; Holbrook 64in. Gap Bed Lathe, £150. BARRATTS PARK, Heathfield. Sussex. Phone: Heathfield 2828.



HAVE AVAILABLE FOR EARLY DELIVERY

NEWALL / KEIGHLEY ' L ' 12 by 24 External Grinder, com-plete with built in Wheel Dressing Compensating Valve.

MILWAUKEE Vertical Milling Machine, Model 'H' 5ft. 3in. by 1ft. 3in.

HEALD 72A Internal Grinder. NEWALL 836 Thread Grinder.

NEWALL 10-U Lapping Machine.

No. 16 BLANCHARD Surface Grinder.

All ex used stock

THE

USED MACHINE DIVISION OUNDLE ROAD ORTON LONGUEVILLE

PETERBOROUGH

Telephone: Peterborough 67116/7



New & Used Machine Tools

CENTRE LATHES
SWISTEN 5in. x 2ft. between.
SOUTHBEND 16in. swing x 7ft.
between centres; chucks, coller and
taper turning attachments, etc.
PROGRESS 7in. gap bed A.G.H. Centre
Lathe. 2 available.

CAPSTAN LATHES
HASSE & WREDE Model 3-5651 Comb.
Turret, 1st class condition. Turret, 1st class condition.
MOREY Model 2D Capstan.

MILLING MACHINES
VICTORIA Model MI, Hori, Mill,
ARCHDALE Hori, Mill, 38in, × 10in.

REINECKER Vertical Mill, swivel head, 42in. × 13in. w/s table, p/f all ways. GRINDING MACHINES SCRIVENER No. 2 Centreless. Re-cond. KAESER Hydraulic Surface Grinder, with

24in. × Bin. mag. chuck, coolant, etc.
CHURCHILL No. I Planetary Internal
Cylinder Grinder.

PRESSES AND FOLDERS
CRAIG & DONALD, 1,000 Ton Mechanical Press Brake. Capacity 8fc. 6in. X
Iin., 60 h.p. main drive, air op. clutch,
SAMUEL GRIFFITHS 150 Ton Eccentric

Power Press, 6in. stroke, air balanced ram, 60in. × 28in. table.

HUMPHRIES 80 Ton Open Fronted
Power Press, toggle action, inclinable
adjustable stroke, 80 s.p.m., 30in. ×

26in. table.

PRIMON 4 Ton Eccentric Power Press, adj. stroke jin. to ljin. with single roll feed.

6 Ton Crank Press, open fronted.

New RATZER 12 Ton Power Press, adj.

stroke.

RHODES 6ft. 6in. Heavy Duty Universal
Swing Beam Folder.

MISCELLANEOUS
G. A. GRAY Double Column Planing
Machine, 12ft. × 4ft. × 4ft. capacity,
2 toolboxes on cross rail.
OSTER Screwing Machine, 2in. gas max.
J. & S. Sensitive Tapping Machine.
RADIAL DRILL 3ft. 6ins. low base, loose
how table floor mounted motors.

box table, floor mounted motor. There are many more at

STRAIGHT & VINES LTD., MINT STREET, BOROUGH, LONDON, S.E.I

Telephone: HOP 4364



NEW S.S. & S.C. LATHES FROM SHEFFIELD STOOK.
W. & M. Series 85 10½in. centres, gap bed, admits 6ft. 0in. between centres.
MITCHELL OF HALLFAX 8¼in. centres, gap bed, admits 6ft. 0in. between centres.
WILLSON 7¼in. centres, gap bed, admits 2ft. 8in.

between centres.

SMART & BROWN 1024 6in. centres, Precision
Toolroom Lathe, admits 2ft. 0in. between

centres.

RAGLAN 5in. centres, flat bed, admits 2ft. 0in. between centres. hat bed, admits 21t. 0lh.
All with electrical equipment for 400-440/3/50
cycles supply.

THO! W. WARD LTD. ALBION WORKS . SHEFFIELD

'Phone 26311. Ext. 345.

Remember - WARDS might have it!

AVAILABLE FROM STOCK AUTOMATICS

FOOTBURT lin.
B.S.A. ACME GRIDLEY §in. 6 spindle.
Rebuilt machine.
CONOMATIC lin. 4 and 6 spindle.
Rebuilt machines.
RYDERMATIC No. 12 Vertical Multi-

RADIAL DRILLS

KITCHEN & WADE 8ft. low base, with loose box table.

GRINDERS

BLANCHARD No. 16 Vertical Spindle, 26in. dia. magnetic table.

26in. dia. magnetic table.

PALLAS No. 2 Surface, 18in. × 6in.
New ALPA Surface 32 × 8in.
JUNG AS Internal.

KEIGHLEY Type XL Hydraulic Plain
Grinder, 6in. × 18in.

CHURCHILL 10in. × 24in. Universal.

LANDIS 12 × 48 Universal.

BROWN & SHARPE No. 3 Universal.

CAPSTAN AND TURRET LATHES

MURAD 3Q ‡in. Capstan. LIECHTI PR Turret Lathe (Swiss) GISHOLT Turret Lathes. Type I FOSTER No. 2B Turret Lathe.

CENTRE LATHES

HENDEY 6in. × 30in. Taper Turning. MONDIALE 7in. × 60in. Gap Bed.

MILLERS

MILLERS

RICHMOND OI Universal.

ADCOCK & SHIPLEY Model OA with

"Multiform" Auto feed. Rebuilt.

WERNER No. 5160 Small Multipurpose.

Vert. and Horiz. Table 22in. 'x 6½in.

ARCHDALE 14in. Manufacturing type.

CINCINNATI Type OK, 18in. Horiz.

EDGWICK 18in. Horizontal.

ARCHDALE 20in. Twin Overarm Horizontal.

ARCHDALE 20in. Twin Overarm Horizontal.

ARCHDALE 20in. Twin Overarm Horizontal.

CINCINNATI 3-24 Plain Hydromatic.

CINCINNATI 3-24 Plain Hydromatic.

CINCINNATI 3-24 Plain Hydromatic.

CINCINNATI 3-24 Plain Hydromatic.

CINCINNATI 3-24 Duplex Hydromatic.

CINCINNATI 3-4 Duplex Hydromatic.

CINCINNATI 3-4 Duplex Hydromatic. New TAYLOR VERTICAL, TABLE TRAINS X 54in.
ARCHDALE I2in. Vertical.
HERBERT No. 10 Vertical.
BROWN & SHARPE No. 2 Vertical Mill.
Table 49in. x 14in.
MAS FV2A Vertical Mill. Table 52in. x

HERBERT 23V Vert. Table 68in. × 17in.

48in. traverse. HELLER Automatic Thread Millers (4). ASQUITH HKO Duplex Keyseater.

PRESS

V. & O. No. 11 Double Action. Approx. 10 tons. Roll feed. Max. draw lin.

MISCELLANEOUS

NOBLE & LUND 11/16in. Fluifeed Cold Saw, fitted with pneumatic vice for tubes.
RICHMOND 4in. Light Duty Slotter.
New ALBA 18in. Shaper.

All machines motorised 400/3/50 unless otherwise stated.

ACBARS LIMITED, 331-3 WALWORTH ROAD, LONDON S.E.17

Telephone: RODney 7822
Telegrams: Acfirb London S.E.17 mmmmmm

A Good Number of High-Class Machine Tools always in stock. At ELLISON (SALFORD), LTD., Cook Street, off Chapel Street, Salford, 3, Lancs.

THE SPOT TO WATCH!

FOR GOOD CLASS SECONDHAND MACHINES AT LOW COST

C.V.A. No. 8 Automatics.
C.V.A. No. 12 Automatic.
B.S.A. No. 48 Automatic.
MODERN 13in. Automatic.
LAPOINTE Screw Broaching Machine 54in.
WARD 'OF 'Capstans.
HERBERT No. 0 Capstan.
HERBERT 15 Capstan.
CORONA 4 5p. Drill.
HERBERT 3 5pindle Drill.
PACERA 2 Spindle Drill.
PACERA 2 Spindle Drill.
SCRIVENER I CA Centreless Grinder.
KAMENICEK Universal Grinder.
NEWALL Thread Grinder.
SOUTHERND 143in. Lathe.
LEBLOND Rapid Production Lathe.
HOGARTH Production Lathe. HOGARTH Production Lathe.
SMALLPIECE 6 W.S.L. Multi Tool Lathe.

MILWAUKEE 4H Uni. Mill,
K. & T. 5HM Vertical Mill I,300 r.p.m.
K. & T. 4H Horizontal Mill.
MANN 6tc. B.C. Threadmill.
MILWAUKEE 12in. x 18in. Simplex Mill
SENTINEL 25T Power Press.
KELLER 1210 Diesinking Machine.
THIEL Punch Shaping Machine.
WICKSTEAD 6in. Hacksaw.

LATE AMERICAN MACHINES

FELLOWS 61A High Speed Gear Shaper. GLEASON No. 16 Spiral Bevel Hypoid Gear Generator.
FELLOWS 612 High Speed Gear Shaper.
HEALD No. 22 Ring and Surface Grinder.
HEALD No. 49 Fine Hole Borer.

All machines motorised 400/440 v. 3 ph. 50 cy. unless otherwise stated.

GOOD USED MACHINE TOOLS WANTED

JONES

48 HIGH STREET. **EDGWARE, MIDDX.** PHONE EDGWARE 4488/9

78, WRENTHAM STREET, BIRMINGHAM 5, Phone Midland 5593

HERBERT No. 3S Capstan Lathe. Motor drive 400/440 volts, 3 phase. 50 cycles. Arranged for chucking.

HERBERT No. 28 Capstan Lathe. Motor drive 400/440 volts, 3 phase, 50 cycles. Arranged for chucking.

HERBERT No. 7 Junior Combination Turret Lathe. Motor drive 400/440 volts, 3 phase, 50 cycles. Arranged for chucking.

Rogery

4/6 Minerva Road, Park Royal, London, N.W.10 Telephone: ELGar 4841/4842

Asquith O.D.1. 6ft. 0in. Arm Radial Drilling Machine.

Radial Drilling Macaning
Further details from:

C. & G. OLDFIELD, LTD.,
15, Abercorn Street,
PAISLEY.

A Comprehensive Selection of Modern Machine Tools Always in stock.

WM. PARTINGTON LTD. Trafford Park Rd. Trafford Park Manchester 17

TRAFFORD PARK 0332

Excello 33 Thread Grinding machine, 1954 model, complete with equip-ment, £1,625 ex works.—K. & C. MACHINERY LTD., Stephen Street. Coventry 23669.

Fielding 50 ton Hydraulic Horizontal pipe bender, up to 6in. bore hydraulic tubes.

200 Ton Fielding Downstroke Hydraulic

Fielding 50 ton Hydraulic Horizontal pipe bender, up to 6in. bore hydraulic tubes.

200 Ton Fielding Downstroke Hydraulic Press, 14in. ram. 42in. stroke, 63in. daylight.

100 Ton Fielding ditto, 10in. ram, 72in. stroke, 99in. daylight.

Fielding 50 ton Hydraulic Horizontal Pipe Bender for 6in. thick tubes.

Bliss 90 Ton Geared Press.

Bliss 90 Ton Geared Press.

3 Bliss No. 304 Vertical Single Action Drawing Presses, 71in. stroke, 60 tons.

3 Bliss No. 304 Vertical Single Action Drawing Presses, 71in. stroke, 60 tons.

3 Windsor 6-ox. Pinstic Injection Moulder. Sedgwick 6ft. × žin. Folder.

6ft. × tin. Overcrank Guillotine.

7ft. × 1in. Craig Donald Flattening Rolls.

"Pyramid" Bending Rolls, 9ft. 0in. × žin.

200 Ton Tangve Hydraulic Straightening Press, bed 25ft. × 3ft. stroke 21in., motorised travelling table, 2 ram pump.

Hugh Smith, Double Table Scarfing Machine, 13in. fixed stroke, from 16in. to 8ft. wide, 14in., thick steel plates.

Crow. Harvey Punch. Shears and Angle Cropper, 18in. blade, 27in. throat, heavy duty.

2in. blode, 19in. 19in. planers by Massey and Alldays & Onlons, also 3-5 cwt. secondhand E.O.T. Cranes.

30 Ton Marshall Fleming, 29ft. span, cab. 25 Ton Clyde, 21ft. 9in. span, cab control.

10 Ton Heywood, 34ft. span, cab control.

10 Ton Heywood, 34ft. span, cab control.

10 Ton Horyes, 32ft. 10in. span, cab control.

10 Ton Morris, 194ft. span.

1964.

FRED WATKINS (ENGINEERING), LTD. Coleford, 26gr. 16 lines).

FRED WATKINS (ENGINEERING), LTD. Coleford, Glos. 'Phone: Coleford 2271 (5 lines)

D

7. J. Edwards Ltd

No. 12 RYDERMATIC three slide Vertical Multi-tool Lathe, maximum swing 20in., Multi-tool Lathe, maximum swing 20in., maximum length 16in., vertical silide stroke 8in., horizontal silde stroke 54in. HERBERT No. 5 Auto Chucking Lathe, swing 184in. over bed. 34in. hollow spindle.

SCREWING MACHINES
KENDALL & GENT Screwing Machine, 3in.
bolts, 6in. tubes. Tangential diehead with

leadscrew.

Machine.

OSTER 6in. capacity Screwing Machine with cutting-off attachment for pipes; fully

cutting-off attachment for pipes; fully equipped.

RENDALL & GENT 3-2 Screwing Machine, capacity 3in. pipes, 2in. botts, tangential dichead, leadscrew control.

ADDEN 2in. Screwing Machine, with Lanco LANDES 1tin. Tangential Dichead Screwing Machine.

SHAPING MACHINES

NEW 194in. Shapers.
GOULD & EBERHARDT 20in. Shaper.
BUTLEB 12in. and 18in. Shapers.
ALBA 24in., 18in., 14in. and 10in. Shapers.
ORMEROD 26in. stroke Traversing Head Shaping Machine, with two universal box tables. 1955 machine,

SLOTTING MACHINES BETTS 12in. stroke heavy duty Slotting Machine NEW 7‡in. stroke Toolroom Slotters.

TAPPING MACHINES HERBERT & in. No. 1 Flashtapper

BORING MACHINES

KITCHEN & WADE Vertical Cylinder Boring
Machine; Table 48in. × 224in.; Table traverse
36in. × 8in.; Spindle No. 5 M. P.
BULLARD 36in. Spiral Drive High Speed
Vertical Boring Mills: 12 speeds from 12 to
200 r.p.m., with side head. 1942 machines.
BULLARD 36in. Spiral Drive High Speed
Vertical Boring Mills: 12 speeds from 12 to
200 r.p.m., with side head. 3-motor type, 1942
machines.

machines.
EMTOG Jig Boring Machine, table 27in. × 11in.;
spindle No. 2 Morse Taper, 350 to 3,500 r.p.m.
WEBSTER & BENNETT 36in. Vertical Boring
Mill with Murray colour control, 6.5 to 124

r.p.m.

GIDDINGS & LEWIS No. 0 Horizontal Boring

Milling and Drilling Machine, spindle 3 in.

dia.

KEARNS Size OB Horizontal Boring Machine,
covered bed, acrew cutting motion. 2½in.
traversing spindle.

PADDON Vertical Cylinder Borer for automobile
cylinders, 2.2in. to 5.5in. dia.; boring depth
14in.

DRILLING MACHINES
NEW 3ft. Radial Drilling Machines, No. 4 Morse
Taper, swivel table, 500 r.p.m.
New TOWN 4ft. 6in. model AE4 Elevating
Arm Radial Drilling Machine. No. 5 Morse
Taper.
TOWN 8ft. Non-elevating arm Radial Drill,
with box bed, 122-790 r.p.m. No. 5 Morse

taner.

LELAND-GIFFORD 3-spindle Drilling Machine
on 4-spindle base, with 4-speed direct mounted
motors, No. 3 Morse Taper.

JONES & SHIPMAN 4in. 4-spindle Drilling

Machine, separate pole change motors.

ARCHDALE and POLLARD No. 3, 4 and 5
Morse Taper Froduction Drilling Machines.

New Heavy Duty Production Drilling Machines.

No. 5 Morse Taper; hydraulic feed to spindle

and table.

HERBERT Type C Pedestal Drilling Machine,
No. 3 Morse Taper, 230 volts, single phase.

Auto spindle feed; flange mounted motor.

GEAR SHAPING MACHINES
BARBER COLMAN 12in. Gear Hobber.
FELLOWS No. 645A3 Gear Shaper, capacity
18in. × Sin.
FELLOWS No. 6 and 612 Gear Shapers, 35in. ×

5in. capacity. FELLOWS No. 61A Gear Shaper, 18in. × 5in.

359-361, EUSTON RD., LONDON, N.W.I Telephone: EUSton 5000 Telex No. 24264

and at Lansdowne House, 41, Water St., irmingham, 3 Telephone: Central 7606-8



24in. INVICTA Model 6M Shaper.
Model O3SD RICHMOND Universal Milling
Machine with equipment 10in. Swift Gap Bed
S.S. & S.C., Lathe 10ft. between centres.
New 63 × 134in LAGUN Universal Milling
machine. Bar feeds and rapids to the table
in all directions

in all directions. 24/28 NOBLE & LUND Hydraulic Cold Saw. 12in. × 48in. between centres MONARCH 15in. LE BLOND S.S. & S.C. Lathe, Heavy

Duty. 48in. between centres.

P.24 SNOW 10in. × 24in. Hydraulic Surface
Grinder, with magnetic chuck and dust

extractor.

8½in. CARDIFF S.S. & S.C. Lathe, 48in. B.C.

8½in. CARDIFF Lathe, fitted with Hydraulic
Copying Attachment, 48in. B.C.

59in. × 16in. CRAVEN Victoria Milling

rapios. ew 10in. × 18in. GER Model 450 Hydraulic Universal Grinding Machines. iin. × 13in. CRAVEN Universal Milling

55in. × 13in. CRAVEN Universal Printing Machine.
35in. × 10in. FRITZ WERNER Production Milling Machine.
New 51in. × 11in. LAGUN Universal Milling Machine. Power feeds and rapids.
New 40in. × 11in. DIMCO Model FV2 Vertical Milling Machine. Power feeds and

rapids.
o. 2 WARNER & SWASEY Capstan Lathe. No. 2 WARNER & SYVENER Vertical Chucking.
43in. × 12in. FRITZ WERNER Vertical 43in. × 12in. Heads.

Chucking.

43in. x 12in. FRITZ WERNER

43in. x 12in. FRITZ WERNER

Miller. Swivelling head.

20in. ARCHDALE Plain Miller. Power feeds

and rapids. Spindle speeds 60-1,230 r.p.m.

20in. ARCHDALE Plain Miller. Power feed

and rapids. Spindle speeds 30-615 r.p.m.

No.3 KITCHEN & WADE Honer.

Model HBY CHURCHILL Electric Grinder.

14in. BUTLER Slotter. Power revolving table.

No. 3 RICHARDS Horizontal Borer Model

PRT3.

No. 3 KEARNS Horizontal Borer.
No. 2 KEARNS Horizontal Borer.
54in. × 15in. CRAVEN Universal Milling

HERBERT S.E. Capstan Lathe. CRAVEN Worm Milling Machines.

DIMCO (Gt. Britain) LTD. 28, WOOD LANE, SHEPHERDS BUSH, LONDON W.12 SHEpherds Bush 4401/2



METAL TRAYS or **WORK PANS** 15" × 11" × 41" @ 108/- per doz. 18" × 12" × 6" @ 121/- per

WH. HURLOCK JHR. LTD. (Estab. 1904) 5-7 Kingston Hill, Kingston-on-Thames Surrey. KIN 4526-7-8 Surrey.

NEW RICHMOND NO. 3 **VERTICAL MILLING MACHINE**

table 48in, by I lin, with quick power traverse Immediate delivery

P. SIMPSON & CO. LTD., 177 Raikes Lane, Birstall near Leeds

Telephone Batley 1235

Cashmores

Selections of Machine Tools from Stock or Early Delivery

DRILLING MACHINES

KITCHEN & WADE 6ft. Girder Type Radial
Drilling machine, 18 spindle speeds, 6 feeds,
No. 5 M.T. spindle.

PROGRESS 4E Pillar Drilling Machine, No. 3
M.T. spindle.

M.T. spindle.

BORING MACHINE

ASQUITH Floor Type Horizontal Borer, 3in.
diameter travelling spindle, swivelling column
with 6ft. × 5ft. tee-slotted bedplate.

SLOTTING MACHINE

ORMEROD 12in. stroke Slotting Machine,
27in. dia. rotary table.

LATHES
LANG 20in, swing Surfacing and Boring Lathe LANG 20in, swing Surfacing and Boring Lathe with hexagon turret.

OLICHESTER \$\frac{1}{2}\text{in}\text{. Mascot \$8.8. & S.C. Gap.}

Bed Lathes, to admit 6ft. 6in. between centres.

MITCHELL OF KEIGHLEY \$\frac{1}{2}\text{in}\text{. \$8. & S.C.}

Gap Bed Lathe, to admit 7ft. 3in. between

MILLING MACHINES
CINCINNATI Model 1/18in. Production Milling
Machine, table 35 in. × 10in., with automatic

CINCINNATI Model 1/18in. Production Milling Machine. 1985; in. × 10in., with automatic feed cycle.

87. ANDRE Horizontal type Heavy Duty Plain Milling Machine, table size 73in. × 164in. HERBERT 46V Vertical Milling Machine, working surface of table 58in. × 15in., power feed to table in all directions, longitudinal traverse 36in., motorised 400/3/50 supply.

6.V.A. "Kearney & Trecker" model 2E Dia. Type Horizontal Plain Drilling Machine, working surface of table 41in. × 12in., longitudinal feed 29in., cross feed 12in., 8 spindle speeds 25/1,000 r.p.m.

CINCINNATI Model 3/36 Hydromatic Milling Machine, table 54in. × 14in.

BROACHING MACHINE

CINCINNATI 10 ton Vert. Single Ram Hydraulic Surface Broaching Machine, 66in. stroke. 20in. × 20in. table.

COVEL No. 12 Tool and Cutter Grinding Machine, with face milling attachment, swing Machine, with face milling attachment. NOBTON 18in. × 6in. Hydraulic Horizontal Spindle Surface Grinding Machine.

NOBTON 18in. × 6in. Hydraulic Horizontal Spindle Surface Grinding Machine, with hydraulic Horizontal Spindle Surface Grinding Machine, with 14in. × 6in. magnetic chuck CHURCHLI 16in. × 36in. Model PRH Universal Grinding Machine, with hydraulic feed and internal grinding internal grinding attachment.

HLL 60in. × 24in. Horizontal Spindle Heavy Duty Surface Grinding Machine, with hydraulic feed and internal grinding statchment.

HLL 60in. × 24in. Horizontal Spindle Heavy Duty Surface Grinding Machine, with hydraulic feed and internal grinding attachment.

HLL 60in. × 24in. Horizontal Spindle Heavy Duty Surface Grinding Machine, with hydraulic feed and internal grinding attachment.

PLANING MACHINE
STIRK 12ft. × 4ft. × 4ft. PIONEER all electric
Planing Machine, four toolboxes, pendant
control, Stirk split field drive, input 400/3/50

POWER PRESSES
H.M.E. 100 tons Geared Rigid Power Press
with adjustable stroke 1ln. to 6in.
New BUTTERLEY No. 4 20 Ton Ungeared
Power Press, 1ln. 3in. adjustable stroke.

NOBLE & LUND 11/16in. Cold Circular Sawing Machine, with hydraulic vice, capacity 5in. diameter rounds, 4\frac{1}{2}in. squares, 9in. \times 3\frac{1}{2}in.

beams.

SCREWING MACHINE
KENDALL & GENT 3-2 Tangential Head
Screwing Machine, to screw boits up to 2in,
outside diameter, tubes up to 3in, inside
diameter, machine fitted with leadscrew. SHAPING MACHINES HERBERT 20in, stroke Shaping Machine,

6 ram speeds.

ORMEROD 18in. stroke Shaping Machine.

9 ram speeds.

MISCELLANEOUS
CLYDE 10 ton Overhead Electric Travelling
Crane, 52ft. 3in. span. All the above machines are motorised 400-440/3/50 cycles

JOHN CASHMORE LTD. GREAT BRIDGE, STAFFS. Tel.: Tipton,2181/7.
(Also at NEWPORT, MON.)

MIDDOMSORS

WARD No. 13 Combination Turret Lathe, covered bed, 25in. concentric chuck, 27in. 4-jaw independent chuck. Good turret tooling, taper turning attachment, 35 h.p. mottor, 400/3/50. Modern machine. Excellent equipment.

ALFRED HERBERT No. 9a Heavy Duty Comibnation Turret Lathe, 20½in. swing over bed, with taper turning attachment, spindle speeds 11 to 809 r.p.m., covered bed, well equipped.

CHURCHILL Model VB Slideway Grinding Machine, 72in. × 34in. × 36in. Excellent condition.

CINCINNATI Model 4HP Heavy Duty Vertical Milling Machine. Table 72in. × 19in., speeds 17 to 480 r.p.m.

CINCINNATI Hydromatic 56-72 Hydraulic Plain Horizontal Production Milling Machine, table 103in. × 26in., speeds 24 to 179 r.p.m

KAESER (Swiss) Hydraulic Plain Cylindrica Grinding Machine. Two machines available: Capacity 6in. × 36in. and 10in. × 20in Both in excellent condition.

DEMM Model S 18-750 Gear Shaping Machine

REINECKER Model SSM3 10ft. Heavy Duty External and Internal Spur Gear Shaping Machine. 64in. face width.

LANG 8fin. S.S. & S.C. Centre Lathe, 5in. between centres, with taper turning attachment, spindle speeds 19 to 900.

OLDFIELD & SCHOFIELD 32in. Swing Gap Bed S.S. & S.C. Lathe, 10ft. between centres, swing in gap 50in. × 16in. Taper turning attachment.

MITCHELL 84in. Centres Gap Bed S.S. & S.C. Lathe. Several available. All As New. 52in., 54in., and 64in. between centres.

PENSOTTI Model KTV1050 Turret Type. Single Column Vertical Boring and Turning Mill, with sidehead. To swing 43in. dia. admit 32in. under cross slides, 20 h.p. motor

JONES & SHIPMAN Model 921 Heavy Duty Pillar Drilling and Tapping Machine. No. 5 M.T.

ORMEROD 20in. Stroke Pedestal Type Shaping Machine, 9 speeds 9 to 104 s.p.m., 5 h.p. motor. Two machines available.

MASSEY 2-cwt. Pneumatic Power Hammers 14in. stroke, 200 blows per minute, 10 h.p.

RHODES 120 ton Double Sided Single Crank, Geared Power Press. 50 strokes per min. 2½in. stroke, 4½in. adjustment. Bed 30in. × 22in. Excellent condition.

HERBERT

WIDDOWSON

& SONS LTD.

CANAL STREET, NOTTINGHAM

'Phone: 51891

G. A. ROBINSON (STOKE-ON-TRENT) LTD.,

HARTSHILL, STOKE-ON-TRENT, STAFFORDSHIRE Tel.: Newcastle (Staffs.) 64771 (5 lines),

> COVENTRY BRANCH: 14/16, Queen Victoria Road, Tel. Coventry 25418 and 26221.

USED AND RECONDITIONED MACHINE TOOLS AT BARGAIN PRICES

SCRIVEN H/D 8ft. × \$in. Plate Guillotine PALLAS Universal Miller, U2, 40in. × 10in All geared, power traverse all round.

HERBERT 2-spindle. All-geared head on 3-spindle pedestal base, table 36in. × 15in. Fitted No. 3 quick change chucks. Spindle speeds 104-562.

RHODES Press Brake, 8ft. × lin., motorised, undercranked.

BESCO 75 ton D/Sided Inclinable, 4½in. stroke, motorised, fitted with Udal guards, platen 27in. × 27in.

CINCINNATI 1/18 Manufacturing Miller, 1,500 r.p.m., with backlash eliminator.

MILWAUKEE No. 4 Horizontal 1,000 r.p.m.

CINCINNATI Plain Grinder, 10in. × 36in. Model "ER" (AS NEW), Late 1957. REED PRENTICE Toolroom Lathe, 10in. centres × 78in. between centres.

DEAN, SMITH & GRACE 6in. Centre Lathes, taper turning, full equipment. TOWN Radial Drilling and Tapping

TOWN Radial Drilling and Tapping Machine, 6ft. arm rise and fall, tee slotted, low base, No. 5 Morse taper. RICHMOND 0.3 Plain Miller.

ARCHDALE Column Drill, compound table, No. 5 Morse.

COVELL Hydraulic Surface Grinder, 24in.×8in.

2 off CLEYELAND single spindle autos, 2\(\frac{1}{2}\)in, cap, complete with all equipment,
 1 off GRIDLEY 4 spindle auto, with equipment.

ment.
2 off HERBERT preoptive head No. 4 Senior Capstans, fully equipped.

1 off ARCHDALE 4 spindle drillers, 3 spindle 2 M.T., 4 spindle 3 M.T. with power D/F. WILSON 8in, Centre lathe × 72in, B/C full

equipment.

1 off BROWN & SHARPE No. 13 Universal Tool and Cutter Grinders, complete with equipment.

of 2D HERBERT Capstan Lathe, 16 spindle speeds 50-2,550, complete with Ball Collet Chuck. Full set Collets 4 way 7/P, rear T/P. Turret equipment, Pump Tank and Fittings.

2 off 2A WARD Capstan Lathes, spindle speeds 71-1,531 r.p.m., arranged chucking 9in. 3-jaw chuck. Pump tank and fittings.

LANDIS Camshaft Grinder, 5in. × 60in. Hydraulic Motion Automatic, sizing and wheel dressing attachment. First class order.

LANDIS Hydraulic Crankshaft Profile Web Grinder Automatic Setting and Grinding Contour attachment. First class order. ARCHDALE 4-spindle Pillar Drill.

SNOW Hydraulic Surface Grinder, 8in. × 24in.

ABWOOD Vertical Spindle Surface Grinder, 18in. × 6in., complete magnetic chuck.

ROBOT 18 × 6 Surface Grinder, Auto traverse magnetic chuck.

LANDIS 10in. × 72in. Plain Hydraulic Grinder.

THESE MACHINES CAN BE INSPECTED AT ANY NORMAL BUSINESS HOURS AT OUR STOKE-ON-TRENT BRANCH.

ELLIOTT INVITES YOU

to visit the

Elliott Machine Tool Exhibition at Willesden—11 - 15th December.

B. ELLIOTT (MACHINERY) LTD
VICTORIA WORKS, LONDON, N.W.10
Tol. ELGAR 4050

Automatic Dial Feed. Suitable for Taylor & Challen B3 Press. 20in. dia. dial with 10 stations.—WILCOX & CO., Barr Street, Birmingham, 19. NORthern 1234/5.

Workpans, Worktrays. Our Special Heavy Gauge. Size 16in. × 14in. × 15in. Pan. forged handles, marvellous value, 8s. 9d. each. Order from BURTONS WORKS, Astley, Shrewsbury. Telephone: Shawbury 266.

Peterman No. 1 and No. 2 Gear Cutters. Motorised.—WILCOX & CO., Barr Street, Birmingham 19. NORthern 1234/5.

Coventry Climax Forklift Trucks.
Diesel and petrol models. 6ft. to 12ft.
lifts. 2,000 lb. to 6,000 lb. capscity. Details
and photographs available. Part exchanges
arranged.—SFEED ELECTRICS, Church Street,
Basford, Nottingham. Tel. 75716.

NEW MACHINES FOR IMMEDIATE DELIVERY

VOLMAN Gear Shapers and Hobbing Machines. Capacity 7₹in.—49in. dia.

WEYDEMANN & HASSEL-KUS Cutter Grinding Machine. Max. cutter dia. 16in.

TOS FEK 80 Cam Miller for peripheral, face and cylindrical cams by mechanical copying from templates.

BEICHLE Models WF.1 & WF.2
Die Milling Machines. Capacities: 20in. × 18in. × 10in. and 25in. × 20in. × 12in. These machines are ideal for producing the simpler moulds and dies.

OPUS 120 Metal Filing and Sawing Machine. Table Ilin. by Ilin. Max. thickness of workpiece 2\(\frac{1}{2}\)in.

ELGAR MACHINE TOOL CO. LTD.

172-178 VICTORIA ROAD, ACTON, LONDON, W.3 Telephone: ACOrn 5555 (7 lines)

EDWIN MILLEN & SONS LTD.

70, CLERKENWELL ROAD LONDON, E.C.1

Tel.: CLE 6064 and 3602

BUTTERWORTH 14in. Good equip. 1958. MANURHIN TR12-16 Im. Auto. BROWN & SHARPE OG Auto. £650.

DRILLING MACHINES BRIMSDOWN. 2 Spindle, £05. PROGRESS 4E, 1 in. cap. (2). £195. CORONA 1 in. 4ft. Radial. £285. DENBIGH. 1 in. cap. £125. GRINDERS

GRINDERS

THOMPSON Hydraulic Surface, Type "F," 18in. × 6in. £750.

18in. × 6in. £750.

SCRIVENER NO. 1 Centreless. £650.

SMART & BROWN Internal. £225.

MYFORD MG9 Cylinder, with internal. £425.

VICTORIA Cyl., 4jin. × 8in. As New. £425.

EXCEL No. 2, 14in. × 6in. Surface. £385.

PALLAS 18in. × 6in. Surface. £275.

NORTON 18in. × 7in. Hyd. Cyl. £295.

NORTON 18in. × 7in. Hyd. Cyl. \$295.

CAPSTANS AND LATHES

COLCHESTER 7in. × 42in. Triumph, \$365

HERBERT No. 7 Comb. Turret. £685.

HERBERT No. 9 Comb. Turret. £685.

HERBERT No. 9 Comb. Turret. £225.

WARD 3A. B/Chuck, B/Feed. £685.

WARD 3A. B/Chuck, 2(2). £550.

WARD 2A. B/Chuck, 2(341 r.p.m. £475.

WARD 2A. B/C. B/F Tooling. As New. £750.

SMART & BROWN \$in. Model "L." B/F. £225.

ACUURATOOL \$in. Capstan. £225.

KUMA 9in. × 36in. Lathe. G.B. £195.

STUDENT 6in. × 24in. Good equip. £125.

DENIAM 44in. × 18in. Good equip. £125.

HERBERT SMALLPIECE \$in. × 24in. £850.

JOHNSTEAD 5ft. 6in. Facing Lathe. £650.

JOHNSTEAD 5ft. 6in. Facing Lathe. £650.

WILLOR 7hin. × 36in. Full equip. £225.

WARD No. 7 Capstan Lathe. £550.

MILLERS (Horis. and Vert.)

ARCHDALE DUPLEX. 45in. × 11in £350.

ADCOCK & SHIPLEY 1VM Vert. £575.

SENIOR M1. 26\fm. × 6in. £195.

SENIOR M1. 264 in. × 61n. £195.

POWER PRESSES AND SHEET METAL

MACHINES

MACHINES

MACHINES

LLISS 21. 40 Ton. 3in. stroke. £425.

BESOO 40 Ton. Adj. stroke and bed. £425.

BESOO 8 Ton. 2in. stroke. £295.

BESOO 8 Ton. AP.X. Adj. stroke. £140.

BESOO 40 Ton. Adj. stroke. £140.

BESOO 8 Ton. AP.X. Adj. stroke. \$140.

BESOO 40 Ton. Adj. stroke. \$200.

MORGAN 6ft. × 14 S.W.G. Folder. As New. £296.

£200. MIDSAW Hyspeed 36in. Fusion Cutter. £485.

MISCELLANEOUS
G. H. ALEXANDER Engraver, with rotary table,

6. B. Albasack.

§175.

ROWLAND 4in. Abrasive Cutter. £150.

THIEL Punch Shaper. As New. £575.

WICKSTEED 10in. × 10in. Powersaw. £195.

RAPHOR 8in. × 8in. Powersaw. £95.

TAYLOR 124in. Spinning Lathe. £385.

Other machines in stock

WE SELL WELCOME

EXCHANGES

WE BUY

HIRE PURCHASE ARRANGED

One Wadkin Heavy Duty Radial Arm Router L.Y.R. Power rise and fall table, in perfect condition.—Telephone: London LiBerty 7681.

Victoria 0-18in. Victomatic Prod-Miller. Table 36in. × 104in. Year 1957. Overhauled by manufacturers. £900.—J. W. LITHERLAND (M/C TOOLS). LTD., 98, Brunswick Road, London, W.5. Tel.: Perivale

Wickman lin. Six-spindle Automatic, for immediate delivery, Practically unused.—BOX D422, MACHINEBY, Clifton House, Euston Road, N.W.1, or phone: CAN 2481.



AUTOMATICS

CONOMATIC 3\(\frac{1}{2}\)in., 4-spindle Bar Auto.

BULLARD Multi-Au-Matic 7in. 8 spindle.

BULLARD Multi-Au-Matic 12in. 6 spindle.

WETZEL HORING MACHINES

WETZEL HOTZONTAL TRAVERING COlumn Floor
Boring and Facing Machine, 7in. diameter
travelling spindle, 45in. diameter facing head.
KEARNS Model OC Horizontal Boring Machine,

REARMS Model OU Horizontal Boring Machine, 3in, dia. travelling spindle. WEBSTER & BENNETT Vertical Boring Machine, table 50in, diameter. RICHARDS Type PRT Horizontal Floor Boring Machine, 3tin. travelling spindle, 28in. diameter facing head.

LATHES

DEAN, SMITH & GRACE S.S. & S.C. Gap Bed Centre Lathe, 8 in. centre height × 48in, between centres.

CAPSTAN AND CENTRE LATHES

CAPSTAN AND CENTRE LATHES
CHURCHILL-REDMAN Model 13NM Heavy
Duty S.S. & S.C. Gap Bed Centre Lathe,
18in, centre height × 72in, between centres.
Swiug in gap 50in.
OLDFIELD & SCHOFFELD Surfacing and
Boring Lathe, 104in, centre height.
WARD 7B Combination Turret Lathe.
NILES Heavy Duty Centre Lathe, S.S. & S.C.
17in, centre height × 28ft, between centres.

DRILLING MACHINES

ASQUITH Model OD.1 5ft. Elevating Arm Radia Drilling Machine. HETTNER Radial Drilling Machine, 10ft. elevating arm.

GEAR MACHINES
ORCUTT Model HM24 Hydraulic Interna Gear Grinder.
GLEASON 3in. Straight Bevel Gear Generator.

GRINDING MACHINES
NEWALL Type LA Plain Hydraulic Cylindrical
Griding Machine, 10in. × 36in. (Two available.)
CHURCHILL Model HBY Internal Grinding

Machine.
CHURCHILL Plain Cylindrical Grinding Machine. 26in. swing × 84in. between centres

(1951). ANDIS Type C Plain Hydraulic Cylindrical Grinding Machine, 6in. swing×18in, between centres.
ORCUTT Model HM24 Internal Spur Gear

ORCUTT Mouse Land Grinding Machines, CHURCHILL Plain Hydraulic Cylindrical Grinding Machine, 20in. swing × 54in.

between centres.

BROWN & SHARPE Plain Cylindrical Grinding
Machine, 10in. swing × 36in. between centres.

SCRIVENER Model 2DF Centreless Grinding

MILLING MACHINES

CINCINNATI Model 5/72 Plain Hydromatic Milling Machine, table 91in. × 22in. (1953). CINCINNATI No. 2L Plain Horisental Milling Machine, table 82in. × 10in. Machine, table 82in. × 10in. PRATT & WHITNEY Model Bl.8620 3-spindle "Keller" Die Sinking Machine. CENTEO Model SR Automatic Production Milling Machine, table 25in. × 16in.

PLANING MACHINES
BUTLER 36in, Open Side Crank Planing Machine.

MISCELLANEOUS

LANGE & GAILEN 28in. stroke Double Headed
Hydraulic Shaplag Mashine.
TAYLOR & CHALLEN Double Sided 50-ton
Geared Power Press, 10th. stroke.

NEWMAN INDUSTRIES LIMITED

Machine Tool Division: YATE, BRISTOL

Tel.: Chipping Sodbury 3311. Telex. 44121. Cables: "Dynamo Yate." London Office: Terminal House, Grosvenor Gardens, S.W.1, Tel.: Sloams \$296.

K·E·N·T

CAPSTANS Ward 2C. late machine first class.
Ward 3A, good condition, late machine.
Murad lin. power feed. 1960 machine.
Bolay & Leinen SR26 1/3 in. capacity.
Ward 2A air collet chuck.
Herbert 2S 1/4 in. bar cap. Herbert 4BS

LATHES

Colchester Triumph 7½in., as new.
Betts Bridgeford 14in. × 16it.
Le Blond "Regal" 5.5. & 5.C. 6jin. × 24in.
Graham & Normanton surfacing and boring. 44in. swing in gap.
Le Blond "Regal" 5.5. & 5.C. 8in. × 36in.
Lang S.S. & S.C. gap bed. 12½in. × 14ft. swing 45in. in gap.

MILLING MACHINES Herbert No. I horiz. 16in. × 5in. table. Herbert No. 10 vert. 25in. × 6in. table. Asquist 2 spindle profile mill. X 6311, table. Asquist 2 spindle profile mill. Archdale 14in. horiz. 29in. X 84in. table. Rigid 124in. horiz. built-in telesc. brace. Archdale 20in. horiz. Very good condition.

PRESSES
Weingarten 30 ton, open fronted, inclin-Raskin R5A 60 ton, only one still available. Raskin R4 50 ton, UDAL guards, only Edwards B.A.19, 18 ton, adjust, stroke, Inc.

GRINDERS Rowland 14in. heavy duty, wet & dry grinding.

B.S.A. centreless No. 7 1 in.-3in. capacity.

AUTOS
Brown & Sharpe O.G. Single Spindle jin. cap.

jin. cap.

ladex OR 12 Single spindle bar feed,
tooling.

C.V.A. No. 8 single spindle jin. capacity.

Very good DRILLS Pollard 12AX 5 spindle. JACOBS chucks

Pollare 12AX 2 spindle bench drill, Pollard 12AX 2 spindle bench drill, JACOBS chucks etc. Herbert single spindle sensitive pillar drill. Jones & Shipman 2 spindle vertical Storey 25 pillar. Good machine.

VARIOUS
Sigma 1 ype Jig Borer and precision Milling and Drilling machine.
Invicta 18in. Shaper. Model 4M.
Heald 48A double headed 'Bore-matic'

All motorised 400/3/50

K·E·N·T MACHINERY & ENGINEERING CO. Datchelor Place Mews, London, S.E.S

Telephone: ROD 4149

New Britain Single Spindle Chucking Auto. Size No. 38. 10in. dia. swing. Motorised.—WILCOX & CO., Barr Street, Birmingham 19. NORthern 1234/5.

KENDALL & GENT Open Sided Plano Type Milling Machine. 16ft. × 3ft. Table, Table traverse 17ft. Motorised 400/440/3/50. For full details apply to:-

> STANCROFT LIMITED Bedworth Road, Coventry Telephone: Coventry 88072/3

ROLLS TOOLS LTD.

OF WOKING, SURREY

AUTOMATICS

B.M.W.13. 13 mm. single Spindle. CLEVELAND Model A. in. capacity. CVA No. 8. 3rd Slide. CVA No. 12. 3rd Slide. INDEX 18. 3rd Slide.

MULTI SPINDLE AUTOMATICS

řin. B.S.A. ACME GRIDLEY RA 6 spindle. Screwing spindle, Collets and Tooling. 2 available. 1944-1948. Išin. CONOMATIC 8 spindle with screwing spindle, thread rolling, tool-

ing and collets.

lin. NEW BRITAIN GRIDLEY 6 spindle, Model 60.

1lin. ACME GRIDLEY 6 spindle Bar

Auto n. ACME GRIDLEY 4 spindle, G Model Bar Auto.

BROACHING

WEATHERLEY Oil Gear, Vertical 12in. by 30in. LAPOINTE Vertical 8 ton, 36in. CVA British Broaching Machine 6 ton, 36in. stroke.

DRILLS

HERBERT J TYPE. Single Column and two column machines. ARCHDALE Snout Type Electrically Controlled Vertical Borer, 50 Int.

LELAND GIFFORD 2 Spindle No. 2

ASQUITH Horizontal Duplex M/c. No. 5 Morse 5ft. dia. Rotary table. ARCHDALE 2 spindle, mounted on a bridge with swivelling and centre distance adjustment. Power traverse to quills. No. 4 Morse. Table 92in. by 13in, working surface. ARCHDALE UGD No. 4 Morse Taper

Power Feed

RADIAL DRILLS

ASQUITH 6ft. D.C. Drive. £400.

GEAR HOBBING MACHINES

PFAUTER type R00 and R.0. MIKRON type 79. CLEVELAND 130D. BARBER COLMAN No. 3 (2 machines).
GLEASON 3in. 2 tool Bevel Gear

Generator and equipment. Setting

LORENZE SOO High Speed Gear Shaper, Rebuilt.

GRINDERS-CYLINDRICAL

PRECIMAX SP 1½, 7in. by 12in. ARCHDALE Horizontal Mill, table 40in. by 10in., with 18in. travel, 10in. PRECIMAX MPL., 6in. by 24in. cross slide travel, 10in. vertical knee Plunge.
NORTON 6in. by 24in.
CHURCHILL 6 by 18 Hydraulic feed, hydrauto bearings.

GRINDERS-SURFACE

DOALL 20in. by 6in. Hydraulic Feed. BLANCHARD 10C. 6in. Magnetic Rotary Table. SNOW VB18, 84in. traverse by 15in.

LAPPING MACHINES

HAHN & KOLB 26in. dia. with Coolant Filter Plant. Reconditioned.
PETER WOLTERS Hydraulic. Two
Spindle Vertical Honing Machine.
NEWALL Hydro Lapper 24in. dia. of table, approx. 8 years old.

LATHES

SMART & BROWN Model A 4jin. by 24in.
WARD HAGGAS & SMITH face-

WARD HAGGAS & SMITH tace-plate Lathe, 57in. swing, 64in. in gap. Short bed with adjustable gap. LE BLOND Production Lathe, 7in. centres by 36in. between. TRIDENT Gap Bed 64in. by 60in. SPRINGFIELD 24in. by 12in. centres by 60in. between, speeds 9 to 280

HOLBROOK Model 16H A.G.H., 1,000 r.p.m. SS & SC, 8in. by 36in. JAMESON 'N' Type 42in. Swing Spinning Lathe. 60in. between centres. Variable speed gearbox. 60in. Faceplate. Back Plate. Tailstock.

CAPSTAN AND TURRET LATHES

ACCURATOOL Capstan. Capacity HERBERT No. 4, Senior Eloptive. HERBERT No. 0.
GISHOLT No. 3 Simplified Capstan.
MODERN No. 1. WARD 3A Capstans. WARD 2A Capstans.

MILLERS THREAD

PRATT & WHITNEY lead screw thread Miller. HILLE 6in. O/D Max. MATTERSON No. 11.

HANSON WITNEY 9in. by 4in.
WICKMAN Moulton.
ARCHDALE with 120 Hobs.
WANDERER. 3in. capacity.

MILLING MACHINES

movement, power traverse all slides.
CINCINNATI 08 Vertical. THIEL Model 58 Tool Room Mill. WADKIN High Speed Vertical Table 35in. by 13in.
CINCINNATI No. 3 Vertical Sliding head (overhauled).

ALEXANDER No. 2, 3 Dimensional Pantograph Machine.
HERBERT No. 1 Hand Mill.
EDGWICK Horizontal Machine. MAXIMA Horizontal Power Feed 30in.

CINCINNATI No. 3 Horizontal Dial Turret Machine. Dual Control.

TAYLOR & CHALLEN Type 1413
40 ton Variable stroke—Guards.
81-6-ton RHODES Upright Geared.
16-ton RHODES Inclinable.
25-ton RHODES Inclinable.
35-ton RHODES Inclinable.
BLISS No. 8 Power Press.
ELY PRESSES No. 3 FLY PRESSES No. 3. HENRY & WRIGHT No. 6, Dieing Press, 25 tons.

SHAPERS

EXCEL Punch Shaper, well equipped, in excellent condition.

THIEL 5in. Stroke Dividing Head, with 8in. table.

JUST RECEIVED

NOBLE& LUND A.G.H. Shed Wheel Lathe, Swing 8ft. by 6ft. 2 saddles external works, I saddle internal works, overall size 19ft. by 8ft. high, weight

18 ton approx.

- Fig. 540 JONES & SHIP-MAN 6 by 18 Surface Grinding Machine.
RICHARDS No. 3 RPT Hori-

zontal Borer with facing head. WARD No. 7 Covered Bed

MIDSAW Standard Toolroom Band Saw and Filing Machine,

20in. Capacity.
300 KVA SCIAKY Projection
Welder, Electronic Control
Panel. The whole unit hardly used, in new coapprox. 3 years old. condition,

All Electrics 400/3/500

ROLLS TOOLS LTD. No. I Factory, Pyrford Road, Pyrford, Woking Contact Mr. P. W. Gander Telephone: Byfleet 43252/3 & 41456

BETTER TRY 600 FIRST

CINCINNATI No. 3 Dial Type Vertical MILLING MACHINE. Table size 15in. × 62in. Spindle speeds 18 to 450 r.p.m. Power feeds and rapid traverse in all directions. Motor drive 400/3/50.

62in. Spindle speeds 18 to 450 r.p.m. Power feeds and rapid traverse in all directions. Motor drive 400/3/50.

PEGARD Model M.P.H. Horizontal Kneeless Type Production MILLING MACHINE. Working surface of table 39\(\frac{1}{2}\)in. X 14\(\frac{1}{2}\)in. Max. longitudinal traverse 25\(\frac{1}{2}\)in. 18 spindle speeds 22.5 to 1.120 r.p.m. Power traverse and rapid feed to table. Motor drive 400/3/50. Price: 6950 NOEL ERNAULT No. 3 CAPSTAN LATHE. Bar capacity 1\(\frac{1}{2}\)in. Spindle speeds 40 to 3,000 r.p.m. Power feed to turret, saddle and cross silde. Arranged for bar work and complete with collet chuck and bar feed equipment. Motor drive 400/3/50. Price: 6750 DEAN, SMITH & GRACE \$\frac{1}{2}\)in. between centres. 2\(\frac{1}{2}\)in. hollow spindle. Spindle speeds 12.5 to 560 r.p.m. Motor drive 400/3/50. Price: 6255 WARD No. 7 Covered Bed CAPSTAN LATHE. Max. bar capacity 2in. Max. distance spindle to turret face 30in. 8 spindle speeds 37 to 750 r.p.m. Power feed to turret, saddle and cross silde. Arranged for bar work. Complete with ball chuck and bar feed mechanism. Motor drive 400/3/50. Price: 6875 LANDIS Universal GRINDING MACHINE 12in. × 36in. between centres. Variable aped workhead. Complete with internal spindle and chuck. Motor drive 400/3/50. Price: £750 BALLINGER (Complete with internal spindle and chuck. Motor drive 400/3/50. Price: £750 BALLINGER (Complete with internal spindle and chuck. Motor drive 400/3/50. Price: £750 BALLINGER (Complete with internal spindle and chuck. Motor drive 400/3/50. Price: £750 BALLINGER (Complete with internal spindle and chuck. Motor drive 400/3/50. Price: £750 BALLINGER (Complete With Internal Application for the 400/3/50. Price: £750 BALLINGER (Complete With Internal Application for the 400/3/50. Price: £750 BALLINGER (Complete With Internal Application for the 400/3/50. Price: £750 BALLINGER (Complete With Internal Application for the 400/3/50. Price: £750 BALLINGER (Complete With Internal Application for the 400/3/50. Price: £750 BALLINGER (Complete With Interna

nal spindle and chuck. Motor drive 400/3/50.

BALLINGER Type "C" Manually Operated Abrasive Wheel CUTTING OFF MACHINE. Max. wheel size 16 in. Capacity—solid bar 2 in. dia.; channel 4 in. × 2 in.; angle 3 in. × 3 in. × 3 in. Motor drive 400/3/50. However, and the spindle spindle spindle spindle speeds 45 to 2,000 r.p.m. Fitted with quick change gearbox, and hydraulic copying attachment. Motor drive 400/3/50.

ADCOCK & SHIPLEY Model SVI40
Low Base Radial Arm DRILLING
MACHINE. Max. radius 36in. Spindle
bored No. 3 M.T. 8 spindle speeds 96 to
1,500 r.p.m. Three rates of power
feed to the spindle. With loose box
table. Motor drive 400/3/50.

GUSTHOLFF 32in. stroke Vertical
SQUTING MACHINE.

GUSTHOLFF 32in. stroke Vertical SLOTTING MACHINE. Max. distance table to ram guides 35 in. Variable ram speeds. Circular table 47in. dis. With variable feed and rapid traverse. Motor drive 220-380/3/50. Fitted with copying attachment.

GEORGE COHEN **SONS & COMPANY LTD**

SUNBEAM ROAD, London, N.W.10 Tel.: Elgar 7222/7 STANNINGLEY, NEAR LEEDS Tel.: Pudsey 2241

BELL STREET, WEST BROMWICH Tel.: Bromwich 2634

MARTIN BROTHERS (MACHINERY) LTD.

EMPRESS WORKS, EMPRESS STREET CORNBROOK, MANCHESTER, 16 Tel.: Trafford Park 1091-2

SELECTION OF OUR NEW

KEETONA 6ft. 6in. × in. Guillotine.

PACERA şin., şin., şin. Drills. (Ex Stock)
FOBCO şin. Bench Drill. (Ex Stock)
TOWN 4ft. 6in. Radial Drill.
PACERA M.F.5 Radial Drill.

PROGRESS 4E Pillar Drill. (Ex Stock)
PROGRESS 3A Pillar Drill. (Ex Stock)
PROGRESS 2GS Pillar Drill. (Ex Stock) KERRY 125 Pillar Drill.

(Due December 1961)
RICHMOND S.R.2 Radial Drill.

RICHMOND S.R.2 Radial Drill.
(Due December 1961)
RAGLAN 5in. S.S. & S.C. Lathes (2).
(Due December 1961)
MITCHELL 8½in. × 4ft. 6in. S.S. & S.C.
Lathe.
Lathe.
DENBIGH DVSR 4 Horizontal Millers (2). BEAVER VBRP Turret Miller. (Ex Stock)
GIEWONT No. 2 Vertical Miller
(Due December 1961)

CENTEC 28 Horizontal Millers (2).

(Due Dec. 1961, Jan. 1962)

B.S.A. No. 0 Drill Pointer. (Ex Stock)
UNION Tool & Cutter Grinder.
(Due December 1961)

EAGLE Surface Grinders, Models SW and

2A. (Ex Stock)
MILFORD 10in. and 12in. D/E Grinders.

Q. & S. 6in. Hacksaw. (Ex Stock)
PELS MKC 10 Punch and Shear. (Due December 1961)
BULLOWS 150 SR Compressor. (Ex Stock)

INVICTA 6M, 4M and 4S. (6M due Dec. 1961) (4M and 4S PILOT 12 ton Press. (Due December 1961)

The above list is only a selection of the many new, used and rebuilt tools we hold, please call or write for our priced brochure.

Reed Prentice No. 5 Vertical Milling Machine. Table 68 in. × 16 in. 18 spindle speeds 17-600 r.p.m. Excellent condition. Further details from:

15. Abercorn Street,
PAISLEY.

FORREST

ASQUITH 7ft. Universal Portable Radial Drill.

KITCHEN & WADE 4ft. 6in. Radial

HERBERT 18P Horiz, Miller. REDMAN 10ft. × 4ft. × 3ft. Planer,

SNOW 12in. Abrasive Wheel Cutting-off machine, 2in. capacity.

W. FORREST & CO. LTD., SYLVESTER GARDENS SHEERIELD I

'Phone 23314/5

1in. Tangential Heap Screwing Machine 400/3/50. Suitable for Pipes and Bolts.—HICKS MACHINERY LTD., 26, Addison Piace, London, W.11. Tel.: PARk 2333.

Potter & Johnson 4D Chucking Auto complete with all Tooling. Two Machines available. Further details from:

C. & G. OLDFIELD, LTD., 15, Abercorn Street, PAISLEY.

For Sale-Thread Milling Machine—In Good Condition, admitting 6th. between centres, swinging 9in. over saddle and having 2tin. hole in spindle. Motor driven, can be inspected. Further particulars on request.—STANLEY MACHINE TOOL CO., LTD., New Bank, Halifax.

ARCHDALE 20in. Plain Horizontal Milling Machine. Motor drive 400 volts, 3 phase, 50 cycles. Table 41in. by 10in. Dial type feed and speed change. 12 Spindle speeds 30 to 600 r.p.m. With arbor and arbor support, separate electric suds pump and tank.

Rosmy.

4/6 Minerva Road, Park Royal, London, N.W.10.

Telephone: ELGar 4841/4842

Selbourne Road LUTON Tel. 52351

New machines available from stock

ARBOGA ER.1258 Radial Drilling

SANFORD 12in. × 6in. Hand Feed Surface Grinder.

BEAVER Model 'A' Turret Milling

SMART AND BROWN Model 'A'

STARTRITE 'Orn '74in. × 40in, Lathe. INVICTA 4M Shaper. ALBA 45 Shaper.

VICTORIA U2 Universal Miller. **DENBIGH** D4 Milling Machine.

Used Machines available include: MILWAUKEE IB Plain Miller. WARD 2A Capstan, with ball chuck, etc. AJAX Sin. Horizontal Miller.



MOST LEADING MAKES IN STOCK

Showrooms at: 342 QUEENSTOWN ROAD (Close to Chelsea Bridge) and CRANFORD LANE, HOUNSLOW (Close to London Airport)

AUTOMATICS

- -> CONOMATIC (U.S.A. Built) 4 Sp. 4\frac{1}{2}in. Cap.
 GREENLEE 6 Sp. 1\frac{1}{2}in. Cap.
- CONOMATIC 6 Sp. Ilin. Cap.
- B.S.A. GRIDLEY 6 Sp. lin. Cap. Bar (1952) (1952).

 B.S.A. GRIDLEY 4 sp. ¿in. Cap.

 GRIDLEY 6 Sp. ¿in. Cap. (Choice of two.)
- B.S.A. No. 68 Single Spindle &in. Cap.
 B.S.A. No. 38 Single Spindle &n. Cap.
 HERBERT No. 4 Chucking.

BORERS

- Horizontal PEARN RICHARDS No. 3 with 24in. dia. facing head. Table Area 7ft. 3in. \times 5ft.
- RICHARDS HB. 2A 3in. Travelling Spindle. (Choice of three.) KEARNS OC. 23in. Travelling Spindle
- CRAVEN 36in. heavy duty, side head, elevating cross rail, rapid feeds.

- LANDIS 6in. × 18in. Hyd. Plain Cylindrical P.F. (1952).
- MYFORD Sin. × 9in. Model MG9 Plain Cylindrical.
- CHURCHILL I6in. × 72in. Universal. CHURCHILL 12in. × 50in. Hyd. Universal,
- internal spindle. FITCHBURG 12in. × 32in. Universal. JONES & SHIPMAN 8in. × 16in. Universal,
- internal spindle. HEALD 72A3 Internal Grinders, Series 18,000. (Choice of two.)
- LUMSDEN 24in. dia. Retractable otary Table Surface Model 90RT. With Rotary Table Surface McChuck (1952). FITCHBURG 48in. Spline. ORCUTT 20in. Spline.

GLEASON No. 24 Straight Bevel Generator S/N17920. MICHIGAN Gear Lapper. S/N2280.

DRULS

- Radial ARCHDALE 4ft. Oin.; 60 to 1,500 r.p.m.
- (Choice of four.) KITCHEN & WADE 4ft. 0in. Bridge Type.

- Single Spindle

 → ASQUITH Type U.G.D. 3in. Cap.;
 31/850 r.p.m. Column. (Choice of two.) 1952. POLLARD CORONA %in. Cap. 642-12,040 r.p.m. bench. (Selection of several.)
- BARNESDRILL Hyd. Type H.4 16 Sp.
- ARCHDALE Cluster 12 Sp. §in. Cap. POLLARD Corona Model H.E.F., 4 Spindle, Tein. Cap. 642-12,040 r.p.m. Bench. (Choice of two.)

MILLING MACHINES

Plano

- KENDALL & GENT, table 5ft. × 4ft. 6in.
- ** KENDALL & GENT, table 5ft. × ft. × 3ft. 6in.
- HERBERT 28V, table 85in. × 28in.; 12 to 360 r.p.m.
- HERBERT 47. Table 72in. × 17in.; 21 to 750 r.p.m.
- CINCINNATI 4 VHP, table 784in. × 164in.: 17 to 480 r.p.m
- CINCINNATI No. 4 Dial type, table 78½in. × 16½in., 18 to 450 r.p.m. Power down feed.
- CINCINNATI No. 3 Dial Type, table n. × 15\frac{1}{2}in.; 18 to 450 r.p.m. (Choice of 62\in. three.)
- CINCINNATI No. 2 Dial type, table 524in. × 124in.; 20 to 500 r.p.m. ARCHDALE 18in., table 38in. × 10in.; 79 to 2,000 r.p.m.

Plain Horizontal

- MILWAUKEE 2K, table 56in. × 12in. 15 to 1,500 r.p.m. (Rebuilt.)
- ARCHDALE 20in., table 40in. × 10in.; 60 to 1,230 r.p.m. Rapid Production. CINCINNATI 2/24 Production.
- CINCINNATI O8, table 181 in. × 61 in.; 75 to 1,100 r.p.m. Production. (Choice of two.)

LATHES

- Centre SWIFT 13in. \times 132in.; 3.6 to 220 r.p.m. Straight Bed.
- SPRINGFIELD 12in. × 48in.; 9 to 380 r.p.m. Straight Bed.

- SCULFORT 12in. × 70in.; 12.5 to 1.000 r.p.m. 1952.
 DEAN, SMITH & GRACE 12in. × 66in., 19 to 418 r.p.m. Straight Bed.
 PROGRESSIVE 11in. × 120in.; 20 to 516 r.p.m. Gap Bed.
 SWIFT 10in. × 96in.; 11 to 400 r.p.m.
 Straight Bed.
 DEAN, SMITH & GRACE 8in. × 50in.; 11 to 490 r.p.m. Straight Bed.
 MOLBBOOK 8iin. × 48iin. Speeds 7.5 to
- HOLBROOK 8½in. × 48in. Speeds 7.5 to 400 r.p.m. Straight Bed. (Choice of two.) PROGRESS 8in. × 60in.; 23 to 1,050 r.p.m.
- Gap Bed. A volin. Speeds 15 to 400 r.p.m. S.S. & S.C. Straight Bed.
 Capstan, Comb. Turret
 LIBBY 1HS Comb. Hole in spindle 5½in.
 Power and rapid feeds to Saddle, Turret and
 Cross slide. CALT 21. Comb. 2019.
- GISHOLT 2L Comb. 22in. swing. 1952 built. HERBERT 21 Comb. No cross slide.
- WARD 10B Comb. Power feed to Turret, Air Ball Chuck, Bar Feed Equipment Rebuilt.

VARIOUS

- BARNESDRILL 5in. × 25in., Vertical Honer. RHODES 75 ton Double Sided Single Geared Press, fitted with Worsam air cushion. BUTLER 24in. Heavy Duty Production Type
- BUTLER 12in. Stroke Slotter with tilting table. BUTLER 18in. Stroke Super Shaping Machine.

NEW BRONX PRESS BRAKES FROM STOCK

Series 98, 90/135 tons, 8ft. by 13in. Series 68, 60/90 tons, 8ft. by 10G Series 48, 40/60 tons, 8ft. by 14G

OTHER NEW MACHINES

- HEINEMANN 28in. Stroke, Heavy-duty, High-Speed, Hydraulic Shaper with power down feed.
- DENBIGH D.4 Mill, Table 46in. by 10in.; 22-720 r.p.m.

OFFERS of OUTSTANDING MACHINES ARE MARKED-

Telephone: Tate Gallery 0633/6 FOR COMPLETE STOCK LIST

MACHINE TOOLS L

GROSVENOR GARDENS HOUSE - GROSVENOR GARDENS - LONDON - S-W-1 Telephone: TATe Gallery 0633/4/5/6 Cables: Norbros, London

machine tools FEDS 63-7398

HERBERT No. 4 Capstan, With air equipt. Speeds to 1,000 r.p.m.

ARCHDALE 18in. Production Miller. Table 32in. × 9½in.; long, power traverse 18in. 14 speeds 32-175 r.p.m.

WILLSON 7 in. Gap-bed S.S. & S.C. Lathe. Swings 26in. in gap and 36in. b.c.

EDGEWICK No. I Vertical Keyseaters. Table 26in. × 9in. Stroke approx. 4in.

RHODES No. 3 Double Sided Hand Screw Press. 3 in. dia. screw. Admits 34in. between slides. Approx. pressure

CINCINNATI 2/18 Production Miller. Table 36in. × 9in. 20 speeds 30-1,200 r.p.m. 2-way cycle. M.D. 400/3/50. SWEENEY & BLOCKSIDGE No. 7 Inclinable Power Press. Cap. 10 tons. Stroke lin.

CINCINNATI No. 3 Vertical Miller. Dial type. Table 62½in. × 15in. Power to head. 21 speeds 18-450 r.p.m.

HOLROYD Oil Groover.

HEIDENREICH & HARBECK Model 15 K.H.G. Bevel Gear Generator. Date 1952.

ASQUITH 7ft. Universal Portable Heavy Duty Radial Drill. No. 5 M.T. As new.

HILMOR Type CI Tube Bender. For steel tubes up to 2½in. dia.

HUNT Model I and IA Twist Drill Caps. in. and lin. resp.

SWIFT 10½in. Gap-bed S.S. & S.C. Lathe. Admits 7ft. 6in. between centres; 35in. dia. in gap. Taper turning.

WARD 7 Bar Lathe. Covered bed. Speeds 50-1,000 r.p.m. With bar feed, ball chuck, collets, etc.

KENDALL & GENT Model C.V.M. 40 Vertical Miller. Table 63in. × 29in. With built-in rotary table. Speeds to

BESCO No. 21 Inclinable Power Press. Tonnage 40. Stroke 3in.

NEW UNION Model G.14 Double Ended Grinders. Grinding wheels 14in. × 2in.

H. BELL (Machine Tools) LTD., Walter Street, LEEDS 4.

No. 4 KEARNS Patent Horiz. Boring and Facing Machine, with 4in. dia. trav. spindle. Automatic facing, 54in. dia. Main table 66in. × 42in. Top table 48in. × 48in. Balanced head.

No. 4 RICHARDS PRN Horizontal Boring and Facing Machine, to face up to 48in. 16 and 16 and

condition.

No. 3 CINGUNATI m/d dial type Vertical
Milling Machine, Table 62‡m. × 15‡m.
Can 34in. × 16in. × 16in.
Auto, feeds
with rapid traverse all discovering the speeds
such rapid traverse and, ready,
5in-ARCHDALE 3-spindle Drilling Mc.
One spindle No. 2 M.T. 2 spindles
No. 3 M.T., geared, auto, feed, tapping
reverse.

LEE & HUNT LTD...

CROCUS STREET,

Tel.: Nottingham 84246.

******* Fielding-Swan S.S. & S.C. Centre Lathe. Taper Turning Attachment New 1958.

Further details from:
C. & G. OLDFIELD, Ltd.,
15, Abercorn Street,
PAISLEY.

Two in No. DRUMMOND Maximatics, 9in. × 18in. Serial Nos. HA.2670 and HA.2671.

One in No. FRASER Automatic Facing and Centring Machine T.F.M.I. and a number of Four Spindle Drilling Machines. All machines are as new, offers invited.

BOX D.433, MACHINERY Clifton House, Euston Road, N.W.I

Maddison Kipp Model S315 6in. Will action a special model S315 6in.

× 6in. Pneumatic Die Casting Machine for sale. Zinc, lead, tin alloys. Pot capacity 150 lb. zinc alloy. Capacity per shot 1† lb. zinc. Die size 6in. × 6in. × 4in. thick.—Photos, etc., from F. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1, or 41, Water Street, Birmingham, 3. HOLROYD 2-Spindle Vertical Profile Milling Machine. Independent motor to each spindle, 400/440 volts, 3 phase, 50 cycles. Table W.S. 18in. by 14in. Spindle speeds to 3,000 r.p.m.

ASQUITH 2-Spindte Vertical Profile Milling Machine. Motor drive 400/440 volts, 3 phase, 50 cycles. Table W.S. 18in. by 14in. Spindle speeds 250 to 3,000 r.p.m.

Rogery. 4/6 Minerva Road, Park Royal, London, N.W.10

Telephone: FLGar 4841/4842

HIGH QUALITY USED **MACHINE TOOLS**

COVMAC 17in. Swing A.G.H. Gap Bed S.S. & S.C. Lathe. 5ft. 0in. B.C. 400/3/

S.S. & S.C. Lathe. 5ft. 0in. B.C. avoyo, 50, 10 and SPRINGFIELD 10in. Centres Gap Bed Screwcuting Silding, Surfacing Lathe. 36in. B.C. 400/3/50. Used OLICHESTER \$4 in. Centre S.S. & S.C. Gap Bed Lathe. 58in. B.C. 400/3/50. Used MITCHELL OF REIGHLEY \$4 in. Centre A.G.H. Gap Bed S.S. & S.C. Lathe. 4ft. 4in. B.C. 400/3/50. ARCENDALE 20in. Milling Machine, table size 40in. X 10in., power and repid traverses to table, reversing spindle, bedclash eliminator 400/3/50. B. Turret Lathe. 400/3/50. Turret Lathe. 400/3/50. ARCENDALE & SWASEY IA Turret Lathe. 400/3/50.

400/8/50.

RUSSELL Saw Sharpening Machine, max. capacity 42in. diameter. 400/8/50.

ORMEROD 12in. Slotting Machine.

400/8/50. WE UNDERTAKE REBUILDING OF ALL TYPES OF MACHINE TOOLS

CENTAUR TOOL WORKS, EYRE STREET, SPRING HILL, BIRMINGHAM, 18

Tel. EDGbaston

'Grams Capetan, Birmingham

Bryant No. 24-36 Hydraulic Internal Grinder, complete with Hydraulic Wheel Dressing device, Spindle, etc. Further details from:-

C. & G. OLDFIELD, LTD., 15, Abercorn Street, PAISLEY.

BLISS 21‡ Open Front, Geared, Inclinable, Power Press. Pressure 55 tons. Stroke 3in. Bed area 32in. × 22in. 400/3/50. VAN NORMAN No. 12 Silding Head, Milling Machine. Tablesize 38in. × 8in. 9 spindle speeds 70 to 1,465 r.p.m. 12 auto feeds ‡in. to 14in. per minute. 400/3/50. Complete with Vertical Attachment. ASQUTH Type EGC. 6ft. Girder Type Radial Drilling Machine. Spindle bored No. 5 M.T. 6 spindle speeds 220 to 905 r.p.m. Travel of quill 12in. Auto feeds 4 to 0.0083 to 0.027in. per rev. 400/3/50.

feeds 4 to 0.0083 to 0.027in. per rev.
400/3/50.

TAYLOR in. Capstan Lathe fitted collet chuck and bar feed. 12 spindle speeds 210 to 2.750 r.p.m. forward and reverse.

Hand lever feed. 400/3/50. 1960 machine.
WILSON 7 in. Centre Lathe. 30 in. between centres. 9 spindle speeds 20 to 477 r.p.m. Hole through spindle 2 in. fid. 10 to 477 r.p.m. Hole through spindle 2 in. fid. 10 to 477 r.p.m. Hole through spindle 2 in. fid. 10 to 470 f.p.m. Hole through spindle 2 in. fid. 10 to 470 f.p.m. Hole through spindle 2 in. fid. 10 to 470 f.p.m. Hole through spindle speeds 25 to 1,000 r.p.m. 400/3/50.

WOODHOUSE & MITCHELL 7 in. Centre Lathe. 36 in. between centres. 8 spindle speeds 30 to 437 r.p.m. Hole through spindle 1 in. dia. Latest type machine. 400/3/50.

400/3/50.

RASKIN Type 6A 100 tons Geared, Eccentric Power Press. Adjustable Stroke in. to 3 in. Bed area 29 in. × 23 in.

tin. to 3†m., here to 400/3/50.

MORGAN 6ft. × in. Universal Folding and Bending Machine. High lift to beam. Geared, Hand Operated.

PROGRESS 5E Pillar Drilling Machine. 2in. capacity. 9 spindle speeds 58 to 839 r.p.m. Power feeds 24in. dia. table.

BESCO 8ft. × 4in. dia. Bending Rolls. Slip roll type. Hand Operated. FROST 4ft. × 4in. Motorised Swing Beam Folding Machine. Complete with gauges 400/8/50.

STANCROFT LTD.,

LANCASTER STREET, BIRMINGHAM, 4 ASTon Cross 2235

m

MACHINES NOW IN STOCK

AUTOMATIC
RYDERMATIC No. 18 Vertical Automatics 60 H.P.

BORING MACHINES

MATHEYS Model FPN/28 Semi Jig Borer. (1956.) PADDON Mk. 3 type WP Cylinder Re-Boring Machines.

HONING AND LAPPING DELAPENA Honing Machine.

CAPSTANS & TURRET LATHES WARD 2A Bar Feed, Ball chuck and

tooling.
AG-UR 2in. Capacity Capstans. Full equipment (New).

BOLEY-LEINEN Model ER15 ‡in.

Capstan (Modern) (1953).
GISHOLT No. 3 Capstan Lathe.
HERBERT Model 22A Turret Lathe.

8‡in. Spindle Hole.

TIMBRELL & WRIGHT Turn Facing Lathe, 6in. Hollow Spindle. WRIGHT Turret

CENTRE LATHES WILLSON 7 in. Newel Lathe. CRAYEN Heavy Duty Railway Wheel Lathe, swing 6ft. by 12ft., vee belt drive. Weight 25 tons.

New CAPITOL 9½in. Centre Lathe. Admitting 6ft. between centres.

FACEPLATE Lathe, 9ft. swing.

DEAN, SMITH & GRACE 8in. by 5ft. 6in. Centre Lathe.

7in. COLCHESTER Triumph Lathe.

4in. HERBERT Screw Cutting Lathe.

4in. HERBERT Screw Cutting Lathe. New GURKA 7in. × 30in. Centre Lathe, full equipment.

REED PRENTICE 10in. × 8ft. Centre

Lathe.

GRINDING MACHINES
MYFORD MG 12 Cylindrical Grinder.
CRAVEN Heavy Duty Roll Grinding
machine with capacity for rolls 42in.
dia. by 12ft. between centres and
fitted with automatic cambering. Will take rolls up to 25 tons weight. Fully motorised machine of modern design. Weight 25 tons.

ZENITH Model PH Horizontal Spindle.

Hydraulic Surface Grinder, 24in. by

. (1953). Universal Grinder 10in. by 17in. (new).

CINCINNATI No. 2 Tool and Cutter

Grinding Machines.

COVEL No. 2 Tool and Cutter Grinder, Mill, 43in. × 12in. table.

Grinding Machine.

Grinding Machine.

Grinding Machine.

Grinder, Machine.

Mill, 43in. × 12in. table.

DENBIGH Model No. C2 Horizontal

Grinding ...
IMPERIA Tool and Cut.
Model M6AR. (1953).
Model M6AR. (1953).
TOLK No. 16G Plain Straight Two SCRIVENER No. I Centreless

BLAKE No. I Tap Chamfering Machine

(New). No. 6 Internal Thread Grinders 3in. × 10in.

HEALD Model 81 Internal Grinder.

LUND MPH Cylindrical, 5in. × 18in.

Capacity.
RINDIS De-Burring, Trimming and

Grinding Machine.
HEALD 72A Internal Grinder DIESINKING MACHINES

VICTORIA Duplomatic Hydraulic Copy Milling Machine, 8in. × 8in. (New)

DRILLING MACHINES
ASQUITH Model ODI Radial Drilling

Machine 4 M.T.

ACERA Jin. Bench and Jin. Pillar **PACERA** Drills (New).
Two ARCHDALE 36in, Radial Drilling

Machines. No. 4 M.T. Two 30in. TAGO Radial Drills (New)

£716. 3 Spindle ARCHDALE No. 2 MT Pole

Change motors.

MULLER (Almost New) SR23 Radial

Drilling and Tapping Machine (two

GUILLOTINES

BESCO 42in. × 10 s.w.g. Power Guillotine.

HANDS 4ft. × in. Guillotine. RHODES 6ft. × in. Guillotine.

MILLING MACHINES MILWAUKEE Model 5H V Vertical Mill, dial type, high speed model Mill, dial type, high speed model with power down feed to head, table 94in. × 18in. (New price U.S. \$36,680. This machine is in beautiful condition, offered at a fraction of replacement cost.)

MILWAUKEE 3CE Horizontal Milling

Machine, Table 10in. × 57in. (Almost New).

a few yards from Olympia



348-354, KENSINGTON HIGH STREET - LONDON - W.14.

'Phone WEStern 7031 (5 lines). AFTER BUSINESS HOURS YOU MAY LEAVE YOUR MESSAGES AND ENQUIRIES ON OUR TELEPHONE ANSWERING MACHINE.

TATE

VICTORIA Junior Omnimil (New).
Two ARCHDALE 18in. Automatic
Cycle Kneeless Production Millers.
SOMUA Model FH2C Horizontal
Miller table 67in. × 14jin. (1953).
CUNLIFFE & CROOM No. 2

CUNLIFFE & CRE Vertical Mill (dial). FACKS Thread Miller.

ARCHDALE 34in. Plain Horizontal Miller 60in. × 13in. (nearly new). BEAVER Model VRBP Vertical Miller

CINCINNATI 18in. Manufacturing

Mill. 36in. × 12in.

ADCOCK & SHIPLEY No. 3B Plain Mill, 36in. × 10in. table.

PLANING MACHINES

DYE 12 × 3 × 3 Planing Machines, 2 toolboxes on rail (New).

HOLROYD PLANO MILLING MACHINE, capacity 17ft. 6in. × 9ft. 6in., 2 heads on cross rail with 25 h.p. drive, pendent control, weight 50 tons. (Modern machine).

POWER PRESSES RHODES I-Ton Open Fronted Bench Press with flange motor and UDAL

guards.
LEE & CRABTREE 15-Ton Horning Press.

LEE & CRABTREE 20-Ton Horning Press.

LEE & CRABTREE 35-Ton Double Action Mechanical Press

H.M.E. Model DCP3 70-ton Double Sided, Double Crank, Single Action Power Pre

Six New MULLER Model AMP 22-ton Power Presses. Complete with horn. Three New MULLER Model AMP 35-ton Power Presses.

Two New MULLER AMP 45-ton **Power Presses**

Two New MULLER AMP 60-ton Power Presses. Open Fronted. Two New MULLER AMP 80-ton Geared and Ungeared Power Presses.

BLISS 50-ton Open Front Power Press. SHAPING MACHINES

BERRY 16in, Shaper, BROOK 18in. Shaping Machine. KLOPP 22in. Shaping Machine. TORPEX 22in. Shaping Machine. New LIMA 22in. Shaper.

SAWING & FILING MACHINES WESPA AS4 Bandsawing and Band-filing Machine, hydraulic feed (similar Do-all V/16).

WATCHMAKERS' MACHINES MIKRON Automatic Cutter Sharpening Machine. SAFAG Model 24 Automatic Cutter

Relieving Machines.

rry Wii

nend the following modern quality machines from STOCK

AUTOMATICS

WICKMAN 5in. Chucking Automatic.

RYDER Verticalauto, capacity 16in. swing

× 8in., 6 spindles.

BORING MACHINES

KEARNS O.B. Horizontal Boring Machine, 2%in. Spindle. Spindle speeds 15/600 r.p.m. Excellent condition.

JONES 6in. Spindle Horizontal Borer-Table 17ft. 6in. × 8ft. Spindle travel 48in. Rapid traverse 84in. per min. Motorised 400/8/50. Weight 70 tons

BULLARD 36in. Vertical Boring Mill. KITCHEN & WADE Vertical Fine Boring
Machine, 14in. stroke. Compound table.

DRILLING WACHINE

ARCHDALE 8-Spindle Hydraulic Vertical Drilling Machine.

GRINDING MACHINES

BROWN & SHARPE No. 5 Surface Grinder,

BROWN & SHARPE No. 2 Surface Grinder, 18in. × 6in. table.

HEALD No. 172 Gap Bed Internal Grinding Machine, maximum diameter of com-ponent 36in.

LATHES

W.D. Sin. × 6ft. S.S. & S.C. Lathe, 30in. between centres.

NOBLE & LUND Heavy Duty Centre Lathe, 22in. centre height × 29ft. between centres. Max. swing over saddle 33in. dia.

HARVEY Heavy Duty Centre Lathe, 42 in. centre height × 52 ft. between centres. Max. swing over saddle 5 in. dia.

MILLING MACHINES

EDGWICK No. 2 Universal Milling Machine. Working surface of table 38in. × 71in.

BROWN & SHARPE No. 3A Universal Milling Machine with Vertical Head Attachment. Spindle speeds 30/1,200. Power feed all movements.

COLLET & ENGLEHARDT Keller Type
Die Sinking Machine. Model FKf80
capacity 60in. × 20in.

PLANING MACHINES

CLEVELAND Openside Planing Machine, capacity 10ft. × 2ft. 6in.

CINCINNATI Planing Machine, capacity 8ft. × 2ft. 6in.

MISCELLANEOUS MACHINES

Hydraulic Vertical Internal Honing Machine (manufactured by PETER WOLTERS). Capacity 0.2in. to 2in.

BAPIDAN Double Helical Gear Generating Machine, 12in, diameter capacity.

Further details from

HARRY KIRK ENGINEERING LTD.,

BRANDON ROAD WORKS, BRANDON BOAD, COVENTRY

'Phone: WALSGRAVE-ON-SOWE 2253 (6 lines).

all ways. Spindle speeds 30 to 462 r.p.m.
400/3/50.

TAYLOR & CHALLEN Double Crank,
Double Sided, Power Press. Type 1622.
75 ton pressure. 4in. stroke. Bed area
39in. × 38in. Balanced silde. 400/3/50.
Fully guarded.
BALLIMGER Type C Abrasive Wheel Cut
Off Machine. 2in. bar capacity. 3in.
tubes. Petal operated, swivelling vice.
RNYIOTA. 6M 24in. Shaping Machine.
6 speeds 8 to 74 s.p.m. Table top area
23in. × 13in. Longitudinal traverse 29in.
Swivel base vice. 400/3/50.

HERBERT C Type Pedestal Drilling
Machine. Capacity in mild steel 14in.
dia. Spindle bored No. 3 M.T. Speeds
104 to 562 r.p.m. auto feeds. Table area
164in. × 13in. 400/3/50.

STANCROFT LTD.,

LANCASTER STREET, BIRMINGHAM, 4 ASTon Cross 2235

JONES & LAMSON No. 3 Universal Turret Lathe. Motor drive 400/440 volts 3 phase, 50 cycles. 2in. Hollow spindle Chuck capacity 10in. Swing over bed 21½in. 12 Spindle speeds 20-1,000 r.p.m. Power feed to turret, saddle and cross slide. Fitted with 12in. four-jaw chuck, square turret, suds pump and fittings.

Rosay. 4/6 Minerva Road, Park Royal, London, N.W.10

Telephone: ELGar 4841/4842

Lang 20in. Surfacing and Boring Lathe, Chuck Model. Excellent Machine Further details from:— C. & G. OLDFIELD, LTD.,

15, Abercorn Street, PAISLEY.

Hilmor Motor Driven Tube Handor Mothor Driven Tube
Bending Machine for sale. Mandrel type.
Max. capacity: copper tubes 24in. bore ×
10 gauge; steel tube 2in. 0.D. y. 10 gauge;
conduit 2in. 0.D.; gas and steam tubes 14in.
nominal bore. Motor drive 400-440/3/50—
F. J. EDWARDS LTD., 359, Ruston Road,
London, N.W.1, or 41, Water Street, Birmingham 3.

Automatics. Acme Gridley model R. in. Four-spindle; Cleveland 1 tin. model "A" Single Spindle; Index "O" tin. model "A" Single Spindle; Index "O" tigh. Single Spindle; Brown & Sharpe "O" High Speed Single Spindle with motor.—HICKS MACHINERY LTD., 26, Addison Place, London. W.11. Tel.: PARk 2383.

COMPRESSORS

BROOM & WADE D22 100 lb. Compressor.

DRILLING MACHINES

PROGRESS No. 3 Pillar Drill. 1in. cap. PROGRESS 4E Pillar Drill, 11in, cap.

GRINDING MACHINES

NEW N.I. 10in., 12in., 14in., 16in. and 20in. D/E Tool Grinders. RUSSELL 40in. Saw Blade Sharpener. PRECIMAX M.P.H. 10in. × 24in. Hyd. Plain Cyl. Grinder, plunge feed. CHURCHILL 10in. × 24in. Hyd. Plain Cyl. Grinder, Din. × 24in. Hyd. Plain Cyl. Grinder,

GUILLOTINES

PRATT 3ft. 6in. × 16 gauge U/Crank Power Guillotine.

LATHES

COLCHESTER 81 in. × 4ft. 6in. Gap Bed HERBERT 7 Comb. Turret. 2in. H/Spindle. HERBERT 7 COMD. Turret. 2m. H/Spinare. Speeds 767 r.p.m. HERBERT 9 Comb. Turret, 44in. H/Sp. Speeds—400 r.p.m. HERBERT Carbicut Lathe. Speeds— 3.025 r.p.m.

MILLING MACHINES

MILWAUKEE 3H Horizontal Mil Speeds—1,000. Table 63in. × 13 in Miller.

NIBBLERS

W.F. 14 Gauge Nibbler. 59in. throat.

POLISHING SPINDLES

CANNING 3 and 5 h.p. Double Ended Polishing Spindles. H/Duty.

PRESSES

BRADLEY & TURTON No. 3 Flypress.
NORTON No. 4 Flypress,
NORTON 3BP Bar Type Flypress,
TAYLOR & CHALLEN 1274 Notching Press,
TAYLOR & CHALLEN B2 10 Ton O/F TAYLOR & CHALLEN B2 10 Ton O/F Power Press.

TAYLOR & CHALLEN 370 20 Ton O/F Power Press.

WEENEY & BLOCKSIDGE 20 Ton O/F Power Press, EDWARDS No. 21 40 Ton O/F Power Press.

SAWING WACHINES

RAPIDOR 6in, Power Hacksaw, NEW RAPIDOR 6in, Power Hacksaw, SPEEDAX 9in, Power Hacksaw, BARSON No. 1 High Speed Circular Saw, Cap, 1‡in, rounds, 2'n, tubes, 1‡in. × ‡in. flats, 1‡in. × ‡in. angles.

SHAPING MACHINES

CHURCHILL-REDMAN 18in. Shaper. Univ.

All machines 400/3/50 electrics unless otherwise stated

THE

MIDLAND MACHINE TOOL CO.

BRADLEY, BILSTON, STAFFS.

Tel.: Bilston 42471/9

HELIOT MACHI TOOLS

HORIZONTAL MILLERS SUNSTRAND No. 2 Rigidmil, kneeless production miller, fully automatic cycle, 54in. × 12in. table, table traverse 24in., spindle speeds 58-522 R.P.M., speeds and feeds by pick-off gears. Price £550

pick-off gears.

ARCHDALE 20in. horizontal
miller, 40in. x 10in. table, 20in.
table traverse, spindle speeds 30-615
R.P.M., speeds and feeds by dia
selaction, complete
milling attachment.

Price 4525.

CENTEC 3R electronic controlled high speed kneeless type automatic production miller, fully automatic cycle including elevation to head, spindle speeds up to 3,000 R.P.M., table traverse 14in., 34in. × 1lin table.

Price £725.

CAPSTAN LATHES

WARD No. 7 capstan lathe, covered bed, 2in. bar capacity, with collet and bar feed, surfacing, sliding and screwcutting, maximum swing l64 in. spindle speads 37-750 R.P.M. (2 machines available.) Price £1,250 each.

DRUMMOND K. capstan lathe, chucking machine, spindle bored 2½in., power feeds to cross slide, saddle and turrer maximum swing 17in., maximum distance spindle to turret 30in., spindle speeds 60-1,000 R.P.M. Price £375.

WARNER & SWASEY No. 5 capstan lathe, chucking machine, spindle bored 2†in., power feeds to cross slide, saddle and turret, maximum swing 19in., spindle speeds 26-658 R.P.M. Price 6450.

TURRET LATHES

WARD No. 16 turret lathe, covered bed, 32in. chuck, spindle bored 8½in., screwcutting, power and rapid feeds to cross slide, saddle and turret, power rotating turret, spindle speeds 7-225 R.P.M., maximum distance spindle to turret, 99in. Price £3,500. WARD No. 10 turret lathe, covered bed, chucking machine, spindle bored 4½in, screwcutting power feeds to cross slide, saddle and turret, rapid feed to turret, power rotating turret, maximum swing 23in., spindle speeds 19-580 R.P.M. Price £975. HERBERT 7A Preoptive turret lathe, as above, but fitted with taper turning attachment and collet head Price £990.

CENTRE LATHES

HOLBROOK 64in. centre lathe, straight vee bed, 30in. between centres, surfacing, sliding and screw-cutting, spindle speeds 15-400 R.P.M. quick change gear box, taper turning attachment. Price 4325.

DEAN, SMITH & GRACE 4BR 10in. centre lathe, straight bed, 42in. between centres, surfacing, sliding and screwcutting, spindle speeds 27-602 R.P.M., patent feed box, taper turning attachment. Price £708.

GRINDING MACHINES

BROWN & SHARPE No. 2 surface grinder, mechanical feed, 18in. × 6in. capacity. Price £189. grinder, mechanic fin. capacity.
WICKMAN 14C double sided tool grinding and lapping machine, 14in.
× 2in. × 1½in. double faced grinding wheels, 31in. × 19½in. recessed canting tables, coolant pump.

Price 2350.

Price £250.

JACKMAN No. 28, horizontal dice grinder, 51 in. diameter grinding disc, with overhead trueing attachment.

CHURCHILL OSB horizontal spindle surface grinder 30 in. x Sincapacity, variable hydraulic table feeds, 10 in. diameter grinding wheel mounted on cross adjustable head.

DRILLING MACHINES

ARCHDALE 5ft. radial drilling machine, low base, power elevating arm, No. 4 Morse caper, capping reverse, spindle speeds 40-2,000 R.P.M., maximum spindle feed 12½in., maximum spindle to base 56in.

Price £875

35 GREENWICH CHURCH STREET LONDON S.E.10

Phone: GREenwich 1222

Airedale " Kok-Out " Forging Hammer for sale. Coll spring type. Whip stroke 7in. Centre to back 144in. Treadle friction clutch.—F. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1, or 41, Water Street, Birmingham 3.

ACME GRIDLEY RAC.6 Chucking Automatic. 6½in. cap. 6-spindle.

NILES POND 6ft. Double Column Borer.
Power traverse all ways. Motorised.

PETERMANN No. 2 Pedestal Gear

Cutters. Jin. capacity.
HAMILTON 80-ton Inclinable Ungeared

Power Press.

KELLER Model B.L. Die Sinking Machine.

Table 48in. × 26in. 16 spindle speeds,
4-3,600 r.p.m. Motorised.

NORMAN E. POTTS (MACHINERY) LIMITED,

151/154, Sandy Lane, Birmingham 12 Tel.: VIC. 1278.

Rielding 75 Ton Four Column down stroke Hydraulic Press. Bed 23in. 21in. Daylight 72in.—HICKS MACHINERY LTD., 26, Addison Place, London, W.11. Tel.: PARk 233a.

Two Gleason 12in. Gear Generators complete with all Equipment including Gleason Gear Checker and Gleason Gear Cutter Sharpener. Can be sold as one lot or separate items. Further details from:

C. & G. OLDFIELD, Ltd., 15, Abercorn Street, PAISLEY.

Lang 8in. × 4ft, S.S. & S.C. CO., LID., New Line, Bacup, Lanes. Phone: Bacup 946.

20ft. Swing Faceplate Lathe, Saddle with two toolboxes. Motorised countershaft.—BOX D446, MACHINERY, Clifton House, Euston Road, N. W. 1.



ASQUITH 28in, Vertical Production Mill Table 49in, × 14in, 1,000 r.p.m. GHURGHILL Model D. Cylindrical Grinder. Cap, 30in, dia, × 56in, JOMES & SHIPMAN Model 745 Slot Hydro-mill, Table 68in, × 104in, HANSON WHITNEY Seml Auto Thread Milling Machine. Cap, 8in, dia, × 16in.

THE CAUSEWAY, EGHAM SURREY

EQHAM 4166-7

SNOW Horizontal Spindle Surface Grinder, hydraulic. Motor drive 400/440 volts, 3 phase, 50 cycles. Table working surface 24in. by 8in.

DISKUS Vertical Spindle Surface Grinder, hydraulic. Motor drive 380 volts, 3 phase, 50 cycles. Table working surface 32in. by 10in. Segmental grinding wheel 14in. diameter.

CHURCHILL Horizontal Spindle Surface Grinder. Motor drive 400 volts, 3 phase, 50 cycles. Table working surface 36in. by 12in

Rosmy.

4/6 Minerva Road, Park Royal, London, N.W.10

Telephone: ELGar 4841/4842

Plant or material wanted or to sell? Men wanted for executive positions? Situations required? Work wanted for a slack department?

Then 'Phone EUSton 8441

advertisements telephoned Wednesday will be inserted the following Wednesday.



PIDGEN BROS. LIMITED

HELMET ROW, OLD STREET, LONDON, E.C.I

Telephone: CLErkenwell 6481

ALL MACHINES MOTORISED FOR 3 PHASE SUPPLY UNLESS OTHERWISE STATED



AUTOS
GREENLEE lin. × 6 spindle.
PETERMAN No. 0.
BORERS (Horizontal)
KEARNS No. 2.
BROACHING AMERICAN model H2, stroke 30in.
CAPSTANS
MURAD \$\frac{1}{2}in.
HERBERT 4, Ball Chuck.
CUTTING-OFF MACHINES
TAYLOR 10in.
DRILLS TAYLON Toin.

PRILLS

NATCO 24 spindle No. 1 M.T.

CORONA Type 15CX 2 spindle.

HERBERT 2 spindle. Type V.H.

DENBIGH 24in. B.G.

HERBERT "C" Power Feed.

CORONA IAX, No. 1 Morse Taper.

LELAND GIFFORD 2-sp., No. 2 M.T.

HERBERT Type B. Single Spindle, §in.

CORONA 6MX Cluster Type.

HERBERT Type H. §in. cap.

CORONA 9FX § Capacity.

BOLEY Multi Spindle.

ENGRAVERS

LIENHARD 3-dimensional. (New.)

HUPFIELD Router. LIENHARD 3-dimensional. (New.)
HUPFIELD Router.
T.T. & H. Type C, C.B. and M.A.
T.T. & H. Multi Etcher.
FILING AND SAWING MACHINES
MIDSAW 22in. Bandsaw.
JONES No. 13 Bandsaw.
RAPIDOR 6in. Hacksaw.
RAPIDOR Filing and Sawing.
FOLDERS

FOLDERS
Sheet Edging, 30in. × 22g.
GEAR CUTTERS GEAR CUTTERS
SAFAG Pinion.
MAXICUT 7in. × 2in. × 6 D.P.
PETERMAN No. I and 2.
GRINDERS (Internal)
NOVA A, with facing head.
CHURCHILL HBY. CHURCHILL HBY. BRYANT 16/38 and 5.
GRINDERS (Surface)
CHURCHILL OSB, 8in. × 30in.
LUMSDEN Vert. 210 XXM.
ABRASIVE No. 34 Vertical Spindle. GRINDERS (Cylindrical)
PRECIMAX MPB, I0in. × 15in.
CHURCHILL 6 × 36in. B.Y.
CHURCHILL PBH 12 × 36in. Univ. CTURCHILL 9 × 36In. B.Y.
CHURCHILL PBH 12 × 36in. Univ.
GRINDERS (Miscellaneous)
BLACK DIAMOND 1/6in.-pin. Drill.
BROWN & SHARPE No. 10 and 13 T. & C.
J. & S. "Perfect Poinc" 0-010in.-pin. Drill.
J. & S. Drill. pin. to pin.
STEDALL WUNDERL Carbide.
ROWLAND 12in. × 2in. Single Wheel.
WICKMAN NIVEN Carbide.
WADKIN Saw Sharpener.
JACKMAN D/E 18in. Disc.
EXCEL Model OS. T. & C.
NEWALL 420 Univ. Threads.
HUNT No. 0 and 1 Tap Regrinders.
HUNT No. 0, 2 and 3 Drill.
CHURCHILL Valve.
ORCUIT Gear. HONER DELAPENA 4-speed.

KEYSEATERS

ASQUITH H.K.O. Horiz. Duplex.
EDGWICK 4in.

EDĞWICK 4in.
ATHES
SPRINGFIELD 7in. × 36in. S.S. & S.C.
BOXFORD 4jin. × 22in. S.S. & S.C.
JONES Watchmakers.
COULTHURST 9jin. × 27in. Prod.
LE BLOND REGAL 10in. S.S. & S.C.
LE BLOND REGAL 17in. × 36in.
SOUTHBEND 13in. S.S. & S.C.
LE BLOND PROJUCTION. LIII. SOUTHBEND 13 in. S.S. & S.C.
LE BLOND Production, 11 in.
RIVETT S.S. & S.C. 4 in. Model 602.
SOUTHBEND 10 in. Toolroom.
MONARCH 10EE × 22 in. S.S. & S.C.
SMALLPIECE SW Multi-tool.
RIVETT 34 in. Plain. Model 715.
WARD, HAGGAS & SMITH 84 in. × 78 in.
RYDERMATIC No. 12 Multi Tool.
BERRY 64 in. × 36 in. S.S. & S.C.
COLCHESTER 6 in. Master.
HENDY 10 in. Swing ool and Gauge.
BERRY 14 in. × 6f.
KISCELLANEOUS MACHINES
LUKE & SPENCER 38 in. × 4 HP Polisher.

LUKE & SPENCER 38in. × 4 HP Po CANNING 54in. × 2 H.P. Polisher. Dust Extractors, Various. 4 HP Polisher. MILLERS (Horizontal)
ADCOCK & SHIPLEY 0, Table 17½in. × 5in.
CINCINNATI 08 Production.
CINCINNATI 1/18 Production.
ROSCHER EICHLER. Table 39in. × 12in
ST. ANDREA Model UFO3, Table 57 × 14.
KENT OWEN 1/8, Production.
HARDINGE Precision. Table 25 × 6½.
WERNER. Table 14 × 5.
JONES 225 Luiv. Table 22 × 6.
ARCHDALE 20in. dia. and 14in. mfg.
RICHMOND 03. Table 40 × 10.
U.S. Multr Mill. Production.
ASQUITH Duplex Keyseater HKO.
SENIOR MZ, Table 24 × 6½.
MILLERS (Vertical)
HERBERT No. OV and No. 10.
BROWN & SHARPE No. 2 Light.
REED PRENTICE No. 5, 68in. × 16in. table.
WADKIN Type LXIA. Table 36in. × 13in.
CINCINNATI Contourmaster Tool and Die.
PRESSES (Power)
BESCO R&20 Adi Str. 28 foos.

CINCINNATI Contourmaster Tool and PRESSES (Power)
BESCO BA20, Adj. Str., 28 tons.
BLISS No. 18. Adj. Str. 8 tons.
LECRA No. 8. 4 tons.
MECO 3 ton capacity.
PROFILING MACHINE
CURDNUBE 2 Spindle. Model KIV.
BIVETERE

CURDNUBE 2 Spindle. Model KIV.
RIVETERS
HIGH SPEED Hammer. 7/16 cap.
TURNER RHIB (\(\frac{1}{2}\)in.), RH34 (\(\frac{1}{2}\)in.), RH3
and 14/12 (\(\frac{1}{2}\)in.).

SCREWING MACHINE
ATLAS No. 2, \(\frac{3}{2}\)in.-6in. (Unused.)

SHEET METAL MACHINES
BESCO 12in. and 6in. Treadle Guillotines.
FROST 6in. \(\times\) \(\frac{1}{2}\)in. Rolls.

SLOTTERS
GSP \(\frac{3}{2}\)in.

DENHAM 6in.
EDGWICK 6\(\frac{1}{2}\)in.

TAPPERS

TAPPERS

ESSEX No. 24, ‡in. cap.
ACE Horiz., ‡in. cap.
J. & S. Electrotap, ‡in.
THREAD MILLERS JONES FBI 23in. × 48in. WICKMAN MOULTON IB.

NEW MACHINE TOOLS FROM STOCK

MITCHELL OF KEIGHLEY Sin. Type
DMS Gap Bed Lathe, by 5ft. Sin. B.C.
400/440/8/50. Instant delivery.
VIOTORIA No. 2 Rapdmil Universal Milling
Machine. Table size 48in. × 11fin.
400-440/8/50. Instant delivery.
VIOTORIA No. V2 Vertical Milling Machine.
Table size 45in. × 11in. 400-440/8/50.
Instant delivery.

CENTAUR TOOL WORKS, EYRE STREET, SPRING HILL, BIRMINGHAM, 18

el. EDGbaston 1118 & 1119. 'Grams Capetan, Birmingha

SPECIAL OFFER MACHINE TOOLS

2 BROWN & SHARPE ISin. × 6in. Surface Grinders. £250 each.

I THIEL Punch Shaper.

I IS HERBERT Capstan Lathe. Bar feed. Draw in Collet complete.

POLLARD 2 Spindle Drill, in. Cap. 685.

PACERA in. Cap. 2 Spindle Drill on Stand. 685. Stand.
All motorised 400/3/50

BOX D.449, MACHINERY Clifton House, Euston Road, N.W.I Corona Heavy Duty Vertical Drilling Machine. No. 5 Morse Taper.

Further details from:—
C. & G. OLDFIELD, Ltd.,
15, Abercorn Street,
PAISLEY

PARKSON INA Universal Milling Machine. Motor drive 400/440 volts, 3 phase, 50 cycles. Prismatic over-arm, rapid traverses. Table 37in. by 104in. rapid traverses. To With dividing head.

Rogery.

4/6 Minerva Road, Park Royal, London, N.W.10

Telephone: ELGar 4841/4842

Warner & Swasey No. 1A Com-bination Turret Lathe, Serial No. 434730. Further details from:—

C. & G. OLDFIELD, LTD., 15, Abercorn Street, PAISLEY. Member of B.A.M.T.M.

Phone EUSton 8441 Extension 27 for small advertisements New 6ft, 0in. × 3ft, 6in.; 7ft, 0in. × 4ft, 0in.; and 10ft, 0in. × 3ft, 0in. Marking 0ff Tables for sale. Accurately machined top face and heavily ribbed. Mounted on cast iron legs. Total height approx. 84in.—Illustrations and full details from F. J. EDWARDS LTD., 359, Euston Rosd, London, N.W.I., or 41, Water Street, Birmingham, 3.

it's ACORN 8881 for Machine Tools

USED MACHINE TOOLS EX STOCK

MINGANTI 20/40 Turret Lathe.

42-1,650 r.p.m. Well equipped. WARD 3A Ball Chuck Bar Feed and Chucking Machines. Very good selection of equipment also available with machines.

HERBERT No. 4 Capstan. Speeds up to 511 r.p.m. Well equipped. up to 511 r.p.m. Well equipped.

BOLEY & LEINEN SR.26 High
Speed Multi Tool Turret Lathe.

lin. Capacity 42/2,400 r.p.m.

LANG 8½in. × 24in. S.S. & S.C.

Lathe. 19-900 r.p.m. Spindle Bore

Lathe. 17-22 2½in. 5 h.p. LANG 10in. × 60in. S.S. & S.C. Lathe. 10-500 r.p.m. Spindle Bore 2½in. 12½ h.p.

5ft. 6in. Speed Range 10-600 r.p.m. Excellent Condition.

MONARCH 7in. × 30in. S.S. & S.C. Lathe 24-1,000 r.p.m.

CINCINNATI 8-18 Tool and Die Milling Machine 185-3,330 r.p.m. equipped with Slotting Attachment.

VICTOMATIC 30in. Production Milling Machine 30-1,100 r.p.m.

VICTORIA U.2 Universal Milling Machine, table 45in. × 11\frac{3}{3}in., 25-900

r.p.m. with Universal Milling Attachment and Dividing Head.

PRATT & WHITNEY 12B Profile

Mill. Twin Spindles, 225-2,880 r.p.m **EDGWICK** Horizontal and Vertical Mill Ilin, × 46in, Table, 24-405 r.p.m. Horizontal, Vertical Milling r.p.m. Horizontal.

attachment 42-680 r.p.m.
CINCINNATI I-18 Production Mill. KENDALL & GENT Vertical Mill, Table 19in, × 69in, Speed

Range 20-300 r.p.m.
INVICTA 5M Shaper. 2lin. Stroke, 6 Speeds. Good Condition.
BUTLER 14in. Slotter. 6 Speeds 4in. to 14in. Stroke, Table Diameter

39in, 124 h.p.

DOWDING V 8 Gear Hobber. Capacity 8in, dia, Maximum Pitch Hobbed in one cut 14 d.p. Hob Traverse 7½in. 6-400 Teeth. Fully equipped.

MATHEY Jig Borer. Table 34in. × 12in. Speeds 80-1,680 r.p.m.

CHURCHILL "HBA" Automatic Internal Grinder. Table Traverse 18in, Maximum Swing over Table 19in. Work Speeds 48-340 r.p.m. CHURCHILL 30in, × 36in, Heavy

Plain Cylindrical Grinding Machine. Capacity 30in, dia, × 36in, between centres.

BROWN & SHARPE No. Universal Grinder. Capacity 8in. dia. 27in. between centres.

EXCEL No. I Pedestal Model Surface Grinder.

PROGRESSIVE LATHE 10in. Centre height. 40in. between centres. Gap Bed. 30in. Dia. Swing. 12 Speeds 17-750 r.p.m. Well equipped.

No. 18 BLANCHARD Vertical Surface Grinder, 36in, Dia, Chuck, Capacity 36in, Dia, × 12in, High, NOYAMATIC Model "A" Hydraulic Automatic Internal Grinder. Capacity 10mm, to 120mm, Dia.

E MACHINERY CO.LTD TORIA ROAD . ACTON LONDON W-3

WARD 2A Capstan Lathe. Motor drive 400/440 volts, 3 phase, 50 cycles. With automatic chuck and bar feed, square turret and back toolpost, certain turret tools, electric suds pump and fittings.

WARD 3A Capstan Lathe, as above.

Rosay.

4/6 Minerva Road, Park Royal, London, N.W.10.

Telephone: ELGar 4841/4842

FOR SALE little used

ZOCCA COMO

Hydraulic Slideway and Surface Grinder

Model R.P.A. 3000

carrying 1 horizontal and 2

vertical spindles

CAPACITY

Table Width ...

Length 10ft. 6in. Traverse longitudinal 7ft. 0in. General

24in

Wheel Head (Nos. 1 & 2) Cross Slide 20in. Wheel Head (Nos. 1 & 2) height 26in.

Machine Tool Dealers and Merchants are requested not to apply.

BOX D437 MACHINERY

Clifton House, Euston Road, N.W.1.

Besco No. 14 Heavy Double Sided Fly Press for sale. Suitable for tool testing. Dia. of screw 3/in. Max. stroke 8in. Bed 32in. \(\) 304in. Hole in bed 23/in. \(\) 174in. Max. daylight bed to ram 304in.—F. J. EDWARDS LIMITED. 358. EUSCHO Road, London, N.W.1, or 41, Water Street, Birmingham 3.

Gordon Try Ltd THE BAMTM

THE BAMIM
SIMMONDS 12in. by 66in. Gap Bed
SOUTHBEND 64in. by 36in. S. Bed
WARD 7 Comb. Turret.
HERBERT 28S Chucker.
HERBERT 28S Chucker.
HERBERT 28S Chucker.
HERBERT 9 Comb. Turret.
SOUTHWARK NO. 2 Capetan.
NERO 4in. Collet Capetan.
PITTLER R. B. 36 Capetan.
PITTLER R. B. 36 Capetan.
AGME 4 Spindle Bar Auto.
F. 6 6. 50 Chuck Auto.
HUCTORIA 10 Chuck Auto.
HUCTORIA 10 Chuck Auto.
HUCTORIA 10 Chuck Alearly new
ARCHDALE 20in. Hort unused.
OLIVETTI FP Plano type.
MILWAUKEE 2K Universal.
RICHMOND O.1 Universal.
RICHMOND O.1 Universal.
RICHMOND Tool & Cutter.
CATOO No. 2 Surface.
J. & S. Tool and Cutter.
GATOO No. 2 Surface.
J. & S. Tool and Cutter.
H. & S. O. 13 Universal
LANDIS 10in. by 30in. Uni.
THE CAUSEWAY, EGHAM, SU £450 £325 £250 £325 £275 £175 £250 £450 £1,150 £1,250 £250 £550 £450 £450 £155 £425 275

THE CAUSEWAY, EGHAM, SURREY Tel: Egham 4166/7

USED MACHINES FOR IMMEDIATE DELIVERY

CHURCHILL 10in. × 24in. Universal Grinding M/c with Internal Spindle. SNOW Hexagon and Square Bar Grinder up to 8in. square cap. with bar feeds.
NORTON 12in. × 36in. Universal Grinding

Machine. CHURCHILL Model HBB Internal Grinder. LANG 18in. swing Surfacing & Boring Lathe. PALLAS Model H.O. Miller. Table 30in. ×

Sin.
CINGINNATI No. 2 Centreless Grinder,
HERBERT No. 1 Hand Milling Machine,
HERBERT No. 1 Hand Milling Machine,
ARGEDALE 18in. Plain Horiz, Miller,
UNIVERSAL Magnetic Chuck with effective
area of 60 in. × 7in.
RIOHARDS No. 3 Horiz, Boring & Facing
Machine

Machine.
MIDSAW 20in. Bandsaw with brazing attach. SKODA 40 Single Spindle Automatic. 1 in.

STIRK 20ft. × 6ft. × 6ft. Open side all

SILKE 201L × 6ft. × 6ft. Open side all electric Planing Machine.

KITCHEN & WADE Column Drill, No. 5
Morse Taper.

WILSON 7im. × 3ft. 6in. Gap Bed S.S. & S.C. Lathe.

MOTCH & MERRYWEATHER 30in. Cold Sawing Machine.

All machines motorised 400/3/50.

ANGLO-AFRICAN MACHINERY CO. LTD.,

EEL ST., OLDBURY, nr. BIRMINGHAM Tel.: BROadwell 2455.

UNREPEATABLE OFFER!!! MODERN LARGE-CAPACITY MACHINES

KENDALL & GENT

20 FT.

LONG TABLE
UNIVERSAL MILL
WITH HYDRAULIC
COPY

CAPACITY: 20ft. by 3ft. 6in. by 2ft. 0in.

36 SPINDLE SPEEDS 7-1000 R.P.M.

16 TABLE FEEDS

RAPID TABLE MOVEMENT

£9,000

WADKIN BRIDGE-TYPE PATTERN MILLER


4-SPEED SWIVELLING CUTTERHEAD 500-3000 R.P.M.

POWER TRAVERSE TO HEAD

TABLE SIZE 60in by 36in.

BOTH ROTARY AND LONGITUDINAL POWER MOVEMENTS.

£3,500



BARKER MACHINE TOOLS & EQUIPMENT LTD.

FAGGS ROAD · FELTHAM · MIDDX. Telephone: FELTHAM 6551

DOUGLAS OF HIGH WYCOMBE

NEW MACHINE TOOLS FOR IMMEDIATE DELIVERY FROM OUR HIGH WYCOMBE SHOWROOMS

DRILLING MACHINES DRILLING MACHINES
RICHMOND SR.2 4ft. Arm Radial.
PROGRESS 3A 1½ in. Pillar Drill.
PACERA A.10 ½ in. Artic. Radial.
IMA A.60S lin. Pillar Drill.
PACERA MF.5 lin. Pillar Drill.
PROGRESS 2.65 ½ in. Pillar Drill.
PROGRESS 2.65 ½ in. Bench Drill.
Range of ½ in. Bench Drill.
Range of ½ in. Bench Drill.
PROGRESS, PACERA, KERRY, UNION,
FOBCO, etc.

BANDSAWS, HACKSAWS AND SHAPERS

SHAPERS
SPEEDAX 16in. Bandsaw.
SPEEDAX 20in. Bandsaw.
SPEEDAX 20in. Bandsaw.
WICKSTEED 6in. Hacksaw.
WICKSTEED 8in. Hydramatic Hacksaw.
WICKSTEED 10in. Hacksaw.
VELOX 6in. Hacksaw.
VELOX 6in. Hacksaw.
QUALTERS & SMITH 6in. Sawmaster

QUALTERS & SMITH Bin. Hacksaw. QUALTERS & SMITH 8 in. Hackst MELBO 6 in. Light Duty Hacksaw. RAPIDOR 6 in. Light Duty Hacksaw. BOXFORD 8 in. Shaper. ALBA 25 4 in. Stroke Shaper. INVICTA 4M 18 in. Stroke Shaper. INVICTA 6M 24 in. Stroke Shaper.

MILLING MACHINES MILLING MACHINES
VICTORIA V.2R Rapidmill Vertical Mill.
VARNAMO FU.2 Universal Mill.
VICTORIA Juniormil Plain Horizontal Mill.
VICTORIA Juniormill Horiz. and Vert. Mill.
CENTEC 2B Horizontal Mill.
RICHMOND Turret Milling Machine with
New Power Down Feed Head.
GIEWONT 2.VR Vertical Mill.

LATHES AND CAPSTANS SMART & BROWN L.16 Capstan.
SMART & BROWN Model "A" Toolroom

Lathe.

SMART & BROWN 1024 Toolroom Lathe.

RAGLAN \(\frac{1}{2}\)in. Cap. Capstan Lathe.

WILLSON \(\frac{1}{2}\)in. Capstan Lathe.

WILLSON \(\frac{1}{2}\)in. Capstan Lathe.

WILLSON \(\frac{1}{2}\)in. Capstan Lathe.

CARDIFF \(\frac{7}{2}\)in. X \(\frac{4}{2}\)in. Major Lathe.

CAROWTHORNE \(\frac{7}{2}\)in. S.S. & S.C. Lathe.

MYFORD Super 78 \(\frac{3}{2}\)in. Lathe.

GRINDING MACHINES RIBON RUR.500 Universal Grinder.
EXCEL No. I Swing Head Grinder.
CLARKSON Tool and Cutter Grinder.
UNION CARBIDE Tool Grinding and

Complete range of Double-Ended Pedestal Tool Grinders and Polishers by MILFORD, VICEROY, UNION, R.J.H., etc., always

In addition to the above machines we have many popular machines for Early Delivery from our Stock Orders.

A. DOUGLAS CO., LTD., LINCOLN ROAD,

BUCKS. Tel.: High Wycombe 4390 (10 lines) BROWN & SHARPE No. 2 Universal Milling Machine. Motor drive 5 h.p. 400/440 volts, 3 phase, 50 cycles. Table 46in. by 10in. 16 Spindle speeds 40-1le of the machine with the speed attachment. slotting attachment, rotary milling table, universal dividing head, tailstock chuck, change gears, and other equipment

Rosmy.

4/6 Minerva Road, Park Royal, London, N.W.10

Telephone: ELGar 4841/4842

Kitchen & Wade G.5 4ft. Girder Radial Drilling Machine in new condition.

3 Speeds and 3 Feeds. Further details from:

C. & G. OLDFIELD, LIMITED, 15, Abercorn Street, PAISLEY.

- Edwards

ROBERTSON Motorised Gang Slitting Machine. Capacity lin. Width of cutters 18in. Dia. of cutter shafts 4in. The machine is complete with a number of cutters 81in. diameter. 2-speed gearbox. Motor drive 400/3/30.

NEW BESCO Model R. High Duty Guillotine, Overcrank type. Capacity 120in. × in. mids steel. Automatic hold-down and gauges. Depth of gap 6in. Motor drive 400-440/3/50.

BENNIE Power Gearde Plate Bending Roller.
Canacity 10ft. * fin. Diameter of top roller
114in. Diameter of bottom rollers 8ln.
Swing out frame for removing completed
cylinders. Forward and reverse motion.
Motor drive 400/3/50.

AS NEW MARSHALTOWN Model 12H. Handwheel Operated Rotary Throatless Shearing Machines on pedestal stand. Cast steel frame. Suitable for cutting straight or irregular shapes in any size sheet up to 12 s.w.g.

BUFFALO FORGE Size \(\frac{1}{2}\) Horizontal Section Rolling Machine. Capacity angles leg out \(2\)in, \(\times 2\)in. \(\frac{1}{2}\)in. \(\times 1\)in. \(\times 1\)in to a dige \(2\)in. \(\frac{1}{2}\)in. Flats on flat \(5\)in. \(\frac{1}{2}\)in. Arranged motor drive \(220-440/3/50\).

Arrangen motor drive 220-440/3/00.

BENNIE Motorised Swing Beam Universal Folding, Rounding and Box Forming Machine. Capacity 12ft. wide x-int. hick mild steel. Lift of top beam 18½in. Beam also swings out to enable complete trunks to be formed. Smallest trunk formed round the beam 18in. square. Max. adjustment of bed 8in. Adjustment of folding beam in side arms 8in. Largest diameter tube formed on mandrel, 16in. Arranged motor drive through gearbox 460-440/3/50. Weight about 14 tons.

RHODES Model 1036 150 tons Motorised Press HODES Model 1036 150 tons Motorised Fress Brake. Forming capacity 10ft. 6in. × ½ in. plate. Width between housings 8ft. 8in. Depth of gap in open ends 10½ in. Stroke 3in. Die space 12½ in. Steel plate bed and top beam. Arranged motor drive 400/3/50. Weight about 16 tons.

Photographs of the above are available.

VERY FAVOURABLE HIRE OR HIRE PURCHASE TERMS CAN BE OBTAINED

MACHINE TOOLS, NEW AND USED, Of Every Description. Attractive Prices.

F. J. EDWARDS LTD.,

359-361, EUSTON RD., LONDON, N.W.1 Telephone: EUSTON 5000. Telex 24264 And at Lansdowne House, 41, Water St., Birmingham, 3. Telephone: Central 7606-8



New for Immediate Delivery CENTEC Model 2B Precision Milling Machine. Power feed to table.

Further details from: C. & G. OLDFIELD, LTD., 15, Abercorn Street PAISLEY.

HIGH QUALITY USED MACHINE TOOLS

EDGWICK No. 2 Horizontal Plain Milling Machine. Table size 46in. × 11in. 400/8/50. HERBERT No. 1 Horizontal Milling Machine

HERBERT No. 1 Horizontal Milling Machine
Table size 26in. × 84in. 400/3/50.

ORMEROD 20in. Stoke Heavy Duty
Shaping Machine. 400/3/50.

TOWN Shaping Machine. Max. stroke
19in. 400/3/50.

CLIFTON & BAIRD 22in./24in. Mechanical
Cold Sawing Machine. Self-contained.
Universal Cylindrical Grinding Machine.
Universal Cylindrical Grinding Machine,
with variable speed workhead and electrics to suit 400/3/50.

HERBERT No. 12 Heavy Duty Combination Turret Lathe. Full chucking equipment. 400/3/50.

TOWN 28in. Vertical Spindle Drilling
Machine. Compound table. 400/3/50.

K. & W. 38in. Sensitive Radial Drilling
Machine. Swing-saide table, swing-saide
arm. 400/3/50.

K. & W. SSIN. Sensitive Radial Drilling
Machine. Swing-saide table, swing-saide
arm. 400/3/50.

S. SHIPMAN 20in. Vertical Drilling

arm. 400/8/50.

JONES & SHIPMAN 26in. Vertical Drilling Machine. No. 4 Morse Taper. Power feed. 400/3/50.

HERBERT No. 6 Horizontal Milling Machine

WE UNDERTAKE REBUILDING OF ALL TYPES OF MACHINE TOOLS

CENTAUR TOOL WORKS. EYRE STREET, SPRING HILL, BIRMINGHAM, 18

Tel. EDGbasto 1118 & 1119

Grams: Capstan, Birmingham

RING BELLS for machine tools

Cincinnati
Horizontal
7in. x 44in.
Further details from:
C. & G. OLDFIELD, Lrd.,
15, Abercorn Street,
PAISLEY.

TWO HERBERT O.V. Vertical Milling Machines, swivel head. Motor drive 400/440 volts, 3 phase, 50 cycles. Table working surface 18in. by 5in. Spindle working surface 18in. b speeds 25 to 2,000 r.p.m.

Rosamy.

4/6 Minerva Road, Park Royal, London, N.W.10

Telephone: ELGar 4841/4842

BUTTERLEY Open Front 100 Ton Press. Adjustable stroke 1in. to 5in. Die

SCHULER Double Sided Geared Press. 230 tons pressure. Sin. stroke. Bed area 24in. × 21‡in. 400/3/50.

JONES & SHIPMAN Model 1300/EIUR Universal 10in. × 27in. Grinding Machine. Rise and fall wheel head. Coolant pump and fittings. 400/3/50, Little used with plenty of equipment.

ABA Type VL600 Jig Boring Machine, fitted Optical measuring device. Table 26in. × 16in. Spindle bored 4 M.T. 12 spindle speeds 31 to 1,400 r.p.m. 400/3/50. Complete with 16in. dia. Optical rotary table. Sine angle plate, Wet boring attachment, boring head, etc., etc. Little used machine.

TAYLOR & CHALLEN Size 4‡ Toggle Drawing Press. Punch stroke 15in. Largest draw 7‡in. Largest blank admitted 18in. dia. Bed area 24in. × 26in. 400/3/50.

TAYLOR & CHALLEN Type 1449 Double Sided Geared Power Press. 150 tons pressure. 10in. stroke. Bed area 32in. × 28in. 400/8/50.

STANCROFT LTD.,

LANCASTER STREET, BIRMINGHAM, 4
ASTon Cross 2235

One Slotting Attachment, 10 mm

Wickman. £20. 2 Slotting attachments with pick up arms, n. B.S.A. £20. 1 Slotting attachment less motor, †in. B.S.A.

615 1 Pick up arm, ‡in. B.S.A. £15. 27 External Caliper Thread Gauges, B.S.P., oventry Gauge & Tool Co., from ‡in. to 1‡in.

Large quantity of 10 mm, Wickman Auto Collets, Steadies, Headstock, Self Adj. 7s, 6d. each.—BOX D447, Machinery, Clifton House, Euston Road, N.W.1.

Ward 3A Capstan Lathes, Bar feed, etc.—A. McNAMARA & CO., LTD., New Line, Bacup, Lancs. 'Phone: Bacup 946.

before we move them! These late type

SHEET METAL & PLATE WORKING MACHINES

still on original foundations are offered at special "ex situ" prices.

BENNY 7-Roll Leveller, cap. 8ft. \times $\frac{1}{2}$ in. Top roll dia. $9\frac{1}{2}$ in. Main Motor 17-h.p. 1951.

CRAIG & DONALD 500-ton Mechanical Press Brake, 11ft., bet. uprights 80in., stroke 4in. Main Motor 50-h.p. 1942.

BENNIE ENNIE Horizontal Beam Straightening and Bending Machine. All steel construction. Cap. 15in. H.P. Motor 15. 1951.

Electrics for all the above are 400/3/50.

Inspection by appointment

Full particulars from:

SOAG MACHINE TOOLS LTD

Juxon Street. Lambeth, London, S.E.II. Tel. RELiance 7201.

FOR "CLASSIFIED" **ADVERTISEMENT** RATES PLEASE SEE PAGE 190. SERIES RATES ON REQUEST.

Churchill-Redman " Cub " S.S. & S.C. Lathes, A.G.H. gap.—A. McNAMARA & CO., Ltd., New Line, Bacup, Lanes. Phone:

Kitchen & Wade 8ft, Girder Radial. M.D. 400/8/50. Cheap for quick sale.—BOX D445, MACHINERY, Clifton House, Euston Road, N.W.1.

Q-Roll Plate Straightening Machine by "Horn & Buire" for sale. Capacity & in. Maximum width admitted 61in. Diameter of rollers 61n. Motor drive: hrough gearbox, with 40 h.p. motor for 400/3/50. Weight presence of rollers oil. Motor cirve: income gearbox, with 40 h.p. motor for 400/3/50. Weight about 10 tons.—F. J. EDWARDS LIMITED, 359, Euston Road, London, N.W.1, or 41; Water Street, Birmingham 3.

Camco Power Horizontal Scrap
Metal Baling Press for sale. For all types
of scrap such as stampings, shearing, tin cass,
etc. Will take 40 to 45 lb. in welght, according
to the material. Size of finished bale about
13th. × 12th. × 10th. Motor drive for 400/3/50.
F. J. EDWARDS LIMITED, 359, Euston Road,
London, N.W.1, or 41, Water Street, Birmingham 3. Camco Power Horizontal Scrap

One Secondhand Scrivener No. 1 Centreless Grinding Machine, maximum capacity 1 in. diameter with Plunge Feed. Hand Operated. Motorised 400-440/3/50.

C. & G. OLDFIELD, LTD., 15, Abercorn Street, PAISLEY.

AUCTIONS

Rv Order of the



SECRETARY

40th Sale.

CENTRAL ORDNANCE DEPOT, BICESTER. OXON.

Important Sale by Auction by

MIDLAND MARTS LIMITED

GOVERNMENT SURPLUS MACHINE TOOLS, GENERATORS AND SPARES, ENGINEERING SPARES, VEHICLE SPARES AND GENERAL STORES, etc.,

including:

menung:

d Ormerod Slotting and Shaping Machines, 12in. stroke, 400v., Collis Stackers, Holman Air Compressor, Murex Arc Welding Plant, Young Leaf Syring Testers, Black & Decker Vaive Seat Grinders, Black & Decker Drills, Reavall Air Compressor, Green Grinding Machines, etc.

Lister Generators, 15 kVA, 230v., O'Keefe Merritt Power Units, 10 kW, 125/250v., Onan Power Units, Pioneer Charking Sets, Briggs & Stratton Spares, Burlee Battery Chargers, Lagonda Generating Sets 4 kW, Lister Spares, American Generating Spares, etc. 210 Caterpillar D.7 and D.8 Tracks and Track Links, Caterpillar Grouser Shoes, 1,100 Batteries 6v., 75.4H, Batteries 24v., etc.
which will be sold in large and small lots to suit all purchasers on

TUESDAY, 19th DECEMBER, 1961, at 10.30 a.m. prompt.

VIEW DAYS: Thursday, Friday and Monday, 14th, 15th and 18th December, and on the morning of the Sale.

CATALOGUES: price 1s., to admit two to view and one on sale day from the Auctioneers, MIDLAND MARTS LIMITED (Dept. 11), Market Square, Bleester, Oxon. (Tel.: 73 and 533)

961

8-

pa-lin. ugh ight ED, ater

pe ith

ap pes ns, ing

out 50.

. 1

R.

an er ls,

8,

k

it

SITUATIONS VACANT

If you do not wish your reply to any Box No. advertisement in this section to be forwarded to certain firms, please advise us. Your reply will then be destroyed, but you will not be notified as this would disclose the identity of the advertiser.

RATE FIXERS

Medium size engineering firm in Portsmouth area setting up Rate Fixing Department require a

CHIEF RATE FIXER

ASSISTANT RATE FIXER

Applicants must possess knowledge of modern bonus schemes and problems relating to their applications to unit and small batch production with the accent on machine shop aspects.

Write with full details to:

BOX D.439, MACHINERY Clifton House, Euston Road, N.W.I

Draughtsmen Required by Our
London tool design office. Should be
experienced single spindle auto layouts and tool
design, but applicants with knowledge capstan
tooling considered. Good ealaries, working
conditions and excellent prospects for suitable
applicants.—Write full details to TAREX
(ENGLAND), LTD., 22, Buckingham Gate,
London, S.W.1.

Senior Draughtsman for interesting work in connection with applications of Air Gauging. Non-Contributory Pension & Insurance scheme in operation.—Apply BOX D400, Machinery, Clifton House, Euston Road, N.W.1.

Sales Engineer required by DOWDING & DOLL, LTD., 346, Kensington High Street, London, W.14. Duties concern correspondence, quotations, production estimates and sales promotion for lathes, including capstans, automatics and production centre lathes. Commensurate previous experience essential. State age, education, apprenticeship, experience, with details of each previous employment.—Reply to Secretary marked "Confidential". Sales required

Highly Paid, Secure and Interesting posts are always available for technically trained men. Find out how you can put some letters after your name by preparing at home on "No Pass—No Fee' terms. A.M.I.Mech.E., A.M.I.Prod.E., A.M.S.E., City and Guilds, etc. Full details of exams, and hundreds of courses in all branches of Engineering, Draughtsmanablip, Management and Automation Techniques, the benefits of our Employment Dept. and unique record of 95 per cent. successes are given in "Engineering Opportunities"—a valuable, 148-page Guide which will reveal many chances you are now missing.—Write for your copy today (staing subject of interest).—FREE and without obligation, B.I.E.T. (Dept. 48a), 29, Wright's Lane, London, W.S. Highly Paid, Secure and Interest-

DIVISIONAL MANAGER

A large internationally known engineering group requires a Manager for one of its Divisions in the north Midlands. A large range of cutting tools and allied equipment is manufactured mainly for the automotive and general engineering industries.

This is an interesting and challenging opportunity with plenty of scope for a man of initiative and drive who can lead a team. No salary bracket has been set, but it is improbable that one who is not already earning more than £1,750 per annum will satisfy the requirements of the post.

Applicants should have a broad engineering and commercial background and be capable of exercising all functions of management. Of particular importance is experience of Production, Budgetary and Cost Control. Responsibilities will also include those for Design and Development, Buying and Commercial Departments, etc.

A recognised qualification in Mechanical Engineering is desirable, and knowledge of the problems of Mechanical Power Transmission will be an advantage. The age group preferred is 35-45 years. Conditions of service, including pension, etc., are excellent. All replies will be treated in strict confidence and should be addressed to:

BOX D.442, MACHINERY Clifton House, Euston Road, N.W.I

SENIOR DESIGN DRAUGHTSMAN

(TOOLING, SPECIAL PURPOSE MACHINERY, MASS PRODUCTION)

An Engineering Company in Cheshire invites applications from Designer Draughtsmen with experience of Tooling and Special Purpose Machinery Design and possibly on Mass Produced Sheet Metal Products. A good commencing salary is offered and there is ample scope for advancement.

Applications indicating age, experience and qualifications and present salary to

BOX D 448, MACHINERY, Clifton House, Euston Road, N.W.1.

Interesting vacancy for

Service Engineer

Machine Tool Company require Engineer available to travel throughout U.K. and often on the Continent. Experience must cover wide range of machines and applicant have excellent personality. applicant has Car provided.

ELGAR MACHINE TOOL CO. LTD. 172-178 Victoria Road Acton, London, W.3

Production Manager Required
for foundry in N.W. London, the essential
requirements being age limit 30-40, an engineering background and ability to plan production,
some knowledge of time and motion study an
advantage. This appointment provides scope
for a man with energy, drive and initiative.
When replying, please give brief details of
education, experience and salary required.
Our own staff have been informed of this advertisement.—BOX D298, MACHINERY, Clifton
House, Euston Road, N.W.1.

Machine Shop Manager (35/45)
required for department containing all types of British and Foreign machine tools and including a fitting section. The machine shop employing about 100 operators is not engaged in production machining but forms part of a precision forging works in the West Riding. Applicants will be expected to have considerable cants will be expected to have considerable pick technical ability. The well as possessing bigh technical ability. The state full particulars of education, previous experience and salary range expected, marking envelope "For the attention of the *Works Manager."—BOX D 451, MACHINERY, Clifton House, Euston Road, N.W.1.

Classified Advertisements (SITUATIONS VACANT, contd.)

CHIEF PLANNER RATE/FIXER Monthly Staff Appointment

Complete charge of Department dealing with a wide variety of Prototype, small and large production in both Aircraft and Commercial Engineering.

Southampton/Portsmouth area.

Write in strictest confidence with fullest details of career and salary required to

BOX D.441, MACHINERY Clifton House, Euston Road, N.W.I

Office Manager Required by Swiss Machine Tool dealers for their London office with Technical background and experience preferably in a machine tools sales office.—Apply in confidence, giving details of age, experience and salary required, to BOX D436, Machinery, Clifton House, Euston Road, N.W.1

Planning Engineer: Experienced Machine Shop Engineer is urgently required by a large Company manufacturing earth moving and road construction machinery. The factory is modern and pleasantly situated in the East Midlan-is. Applicants must apply in own handwriting, giving full details of education and experience, etc. Salary will be in relation to experience.—BOX D438, Machinery, Clifton House, Euston Road, N.W.1.

Advertising Assistant Wanted for machine tool manufacturers. Know-ledge of machinery an advantage. Ability to write intelligently and check proofs essential. Age 28-40. Non-contributory Pension and Insurance Scheme.—Write salary and experience to F. J. EDWARDS LTD., 359, Euston Road, N.W.1.

REPRESENTATIVES

Exceptionally High Commission
rearning terms offered for ambitious
Technical Sales Representative by leading
Importers of Presses and Sheet Metal Working
Machinery. Position only suitable for experienced Salesman with wide connections amongst
machine tool users. Car provided. London and
Southern England Area.

enced Salesman With With an achine tool users. Car provided. Lo Southern England Area.

Apply in strict confidence:

Managing Director,

PEARSON PANKE LIMITED,

1-3, Hale Grove Gardens,

London, N.W.7.

SALES ENGINEER

(Heavy high-quality Machine Tools able to negotiate at all levels required March/April 1962 to cover Birmingham and surrounding Counties. The post, which is not an easy one to fill, offer responsibility with scope for advancement and carries salary according to experience and existing connections, if any. Commission, expenses and car. Please write in first instance to:

BOX D.397, MACHINERY Clifton House, Euston Road, N.W.I Representative for Midlands and North Midlands required by established Hydraulic Engineers. Must have sound engineering background and preferably knowledge of press tools. Write giving details of exerct to date and present salary.—BOX D457, MACHINERY, Clifton House, Euston Road, N.W.1.

Experienced Technical Sales Representative required for the Midlands area by London Company specialising in precision Continental machine tools. Representative will be expected to maintain contact with present users and obtain new customers. Car provided and travelling expenses and commission paid.—With reply please detail previous experience, allary required, business contacts, etc., to BOAD \$48.5. MACHINERY, Clifton House, Easton Rosal, N.W.I.

SITUATIONS WANTED

Senior Executive Wishes to Join small or medium concern in position of trust and responsibility. Considerable experience purchasing in light engineering, general management and administration, etc. Both office and works. Particularly interested in select the develop and expand. Age 40.—BOX. Dec. 10 MACHINERY, Clifton House, Euston Road, N.W.I.

"CLASSIFIED" ADVERTISEMENTS FOR DECEMBER 27th issue:—

First post Friday December 15th

After this date advertisements received Wednesday will be inserted the following Wednesday.

RECEIVED TOO LATE FOR CLASSIFICATION

CONTRACT WORK

Capacity Available in Newly
formed general light engineering unit. fitted
out with new lathes up to 7 in. centres. Drilling
unit may be a man laborication facilities.
Scholmer and some laborication facilities.
Scholmer and laborication facilities.

Press Tools, Simple or Intricate, Jigs, Fixtures, special Machinery, Presswork, short or long runs. Turning, Milling, Cylindrical grinding, etc. A.I.D. approved. Contractors to H.M. Government.—MET PRECISION TOOLS LTD., 149, North Street, Romford, Essex. Tel.: Romford 48425.

AGENCIES

Freelance Engineering Sales
Representative seeks part time commission
based Middleex. Good engineering experience,
knowledge foreign languages. Ideal for firm
going into Common Market.—BOX D444,
MACHINEREY. Clifton House, Euston Road,
N.W.I.

Jig Boring to the Trade. Quick turn round service given on all Jig Boring, also Press Tools, Jigs and Fixtures.—A PTOOLS & CO., LTD., Home Gardens, Dartford, Kent. Dartford 21591.

Whitworth Engineering Co., Ltd. can now accept capacity of up to lin. on one of their Multi-Spindle Autos. Enquiries to 43. London Street, Chertsey. 'Phone: Chertsey 3061.

Press Tools, Stage, Moulds, Diesinking Shaping Milang, Pressings up to 40 tons.—TOOL & PRODUCTION COM-PANY, 40, Spring Lane, S.E.25. Addiscombe

SHOWROOMS

Central London—Southampton Row, W.C.1. Showrooms with basement in new building. Good frontage. Ground floor area about 3,100 sq. ft. Loading bay. Garage. Would divide to let on long lease.—CYRIL LEONARD & CO., 52, Brook Street, London, W.1. MAY, 8771/5.

PLANT WANTED

Collets and Feed Fingers Wanted for Herbert 1½ Bar Auto. Also Short Bed Lathe with minimum 3½ through spindle.— SEALED MOTOR CONSTRUCTION CO., LTD., Britol Road, Bridgwater 4176.

Vertical Head for Cincinnati 2M Hortsontal Miller.—SCOTT ENGINEER-ING (BOURNEMOUTH), L/TD., Stone Lane, Wimborne, Dorset. Wimborne 1173.

Pantograph Engraving Machine. Lienhard 6 head—or similar.—Contact W. Mackie, RONSON PRODUCTS LIMITED, Leatherhead.

MATERIALS FOR SALE

40,000ft. 0.324in. A/F Hex. Brass Bar BSS 249.Excellent Condition, at 1s. 10d. per lb.—BOX D440, MACHINERY, Clifton House, Euston Road, N.W.1.

161

nd ed gilge eer i7, id., eds cive th ar isse, se,


in of riral th in

d

HORNAMILL



THE FULLY
UNIVERSAL
HORNAMILL
EASILY MOUNTED
ON LATHES,
MILLERS
PLANERS AND
SURFACE PLATES



or milling, drilling, boring and grinding

FROM £105

Send for details to-

HORNAMILL MACHINE TOOL CO. LTD.

238 DAWES ROAD . LONDON . S.W.6.

'Phone: FULham 8247

INDEX TO ADVERTISERS

A.	TAXES !
▲ bbey Heat Treatments Ltd.	192
A.B.M.T.M. Ltd	103
Abridge Cam & Tool Co.	196
Abwood Machine Tools Ltd.	12
Acbars Ltd 166 &	205
Acral Ltd.	198
Adcock & Shipley Ltd	34
A.I.D. (Jewels) Ltd.	196
Aircraft Unit Eng'g. Co	194
Ajax Machine Tool Co. Ltd	147
Alfa-Laval Co. Ltd	57
Allen, Edgar & Co. Ltd. Allen & Simmonds (Longham) Ltd.	31
Allen & Simmonds (Longham) Ltd	196
Ambressey Engineering Co. Ltd	198
A.M.T. (Birmingham) Ltd.	198
Anderton Springs Ltd	188
Anglo-African Machinery Co. Ltd.	217
Archdale, James & Co. Ltd	163
Armytage (Tools) Ltd	88
Associated Electrical Industries Ltd.	85
Atkin, W. T. (Tottenham) Ltd.	160
Automation Limited	17
Aylesbury Turned Parts (True Screws) Ltd.	194
Aspesbury Turned Pares (True belows) 12th.	101
	-
Balfour, Arthur & Co. Ltd.	111
Ballinger L. J. H. Ltd.	144
Barker Machine Tools & Equipment Ltd	218
Bayliss Eng'g. Works	193
Baynes, Charles Ltd	
Bedford, James & Co. (Halifax) Ltd.	188
Rell H (Machine Tools) Ltd 202 212 &	
Bell, H. (Machine Tools) Ltd 203, 212 & Benton Engineering Co. Ltd., The	109
D.C. Machiner T.d.	150
B.H.P. Machine Tool Co. Ltd.	156
B.H.P. Machine Tool Co. Ltd.	33
Birmingham Tool & Gauge Co. Ltd	105
Bosch Ltd.	130
Brasshouse, Peter Ltd	224
Brithart Ltd.	1981
British Aero Components Ltd. Inside Back (British Oxygen Co. Ltd	lover & 83

	A 63 67
British Wagon Co. Ltd.	167
Broadbent., Henry Ltd.	76
Brock, L & T. I. & Co. Ltd	168
Brooke Tool Mnfg. Co. Ltd., The	67
Brookman, R. S. Ltd.	143
Brown Bros. (Metals) Ltd.	135
Bryce Ltd.	193
B.S.A. Tools Ltd.	128
Buck & Ryan Ltd	187
Burton, Griffiths & Co. Ltd	123
Butcher, Henry & Co	202
Butterley Co. Ltd., The	169
Differency Co. Lieu., The	100
Manua Dudaluh & Cla TAd	30
Carne, Rudolph & Co. Ltd. Carobronze Ltd. Cashmore, John Ltd.	186
Cochmone Tohn Tad	206
Cashinore, John Ltd	
Castrol Industrial Ltd	128
Centaur Tool Works 212, 216 &	219
Challis, Henry Ltd	158
Christchurch Eng'g. Co. Ltd.	193
Churchill Machine Tool Co. Ltd., The	103
Cinetra Manufacturing Co. Ltd	192
Clarkson (Engineers) Ltd	11
Cohen, Geo. Sons & Co. Ltd	210
Colt Ventilation Ltd	
Cooper & Co. (Birmingham) Ltd	187
Copas, V. J. Ltd	196
Corfield & Buckle Ltd.	166
Cornercroft Ltd	178
Coventry Grinders Ltd.	197
C.P.E. Ltd	193
Craven Bros. (Manchester) Ltd	165
Cross Manufacturing Co. (1988) Ltd	182
Croydon Tool & Case Hardening Specialists	
Ltd.	192
Davis, Stuart Ltd.	15
Denhams Engineering Co. Ltd.	
Denison Deri Ltd.	
Desilux Ltd.	184
Diagrit Diamond Tools Ltd.	151
Dimeo (Gt. Britain) Ltd.	
I PRINCE THE LANGUE AND	-00

P	AGE
Dinsdale Engineering Co. Ltd. Douglas, A. Co. Ltd. Dowling & Doll Ltd. 22, 23, 24, 156 & Dowling, David Ltd. Drummond-Asquith Ltd. Inside Front Cover &	219 176 144
Duplex Electric Tools Ltd	
Eclipse Foundry & Engineering Co. (Dudley) Ltd. Economic Stampings Ltd. Economic Stampings Ltd. Edmonton Tool & Eng'g. Co. Ltd. Edwards, Albert (Machinery) Ltd. Edwards, F. J. Ltd 183, 204, 206 & Elgar Machine Tool Co. Ltd. 80, 81, 117, 180 & Elliott, B. (Machinery) Ltd. E.M.B. Co. Ltd. E.M.B. Co. Ltd. E.M.B. Co. Ltd. Motors Espec Ltd. Eumuco (England) Ltd. Ex-Cell-O Group Sales Ltd. Ex-Cell-O Group Sales Ltd. Ex-Cell-O Group Sales Ltd.	207 207 199 179 170 101
Perris, J. & E. Ltd. escol Ltd. Firth Brown Tools Ltd. Fletcher Miller Ltd. Flexicon Ltd. Forrest, W. & Co. Ltd. Frank, Charles Frost (Rochdale) Ltd. Frye Machine Tool Co. Ltd. 182 &	16

(Continued on page 224)

INDEX TO ADVERTISERS (Continued from page 223)

	10 112 1211 TODITO (CONTINUED)TON	hage zes)
G.A. Precision Products Ltd. 196 Gale, A. E. Ltd. 196 Gate Machinery Co. Ltd. 136, 201 & 217 Gray, R. O. 205, 210, 212, 214, 215, 216, 217, 219 & 220 G.R.M. Heat Treatments Ltd. 193	PAGE	Roth. L. 203 Roto-Finish Ltd. 64 Rozalex Ltd. 178 Rozalex Ltd. 178 Rubert & Co. Ltd. 168 Ryder, Thomas & Son Ltd. 69 Rye, Claude Bearings. 199 & 200
Habit Diamond Tooling Ltd. 51 Hahn & Kolb (Great Britain) Ltd. 112 Hardy & Hanson Ltd. 152 Hargreave, J. M. & Co. Ltd. 196 Harrison, T. S. & Sons Ltd. 44 Hatch, Geo. Ltd. 164 Heald Machines Ltd. 161 Heliot Machine Tools Ltd. 215 Hepworth Iron Co. (Eng.) Ltd., The 10 Herbert, Alfred Ltd. 35, 37, 38, 40, 41, 43, 45, 46, 47, 48, 49 & 50 Herbert, Edward G. Ltd. 160 Hey Engineering Co. Ltd. 185 High Speed Service Tool Co. Ltd. 192 Hollprock Machine Tool Co. Ltd. 42 Holland & Casear Ltd. 160	M.A.S. S. Tools Ltd.	Salter, George & Co. Ltd. 159
\$5, 37, 39, 40, 41, 43, 45, 46, 47, 48, 40 & 50 Herbert, Edward G. Ltd. 160 Hey Engineering Co. Ltd. 185 High Speed Service Tool Co. Ltd. 192 Holbrook Machine Tool Co. Ltd. 192 Holland & Caesar Ltd. 195 Holt Bros. (Halifax) Ltd. 195 Hots Bros. (Halifax) Ltd. 192 Horamaill Machine Tool Co. Ltd., The 23, Horstmann Gear Co. Ltd., The 184 Humphreys, J. H. & Sons Ltd. 187 Humphris & Sons Ltd. 138 Huntic Hepert & Sons Ltd. 138 Huntic Speed Sparks Ltd. 193 Hurlock, Wim. Jnr. Ltd. 206	Marbaix, Gaston E. Ltd.	Salter, George & Co. Ltd. 159
Tdeal Hardening Co. Ltd. 192 Hilich, F. M. (Gears) Ltd. 191 Indusmund (Diamond Tools) Ltd. 155 Industrial & Commercial Finance Corp. Ltd. 189 International Mechanite Metal Co. Ltd., The 192	Naish Bros. & Co. Ltd.	Standard Telephones & Cables Ltd. 170
T.B. Machine Tool Co. Ltd. 200 Ohansson, C. E. Ltd. 175 Jones, A. A. & Shipman Ltd. 94 Jones Bros. (Metal Merchants) Ltd. 201 Jones, E. H. (Machine Tools) Ltd. 200 & 205	Norton, W. E. (Machine Tools) Ltd. 211 O.K. Trading (B'ham Factors) Ltd. 199 dideld & Schofield Co. Ltd. 77 Optical-Mechanical (Instruments) Ltd. 146 & 176 Orniond Mechanical (Instruments) Ltd. 146 & 176 Orniond Eng'g. Co. Ltd., The 149	The following state The following state
Kavanagh O'Moore & Co. Ltd. 118 searney & Trecker-C. V.A. Ltd. 58 Kearns, H. W. & Co. Ltd. 68 Keelavite Hydraulios Ltd. 107 Kenliworth Mufg. Co. Ltd., The 173		Thompson, Michael S. Ltd. 66 & 61 Times Machinery Co. Ltd. 140 & 185 Tradex-Meter Co. Ltd. 191 Try Gordon Ltd. 215 & 217 Turner, G. H. & Co. Ltd. 191
Kenilworth Mnfg. Co. Ltd., The	Darnum Gauges Ltd. 122	Unifinance Ltd. 177 niversal Ball Bearing Co. 199
Kita, Hotif Eus S. Lett 214	Power Petroleum Co. Ltd., The 118 Precision Grinding Ltd. 198 Precision Heating Ltd. 198	Varley, FMC Ltd. 134 aughan Associates Ltd. 161 Vaughan, Edkar & Co. Ltd. 119 Vaughan, F. E. Ltd. 448 Veraloy Products Ltd. 104 Vickers Sperry Rand Ltd. 16 Visual Planning Systems Ltd. 186
Landen (Engineers) Ltd. 190 Jandis Machine-Maiden Ltd. 38 Lang Pneumatic Ltd. 141 Ladjointe Machine Tool Co. Ltd., The 90 Lattimer, E. R. Ltd. 194 Lawrence, A. & Co. (Machine Tools) Ltd. 201 Layton, M. C. Ltd. 201	Press Equipment Ltd	
Layton, M. C. Ltd. 2011 Lee, Arthur & Sons Ltd. 13 Lee & Hunt Ltd. 212 Lenchs (Birmingham) Ltd. 198 Leytoustone Jig & Tool Co. Ltd. 174 Liberty Eng's Bupplies Ltd. 203	Qualters & Smith Bros. Ltd	ward, M. (Machine Tools) Ltd. 201 Ward, Thos. W. Ltd. 204 Wellvil Eng'g, Co. Ltd. 197 Weston Machine Tool Co. Ltd., The 158 Wickman Ltd. 9 Widdowson, Herbert & Sons Ltd.
Layton, M. C. Ltd. 201 Lee, Arthur & Sons Ltd. 13 Lee Arthur & Sons Ltd. 13 Lenche (Birmingham) Ltd. 198 Leytoustone Jig & Tool Co. Ltd. 174 Liberty Eng'g, Supplies Ltd. 203 Lindley, C. & Co. Ltd. 152 Lines, J. H. Ltd. 152 Lines, J. H. Ltd. 9ack Cover Lockheed Precision Products Ltd. 96 London Shafting & Pulley Co. Ltd. 27 Lumaden Machine Co. Ltd. 36 Luria Bros. & Co. Inc. 219	Radyne Ltd.	Ward, H. W. & Co. Ltd. 29 Ward, M. (Machine Tools) Ltd. 201 Ward, Thos, W. Ltd. 204 Wellvil Eng'g, Co. Ltd. 197 Weston Machine Tool Co. Ltd., The 158 Wickman Ltd. 9 Widdowson, Herbert & Sons Ltd. 9 Widdowson, Herbert & Sons Ltd. 72 Wildt, Mellor Bromley Ltd. 72 Wildt, Mellor Bromley Ltd. 72 Windley Bros. Ltd. 122 Winn, W. Martin Ltd. 142 Wire Bands Ltd. 199 W.M. W. Export Deutscher 8
MacDowall Equipment Co. Ltd. 197 achinery Publishing Co. Ltd. The 126, 132 & 218 Machine Shop Equipment Ltd. 127 127 Magnal Products Ltd. 138 138 Manlove, Alliott & Co. Ltd. 154	Rhodes, Joseph & Sons Ltd. 70 & 71 Richards, George & Co. Ltd. 116 Robinson, G. A. (Stoke-on-Trent) Ltd. 207 Robinson, G. A. (Stoke-on-Trent) Ltd. 207	Y orkshire Precision Gauges Ltd 164
Magnal Products Ltd. 128 Manlove, Alliott & Co. Ltd. 154	Rodgers Bros. Ltd. 25 & 26 Rolls Tools Ltd. 191	Zephyr Cams Ltd 195



FOR PRESS TOOLS, JIGS & FIXTURES MOULDS & DIES, SPECIAL MACHINES, MULTI-DRILL HEADS, GAUGES, ETC. CONSULT THE TOOLING SPECIALISTS—

PETER BRASSHOUSE LTD

SPRING HILL . BIRMINGHAM . . 18 . PHONE : EDG 2114-5







61

23815215171

WORLD'S BEST DRILL BUSH


BRITISH AERO COMPONENTS LTD., MONTAGUE ROAD, WARWICK, ENGLAND. Telephone: Warwick 320 Telex 31544 Telegrams: "Aeroparts"

SEND FOR YOUR COPY TODAY

COMMER CARS LTD.

tona select.

serrated blade cutters



We illustrate the simultaneous milling of three faces on synchromesh gearcases at Commer Cars Ltd, Luton, one of many jobs in this factory where GALTONA serrated blade cutters show to advantage. Our Tool Engineers will be happy to co-operate on your own production problems and we invite you to get in touch with us.

RICHARD LLOYD LIMITED

GALTON HOUSE, ELMFIELD AVENUE, TYBURN, BIRMINGHAM. Telephone: Ashfield 1801, Telegrams "Cogs, Birmingham"

, NORTHERN AREA OFFICE: Britannia House Wellington Street, Leeds 1.

Phone: Leeds 21212.
LONDON AREA OFFICE: 240 Romford Road, Forest Gate, London, E.7.
Phone: MARyland 7304-5.
NORTHERN IRELAND: Garage & Engineering Supplies Ltd.,

78 Great Victoria Street, Belfast. SCOTLAND: Stuart & Houston, 5 York Street

ed

HAM,